



United States  
Department of  
Agriculture



Natural  
Resources  
Conservation  
Service



United States  
Department  
of the Interior



National Park  
Service

# Soil Survey of Obed Wild and Scenic River, Tennessee





# How To Use This Soil Survey

---

This publication consists of text, tables, and maps. The text includes descriptions of detailed soil map units and provides an explanation of the information presented in the tables. It also includes a glossary of terms used in the text and tables and a list of references.

The detailed soil maps can be useful in planning the use and management of small areas. To find information about your area of interest, locate that area on the map sheet. Note the map unit symbols that are in that area. Go to the Contents, which lists the map units by symbol and name and shows where each map unit is described.

The Contents shows which table has data on a specific land use for each detailed soil map unit. Also see the Contents for sections of this publication that may address your specific needs.

---

## National Cooperative Soil Survey

This soil survey is a publication of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service has leadership for the Federal part of the National Cooperative Soil Survey. This survey was made cooperatively by the United States Department of Agriculture, Natural Resources Conservation Service, and the United States Department of the Interior, National Park Service.

The soil maps in this survey may be copied without permission. Enlargement of these maps, however, could cause misunderstanding of the detail of mapping. If enlarged, the maps do not show the small areas of contrasting soils that could have been shown at a larger scale.

## Literature Citation

The correct citation for this survey is as follows:

United States Department of Agriculture, Natural Resources Conservation Service, and United States Department of the Interior. 2013. Soil survey of Obed Wild and Scenic River, Tennessee. (Accessible online at: [http://soils.usda.gov/survey/printed\\_surveys/](http://soils.usda.gov/survey/printed_surveys/))

## Cover Caption

Clear Creek, which is a tributary of the Obed River. Large boulders of weathered Cumberland Plateau sandstone create whitewater rapids and rocky soils.

*Additional information about the Nation's natural resources is available online from the Natural Resources Conservation Service at <http://www.nrcs.usda.gov/>.*



## **Nondiscrimination Statement**

### **Nondiscrimination Policy**

The U.S. Department of Agriculture (USDA) prohibits discrimination against its customers, employees, and applicants for employment on the basis of race, color, national origin, age, disability, sex, gender identity, religion, reprisal, and where applicable, political beliefs, marital status, familial or parental status, sexual orientation, whether all or part of an individual's income is derived from any public assistance program, or protected genetic information. The Department prohibits discrimination in employment or in any program or activity conducted or funded by the Department. (Not all prohibited bases apply to all programs and/or employment activities.)

### **To File an Employment Complaint**

If you wish to file an employment complaint, you must contact your agency's EEO Counselor (<http://directives.sc.egov.usda.gov/33081.wba>) within 45 days of the date of the alleged discriminatory act, event, or personnel action. Additional information can be found online at [http://www.ascr.usda.gov/complaint\\_filing\\_file.html](http://www.ascr.usda.gov/complaint_filing_file.html).

### **To File a Program Complaint**

If you wish to file a Civil Rights program complaint of discrimination, complete the USDA Program Discrimination Complaint Form, found online at [http://www.ascr.usda.gov/complaint\\_filing\\_cust.html](http://www.ascr.usda.gov/complaint_filing_cust.html) or at any USDA office, or call (866) 632-9992 to request the form. You may also write a letter containing all of the information requested in the form. Send your completed complaint form or letter by mail to U.S. Department of Agriculture; Director, Office of Adjudication; 1400 Independence Avenue, S.W.; Washington, D.C. 20250-9419; by fax to (202) 690-7442; or by email to [program.intake@usda.gov](mailto:program.intake@usda.gov).

### **Persons with Disabilities**

If you are deaf, are hard of hearing, or have speech disabilities and you wish to file either an EEO or program complaint, please contact USDA through the Federal Relay Service at (800) 877-8339 or (800) 845-6136 (in Spanish).

If you have other disabilities and wish to file a program complaint, please see the contact information above. If you require alternative means of communication for program information (e.g., Braille, large print, audiotape, etc.), please contact USDA's TARGET Center at (202) 720-2600 (voice and TDD).

### **Supplemental Nutrition Assistance Program**

For additional information dealing with Supplemental Nutrition Assistance Program (SNAP) issues, call either the USDA SNAP Hotline Number at (800) 221-5689, which is also in Spanish, or the State Information/Hotline Numbers (<http://directives.sc.egov.usda.gov/33085.wba>).

### **All Other Inquiries**

For information not pertaining to civil rights, please refer to the listing of the USDA Agencies and Offices (<http://directives.sc.egov.usda.gov/33086.wba>).



# Contents

---

<b>How To Use This Soil Survey</b> .....	iii
<b>Preface</b> .....	ix
<b>Introduction</b> .....	1
How This Survey Was Made .....	1
<b>Detailed Soil Map Units</b> .....	3
523861—Ealy-Craigsville complex, 0 to 5 percent slopes, occasionally flooded.....	4
523880—Jefferson-Varilla-Shelocta complex, 20 to 60 percent slopes, very stony...	6
523895—Ramsey-Rock outcrop complex, 20 to 50 percent slopes .....	8
523909—Water .....	10
2439088—Bethesda-Mines pit complex, 10 to 80 percent slopes .....	10
2439089—Gilpin silt loam, 5 to 12 percent slopes .....	11
2439090—Gilpin silt loam, 12 to 20 percent slopes .....	13
2439091—Gilpin-Petros complex, 20 to 35 percent slopes .....	14
2439092—Gilpin-Petros complex, 35 to 80 percent slopes .....	16
2439093—Gilpin-Bouldin-Petros complex, 25 to 80 percent slopes, very stony ....	18
2439098—Lily loam, 5 to 12 percent slopes .....	21
2439099—Lily loam, 12 to 20 percent slopes .....	22
2439100—Lily-Gilpin complex, 5 to 12 percent slopes .....	23
2439101—Lily-Gilpin complex, 12 to 20 percent slopes .....	26
2439102—Lily-Gilpin complex, 20 to 35 percent slopes .....	28
2439103—Lily-Ramsey complex, 5 to 12 percent slopes .....	30
2439104—Lily-Ramsey complex, 12 to 20 percent slopes .....	32
2439105—Lily-Ramsey complex, 20 to 35 percent slopes .....	34
2439107—Lonewood silt loam, 5 to 12 percent slopes .....	36
2439108—Pope-Philo complex, frequently flooded .....	37
2439114—Shelocta silt loam, 5 to 12 percent slopes .....	39
2439115—Shelocta silt loam, 12 to 20 percent slopes .....	41
2439116—Shelocta silt loam, 20 to 35 percent slopes .....	42
2439117—Water .....	43
2439118—Wernock silt loam, 2 to 5 percent slopes .....	44
2439119—Wernock silt loam, 5 to 12 percent slopes .....	45
<b>Use and Management of the Soils</b> .....	47
Interpretive Ratings .....	47
Land Capability Classification .....	48
Prime and Other Important Farmland .....	49
Hydric Soils .....	50
Land Management .....	51
Recreation .....	53
Engineering .....	54
Dwellings and Small Commercial Buildings.....	55
Roads and Streets, Shallow Excavations, and Landscaping.....	55
Sewage Disposal .....	56
Source of Gravel and Sand .....	57

Source of Reclamation Material, Roadfill, and Topsoil.....	58
Ponds and Embankments.....	59
<b>Soil Properties</b> .....	61
Engineering Properties.....	61
Physical Soil Properties .....	62
Erosion Properties.....	63
Total Soil Carbon.....	64
Chemical Soil Properties .....	65
Water Features.....	65
Soil Features .....	66
<b>Formation and Classification of the Soils</b> .....	69
Factors of Soil Formation .....	69
Classification of the Soils .....	77
<b>References</b> .....	81
<b>Glossary</b> .....	83
<b>Tables</b> .....	91
Table 1.—Soil Legend .....	92
Table 2.—Land Capability Classification .....	96
Table 3.—Prime and Other Important Farmland .....	98
Table 4.—Hydric Soils .....	99
Table 5.—Land Management, Part I (Planting) .....	100
Table 5.—Land Management, Part II (Hazard of Erosion and Suitability for Roads) .....	104
Table 5.—Land Management, Part III (Site Preparation) .....	108
Table 5.—Land Management, Part IV (Site Restoration) .....	111
Table 6.—Recreation, Part I (Camp and Picnic Areas) .....	114
Table 6.—Recreation, Part II (Trail Management).....	118
Table 7.—Dwellings and Small Commercial Buildings.....	121
Table 8.—Roads and Streets, Shallow Excavations, and Landscaping.....	125
Table 9.—Sewage Disposal .....	130
Table 10.—Source of Gravel and Sand.....	136
Table 11.—Source of Reclamation Material, Roadfill, and Topsoil.....	140
Table 12.—Ponds and Embankments.....	145
Table 13.—Engineering Properties .....	149
Table 14.—Physical Soil Properties .....	160
Table 15.—Erosion Properties .....	164
Table 16.—Total Soil Carbon.....	168
Table 17.—Chemical Soil Properties.....	171
Table 18.—Water Features .....	175
Table 19.—Soil Features .....	179
Table 20.—Taxonomic Classification of the Soils .....	182

Issued 2013



# Preface

---

This soil survey was developed in conjunction with the National Park Service's Soil Inventory and Monitoring Program and is intended to serve as the official source document for soils occurring within Obed Wild and Scenic River.

This soil survey contains information that affects current and future land use planning in the park. It contains predictions of soil behavior for selected land uses. The survey highlights soil limitations, actions needed to overcome the limitations, and the impact of selected land uses on the environment. It is designed to meet the needs of the National Park Service and its partners to better understand the properties of the soils in the park and the effects of these soil properties on various natural ecological characteristics. This knowledge can help the National Park Service and its partners to understand, protect, and enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. The information in this report is intended to identify soil properties that are used in making various land use or land treatment decisions. Statements made in this report are intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are shallow to bedrock. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

These and many other soil properties that affect land use are described in this soil survey. The location of each map unit is shown on the detailed soil maps. Each soil in the survey area is described, and information on specific uses is given. Help in using this publication and additional information are available at the local office of the Natural Resources Conservation Service or the park office for Obed Wild and Scenic River.



# Soil Survey of Obed Wild and Scenic River, Tennessee

---

United States Department of Agriculture, Natural Resources Conservation Service, and United States Department of the Interior, National Park Service

## How This Survey Was Made

This survey was made in conjunction with the National Park Service's Soil Inventory and Monitoring Program to provide information about the soils and miscellaneous areas within Obed Wild and Scenic River.

The soil survey for Obed Wild and Scenic was extracted from the county-based soil surveys of Cumberland and Morgan Counties, Tennessee. Fieldwork was originally completed in 1998. The Cumberland County part was correlated in November 1998 and the Morgan County part in January 2003. The soil mapping scale was 1:24000.

The soils data for the Cumberland County area was fully certified on January 1, 2003 and that for the Morgan County area on May 15, 2009. Quality assurance was conducted by the USDA-NRCS major land resource area office in Lexington, Kentucky. In some instances, because data was clipped from more than one county-based set of soil maps, some same-named detailed soil map units may have more than one map symbol and their properties may vary.

The information includes a description of the soils and miscellaneous areas and their location and a discussion of their suitability, limitations, and management for specified uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of native plants; and the kinds of bedrock. They dug many holes to study the soil profile, which is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

The soils and miscellaneous areas in the survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

## Soil Survey of Obed Wild and Scenic River, Tennessee

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units).

Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they delineated the boundaries of these bodies on digital imagery and identified each as a specific map unit.



# Detailed Soil Map Units

---

The map units delineated on the detailed soil maps in this survey represent the soils or miscellaneous areas in the park. The map unit descriptions in this section, along with the maps, can be used to determine the suitability and potential of a unit for specific uses. They also can be used to plan the management needed for those uses.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. The contrasting components are mentioned in the map unit descriptions. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives the principal hazards and limitations to be considered in planning for specific uses.

Soils that have profiles that are almost alike make up a *soil series*. All the soils of a series have major horizons that are similar in composition, thickness, and arrangement. The soils of a given series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name

of a soil phase commonly indicates a feature that affects use or management. For example, Gilpin silt loam, 5 to 12 percent slopes, is a phase of the Gilpin series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes. A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Lily-Ramsey complex, 12 to 20 percent slopes, is an example.

This survey includes *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Water is an example.

Table 1 lists each map unit in the park, its major and minor components, and the percentage of each component in the unit. Other tables give properties of the soils and the limitations, capabilities, and potentials for many uses. The Glossary defines many of the terms used in describing the soils or miscellaneous areas.

## **523861—Ealy-Craigsville complex, 0 to 5 percent slopes, occasionally flooded**

### **Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 1,000 to 3,995 feet

*Mean annual precipitation:* 35 to 60 inches

*Mean annual air temperature:* 50 to 57 degrees F

*Frost-free period:* 150 to 200 days

### **Map Unit Composition**

Ealy and similar soils: 60 percent

Craigsville and similar soils: 30 percent

Dissimilar minor components: 10 percent

### **Description of Ealy Soil**

#### **Taxonomic Classification**

Coarse-loamy, siliceous, mesic Fluventic Dystrochrepts

#### **Setting**

*Landscape:* Plateaus

*Landform:* Flood plains

*Landform position (three-dimensional):* Tread

*Slope range:* 0 to 3 percent

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

#### **Properties and Qualities**

*Parent material:* Loamy alluvium derived from sandstone

*Restrictive feature(s):* None within a depth of 60 inches

*Frequency of flooding:* Occasional

*Frequency of ponding:* None

*Depth to water table:* About 60 to 72 inches (see table 18)

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

## Soil Survey of Obed Wild and Scenic River, Tennessee

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* High (about 9.1 inches)

### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 2w

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B

### **Vegetation**

*Existing plants:* Eastern redbud, huckleberry, curlytop knotweed, rhododendron, blackberry, greenbrier, and flowering dogwood

### **Typical Profile**

0 to 10 inches; fine sandy loam

10 to 60 inches; fine sandy loam

## **Description of Craigsville Soil**

### **Taxonomic Classification**

Loamy-skeletal, mixed, mesic Fluventic Dystrochrepts

### **Setting**

*Landscape:* Plateaus

*Landform:* Flood plains

*Landform position (three-dimensional):* Tread

*Slope range:* 0 to 5 percent

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

### **Properties and Qualities**

*Parent material:* Cobbly alluvium derived from quartzite

*Restrictive feature(s):* None within a depth of 60 inches

*Frequency of flooding:* Rare

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Low (about 5.0 inches)

### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 2w

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B

### **Vegetation**

*Existing plants:* Flowering dogwood, mountain laurel, coralberry, northern red oak, white oak, eastern white pine, shortleaf pine, and yellow-poplar

### **Typical Profile**

0 to 3 inches; cobbly fine sandy loam

3 to 21 inches; very cobbly sandy loam

21 to 60 inches; extremely cobbly loamy sand

### Minor Components

#### Unnamed components

*Percent of map unit:* 10 percent

*Representative aspect:* North

*Aspect range:* All aspects

*Meets hydric soil criteria:* No

### 523880—Jefferson-Varilla-Shelocta complex, 20 to 60 percent slopes, very stony

#### Map Unit Setting

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 550 to 3,500 feet

*Mean annual precipitation:* 42 to 54 inches

*Mean annual air temperature:* 48 to 59 degrees F

*Frost-free period:* 169 to 185 days

#### Map Unit Composition

Jefferson and similar soils: 50 percent

Varilla and similar soils: 20 percent

Shelocta and similar soils: 15 percent

Dissimilar minor components: 15 percent

#### Description of Jefferson Soil

##### Taxonomic Classification

Fine-loamy, siliceous, mesic Typic Hapludults

##### Setting

*Landscape:* Plateaus

*Landform:* Hillslopes

*Landform position (three-dimensional):* Side slope

*Slope range:* 20 to 60 percent

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

##### Properties and Qualities

*Parent material:* Loamy colluvium derived from interbedded sedimentary rock

*Restrictive feature(s):* None within a depth of 60 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Moderate (about 7.7 inches)

##### Interpretive Groups

*Land capability subclass (nonirrigated):* 7s

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B



**Vegetation**

*Existing plants:* Flowering dogwood, mountain laurel, yellow-poplar, white oak, chestnut oak, greenbrier, hickory, pignut hickory, red maple, grape, eastern poison ivy, and sassafras

**Typical Profile**

0 to 7 inches; cobbly loam  
7 to 56 inches; cobbly loam  
56 to 60 inches; very gravelly sandy loam

**Description of Varilla Soil**

**Taxonomic Classification**

Loamy-skeletal, siliceous, mesic Typic Dystrochrepts

**Setting**

*Landscape:* Plateaus  
*Landform:* Hillslopes  
*Landform position (three-dimensional):* Side slope  
*Slope range:* 20 to 60 percent  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

**Properties and Qualities**

*Parent material:* Cobbly or stony colluvium derived from sandstone  
*Restrictive feature(s):* None within a depth of 60 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Somewhat excessively drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Low (about 4.3 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 7s  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* B

**Typical Profile**

0 to 7 inches; very cobbly sandy loam  
7 to 44 inches; very cobbly sandy loam  
44 to 60 inches; very cobbly sandy loam

**Description of Shelocta Soil**

**Taxonomic Classification**

Fine-loamy, mixed, active, mesic Typic Hapludults

**Setting**

*Landscape:* Plateaus  
*Landform:* Hillslopes  
*Landform position (three-dimensional):* Side slope  
*Slope range:* 20 to 60 percent  
*Representative aspect:* North

## Soil Survey of Obed Wild and Scenic River, Tennessee

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

### **Properties and Qualities**

*Parent material:* Loamy colluvium derived from sandstone and shale

*Restrictive feature(s):* Paralithic bedrock at a depth of 48 to 71 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Moderate (about 7.6 inches)

### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 7s

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B

### **Vegetation**

*Existing plants:* Red maple, hickory, flowering dogwood, northern spicebush, greenbrier, eastern poison ivy, American beech, trillium, Christmas fern, Virginia creeper, and wild hydrangea

### **Typical Profile**

0 to 3 inches; loam

3 to 50 inches; silty clay loam

50 to 60 inches; weathered bedrock

### **Minor Components**

#### **Unnamed components**

*Percent of map unit:* 15 percent

*Representative aspect:* North

*Aspect range:* All aspects

*Meets hydric soil criteria:* No

## **523895—Ramsey-Rock outcrop complex, 20 to 50 percent slopes**

### **Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 645 to 3,995 feet

*Mean annual precipitation:* 8 to 55 inches

*Mean annual air temperature:* 45 to 61 degrees F

*Frost-free period:* 110 to 205 days

### **Map Unit Composition**

Ramsey and similar soils: 70 percent

Rock outcrop: 20 percent

Dissimilar minor components: 10 percent

### **Description of Ramsey Soil**

#### **Taxonomic Classification**

Loamy, siliceous, subactive, mesic Lithic Dystrudepts

#### **Setting**

*Landscape:* Plateaus

*Landform:* Hillslopes

*Landform position (three-dimensional):* Side slope

*Slope range:* 20 to 50 percent

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

#### **Properties and Qualities**

*Parent material:* Loamy residuum weathered from sandstone

*Restrictive feature(s):* Lithic bedrock at a depth of 7 to 20 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Somewhat excessively drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Very low (about 2.0 inches)

#### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 7s

*Meets hydric soil criteria:* No

*Hydrologic soil group:* D

#### **Vegetation**

*Existing plants:* Huckleberry, mountain laurel, blackberry, greenbrier, eastern poison ivy, grape, and sourwood

#### **Typical Profile**

0 to 2 inches; loam

2 to 18 inches; loam

18 to 25 inches; unweathered bedrock

### **Description of Rock Outcrop**

#### **Setting**

*Landscape:* Plateaus

*Landform:* Hillslopes

*Slope range:* 20 to 50 percent

*Representative aspect:* North

*Aspect range:* All aspects

#### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 8

*Meets hydric soil criteria:* No

*Hydrologic soil group:* D

#### **Typical Profile**

0 to 60 inches; unweathered bedrock

### Minor Components

#### Unnamed components

*Percent of map unit:* 10 percent

*Representative aspect:* North

*Aspect range:* All aspects

*Meets hydric soil criteria:* No

### 523909—Water

#### Map Unit Setting

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

#### Map Unit Composition

Water: 100 percent

### 2439088—Bethesda-Mines pit complex, 10 to 80 percent slopes

#### Map Unit Setting

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 187 days

#### Map Unit Composition

Bethesda, unstable fill and similar soils: 75 percent

Mines pit: 20 percent

Dissimilar minor components: 5 percent

#### Description of Bethesda Soil, Unstable Fill

#### Taxonomic Classification

Loamy-skeletal, mixed, active, acid, mesic Typic Udorthents

#### Setting

*Landscape:* Mountains

*Landform:* Mountain slopes

*Landform position (three-dimensional):* Mountainflank

*Slope range:* 10 to 80 percent

*Down-slope shape:* Convex and concave

*Across-slope shape:* Linear

*Representative aspect:* North

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

#### Properties and Qualities

*Runoff:* Very high

*Parent material:* Loamy skeletal mine spoil or earthy fill derived from acid shale

*Restrictive feature(s):* None within a depth of 60 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

## Soil Survey of Obed Wild and Scenic River, Tennessee

*Drainage class:* Well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Low (about 4.3 inches)

### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 7e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* C

### **Vegetation**

*Existing plants:* Grape, eastern poison ivy, Ohio buckeye, red maple, white ash, boxelder, Japanese honeysuckle, and black cherry

### **Typical Profile**

0 to 2 inches; channery loam  
2 to 45 inches; very channery loam  
45 to 60 inches; channery loam

### **Description of Mines Pit**

#### **Setting**

*Landform:* Mountain slopes  
*Slope range:* 10 to 80 percent  
*Representative aspect:* North

#### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 7e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* Not populated

### **Minor Components**

#### **Lily soils**

*Percent of map unit:* 2 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

#### **Ramsey soils**

*Percent of map unit:* 2 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

#### **Gilpin soils**

*Percent of map unit:* 1 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

## **2439089—Gilpin silt loam, 5 to 12 percent slopes**

### **Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains  
*Elevation:* 750 to 3,320 feet  
*Mean annual precipitation:* 48 to 61 inches  
*Mean annual air temperature:* 41 to 67 degrees F  
*Frost-free period:* 139 to 187 days

### Map Unit Composition

Gilpin and similar soils: 90 percent  
Dissimilar minor components: 10 percent

### Description of Gilpin Soil

#### Taxonomic Classification

Fine-loamy, mixed, active, mesic Typic Hapludults

#### Setting

*Landscape:* Mountains  
*Landform:* Ridges  
*Landform position (three-dimensional):* Interfluve  
*Slope range:* 5 to 12 percent  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

#### Properties and Qualities

*Runoff:* Medium  
*Parent material:* Fine-loamy residuum weathered from interbedded sedimentary rock  
*Restrictive feature(s):* Paralithic bedrock at a depth of 20 to 40 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Low (about 3.7 inches)

#### Interpretive Groups

*Land capability subclass (nonirrigated):* 3e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* C

#### Vegetation

*Existing plants:* Flowering dogwood, eastern hophornbeam, Virginia creeper, roundleaf greenbrier, eastern poison ivy, mapleleaf viburnum, summer grape, and common pawpaw

#### Typical Profile

0 to 6 inches; silt loam  
6 to 21 inches; silty clay loam  
21 to 25 inches; channery silty clay loam  
25 to 35 inches; weathered bedrock

### Minor Components

#### Lily soils

*Percent of map unit:* 5 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

**Sequoia soils**

*Percent of map unit:* 5 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**2439090—Gilpin silt loam, 12 to 20 percent slopes**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 163 to 214 days

**Map Unit Composition**

Gilpin and similar soils: 90 percent

Dissimilar minor components: 10 percent

**Description of Gilpin Soil**

**Taxonomic Classification**

Fine-loamy, mixed, active, mesic Typic Hapludults

**Setting**

*Landscape:* Mountains

*Landform:* Hillsides or mountainsides

*Landform position (three-dimensional):* Side slope

*Slope range:* 12 to 20 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

**Properties and Qualities**

*Runoff:* Medium

*Parent material:* Fine-loamy residuum weathered from interbedded sedimentary rock

*Restrictive feature(s):* Paralithic bedrock at a depth of 20 to 40 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Low (about 3.7 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 4e

*Meets hydric soil criteria:* No

*Hydrologic soil group:* C

**Vegetation**

*Existing plants:* Roundleaf greenbrier, eastern poison ivy, mapleleaf viburnum, summer grape, common pawpaw, flowering dogwood, eastern hophornbeam, and Virginia creeper

**Typical Profile**

0 to 6 inches; silt loam  
6 to 21 inches; silty clay loam  
21 to 25 inches; channery silty clay loam  
25 to 35 inches; weathered bedrock

**Minor Components**

**Lily soils**

*Percent of map unit:* 5 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

**Sequoia soils**

*Percent of map unit:* 5 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

**2439091—Gilpin-Petros complex, 20 to 35 percent slopes**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains  
*Elevation:* 750 to 3,320 feet  
*Mean annual precipitation:* 48 to 61 inches  
*Mean annual air temperature:* 41 to 67 degrees F  
*Frost-free period:* 163 to 214 days

**Map Unit Composition**

Gilpin and similar soils: 55 percent  
Petros and similar soils: 35 percent  
Dissimilar minor components: 10 percent

**Description of Gilpin Soil**

**Taxonomic Classification**

Fine-loamy, mixed, active, mesic Typic Hapludults

**Setting**

*Landscape:* Mountains  
*Landform:* Hillsides or mountainsides  
*Landform position (three-dimensional):* Side slope  
*Slope range:* 20 to 35 percent  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

**Properties and Qualities**

*Runoff:* High  
*Parent material:* Fine-loamy residuum weathered from interbedded sedimentary rock



## Soil Survey of Obed Wild and Scenic River, Tennessee

*Restrictive feature(s)*: Paralithic bedrock at a depth of 20 to 40 inches

*Frequency of flooding*: None

*Frequency of ponding*: None

*Depth to water table*: More than 72 inches

*Drainage class*: Well drained

*Shrink-swell potential*: Low (about 1.5 LEP)

*Salinity maximum*: Not saline

*Sodicity maximum*: Not sodic

*Calcium carbonate equivalent (maximum weight percentage)*: 0

*Available water capacity*: Low (about 3.7 inches)

### **Interpretive Groups**

*Land capability subclass (nonirrigated)*: 6e

*Meets hydric soil criteria*: No

*Hydrologic soil group*: C

### **Vegetation**

*Existing plants*: Common pawpaw, flowering dogwood, eastern hophornbeam, Virginia creeper, roundleaf greenbrier, eastern poison ivy, mapleleaf viburnum, and summer grape

### **Typical Profile**

0 to 6 inches; silt loam

6 to 21 inches; silty clay loam

21 to 25 inches; channery silty clay loam

25 to 35 inches; weathered bedrock

## **Description of Petros Soil**

### **Taxonomic Classification**

Loamy-skeletal, mixed, semiactive, mesic, shallow Typic Dystrudepts

### **Setting**

*Landscape*: Mountains

*Landform*: Hillsides or mountainsides

*Slope range*: 20 to 35 percent

*Down-slope shape*: Convex

*Across-slope shape*: Convex

*Representative aspect*: North

*Aspect range*: All aspects

*Soil temperature class*: Mesic

*Soil temperature regime*: Mesic

### **Properties and Qualities**

*Runoff*: High

*Parent material*: Loamy skeletal residuum weathered from shale and siltstone

*Restrictive feature(s)*: Paralithic bedrock at a depth of 10 to 20 inches

*Frequency of flooding*: None

*Frequency of ponding*: None

*Depth to water table*: More than 72 inches

*Drainage class*: Excessively drained

*Shrink-swell potential*: Low (about 1.5 LEP)

*Salinity maximum*: Not saline

*Sodicity maximum*: Not sodic

*Calcium carbonate equivalent (maximum weight percentage)*: 0

*Available water capacity*: Very low (about 1.2 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated): 6e*

*Meets hydric soil criteria: No*

*Hydrologic soil group: D*

**Typical Profile**

0 to 2 inches; channery silt loam

2 to 8 inches; very channery silt loam

8 to 16 inches; extremely channery silt loam

16 to 26 inches; weathered bedrock

**Minor Components**

**Sequoia soils**

*Percent of map unit: 5 percent*

*Representative aspect: North*

*Aspect range: All aspects*

*Meets hydric soil criteria: No*

**Lily soils**

*Percent of map unit: 3 percent*

*Representative aspect: North*

*Aspect range: All aspects*

*Meets hydric soil criteria: No*

**Shelocta soils**

*Percent of map unit: 2 percent*

*Representative aspect: North*

*Aspect range: All aspects*

*Meets hydric soil criteria: No*

**2439092—Gilpin-Petros complex, 35 to 80 percent slopes**

**Map Unit Setting**

*Major land resource area (MLRA): 125—Cumberland Plateau and Mountains*

*Elevation: 750 to 3,320 feet*

*Mean annual precipitation: 48 to 61 inches*

*Mean annual air temperature: 41 to 67 degrees F*

*Frost-free period: 163 to 214 days*

**Map Unit Composition**

Gilpin and similar soils: 65 percent

Petros and similar soils: 25 percent

Dissimilar minor components: 10 percent

**Description of Gilpin Soil**

**Taxonomic Classification**

Fine-loamy, mixed, active, mesic Typic Hapludults

**Setting**

*Landscape: Mountains*

*Landform: Hillsides or mountainsides*

*Slope range: 35 to 70 percent*

*Down-slope shape: Convex*

*Across-slope shape: Linear*

*Representative aspect: North*

## Soil Survey of Obed Wild and Scenic River, Tennessee

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

### **Properties and Qualities**

*Runoff:* Very high

*Parent material:* Fine-loamy residuum weathered from interbedded sedimentary rock

*Restrictive feature(s):* Paralithic bedrock at a depth of 20 to 40 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Low (about 3.7 inches)

### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 7s

*Meets hydric soil criteria:* No

*Hydrologic soil group:* C

### **Vegetation**

*Existing plants:* Common pawpaw, flowering dogwood, eastern hophornbeam, Virginia creeper, roundleaf greenbrier, eastern poison ivy, mapleleaf viburnum, and summer grape

### **Typical Profile**

0 to 6 inches; silt loam

6 to 21 inches; silty clay loam

21 to 25 inches; channery silty clay loam

25 to 35 inches; weathered bedrock

## **Description of Petros Soil**

### **Taxonomic Classification**

Loamy-skeletal, mixed, semiactive, mesic, shallow Typic Dystrudepts

### **Setting**

*Landscape:* Mountains

*Landform:* Hillsides or mountainsides

*Landform position (three-dimensional):* Side slope

*Slope range:* 35 to 60 percent

*Down-slope shape:* Convex

*Across-slope shape:* Convex

*Representative aspect:* North

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

### **Properties and Qualities**

*Runoff:* Very high

*Parent material:* Loamy-skeletal residuum weathered from shale and siltstone

*Restrictive feature(s):* Paralithic bedrock at a depth of 10 to 20 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Excessively drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Very low (about 1.2 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 7s  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* D

**Typical Profile**

0 to 2 inches; channery silt loam  
2 to 8 inches; very channery silt loam  
8 to 16 inches; extremely channery silt loam  
16 to 26 inches; weathered bedrock

**Minor Components**

**Bouldin soils**

*Percent of map unit:* 5 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

**Shelocta soils**

*Percent of map unit:* 4 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

**Rock outcrop**

*Percent of map unit:* 1 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

**2439093—Gilpin-Bouldin-Petros complex, 25 to 80 percent slopes, very stony**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains  
*Elevation:* 750 to 3,320 feet  
*Mean annual precipitation:* 48 to 61 inches  
*Mean annual air temperature:* 41 to 67 degrees F  
*Frost-free period:* 163 to 214 days

**Map Unit Composition**

Gilpin and similar soils: 35 percent  
Bouldin and similar soils: 30 percent  
Petros and similar soils: 25 percent  
Dissimilar minor components: 10 percent

**Description of Gilpin Soil**

**Taxonomic Classification**

Fine-loamy, mixed, active, mesic Typic Hapludults

**Setting**

*Landscape:* Mountains  
*Landform:* Mountain slopes

## Soil Survey of Obed Wild and Scenic River, Tennessee

*Landform position (three-dimensional):* Mountainflank

*Slope range:* 25 to 70 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

### **Properties and Qualities**

*Runoff:* Very high

*Parent material:* Fine-loamy residuum weathered from interbedded sedimentary rock

*Restrictive feature(s):* Paralithic bedrock at a depth of 20 to 40 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Low (about 3.7 inches)

### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 7s

*Meets hydric soil criteria:* No

*Hydrologic soil group:* C

### **Vegetation**

*Existing plants:* Common pawpaw, flowering dogwood, eastern hophornbeam, Virginia creeper, roundleaf greenbrier, eastern poison ivy, mapleleaf viburnum, and summer grape

### **Typical Profile**

0 to 6 inches; silt loam

6 to 21 inches; silty clay loam

21 to 25 inches; channery silty clay loam

25 to 35 inches; weathered bedrock

## **Description of Bouldin Soil**

### **Taxonomic Classification**

Loamy-skeletal, siliceous, subactive, mesic Typic Paleudults

### **Setting**

*Landscape:* Mountains

*Landform:* Mountain slopes

*Landform position (three-dimensional):* Mountainflank

*Slope range:* 30 to 75 percent

*Down-slope shape:* Concave

*Across-slope shape:* Concave

*Representative aspect:* North

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

### **Properties and Qualities**

*Runoff:* Very high

*Parent material:* Loamy-skeletal colluvium derived from sandstone and shale

*Restrictive feature(s):* None within a depth of 60 inches

*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Moderate (about 6.4 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 7s  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* B

**Typical Profile**

0 to 2 inches; flaggy loam  
2 to 17 inches; channery loam  
17 to 80 inches; extremely flaggy clay loam

**Description of Petros Soil**

**Taxonomic Classification**

Loamy-skeletal, mixed, semiactive, mesic, shallow Typic Dystrudepts

**Setting**

*Landscape:* Mountains  
*Landform:* Mountain slopes  
*Landform position (three-dimensional):* Mountainflank  
*Slope range:* 25 to 60 percent  
*Down-slope shape:* Convex  
*Across-slope shape:* Convex  
*Representative aspect:* North  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

**Properties and Qualities**

*Runoff:* Very high  
*Parent material:* Loamy-skeletal residuum weathered from shale and siltstone  
*Restrictive feature(s):* Paralithic bedrock at a depth of 10 to 20 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Excessively drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Very low (about 1.2 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 7s  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* D

**Typical Profile**

0 to 2 inches; channery silt loam  
2 to 8 inches; very channery silt loam

8 to 16 inches; extremely channery silt loam  
16 to 26 inches; weathered bedrock

#### **Minor Components**

##### **Shelocta soils**

*Percent of map unit:* 5 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

##### **Lily soils**

*Percent of map unit:* 4 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

##### **Rock outcrop**

*Percent of map unit:* 1 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

## **2439098—Lily loam, 5 to 12 percent slopes**

#### **Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains  
*Elevation:* 750 to 3,320 feet  
*Mean annual precipitation:* 48 to 61 inches  
*Mean annual air temperature:* 41 to 67 degrees F  
*Frost-free period:* 139 to 187 days

#### **Map Unit Composition**

Lily and similar soils: 85 percent  
Dissimilar minor components: 15 percent

#### **Description of Lily Soil**

##### **Taxonomic Classification**

Fine-loamy, siliceous, semiactive, mesic Typic Hapludults

##### **Setting**

*Landscape:* Mountains  
*Landform:* Ridges  
*Landform position (three-dimensional):* Interfluve  
*Slope range:* 5 to 12 percent  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

##### **Properties and Qualities**

*Runoff:* Medium  
*Parent material:* Fine-loamy residuum weathered from sandstone  
*Restrictive feature(s):* Lithic bedrock at a depth of 20 to 40 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches

*Drainage class:* Well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Low (about 4.5 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 3e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* B

**Vegetation**

*Existing plants:* Red maple, pignut hickory, flowering dogwood, white ash, eastern hophornbeam, sourwood, mayapple, black cherry, chestnut oak, black oak, sassafras, greenbrier, blueberry, American cranberrybush, and grape

**Typical Profile**

0 to 3 inches; loam  
3 to 30 inches; clay loam  
30 to 37 inches; unweathered bedrock

**Minor Components**

**Gilpin soils**

*Percent of map unit:* 8 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

**Shelocta soils**

*Percent of map unit:* 7 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

**2439099—Lily loam, 12 to 20 percent slopes**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains  
*Elevation:* 750 to 3,320 feet  
*Mean annual precipitation:* 48 to 61 inches  
*Mean annual air temperature:* 41 to 67 degrees F  
*Frost-free period:* 139 to 187 days

**Map Unit Composition**

Lily and similar soils: 85 percent  
Dissimilar minor components: 15 percent

**Description of Lily Soil**

**Taxonomic Classification**

Fine-loamy, siliceous, semiactive, mesic Typic Hapludults

**Setting**

*Landscape:* Mountains  
*Landform:* Ridges  
*Landform position (three-dimensional):* Side slope  
*Slope range:* 12 to 20 percent  
*Down-slope shape:* Convex



*Across-slope shape*: Linear  
*Representative aspect*: North  
*Aspect range*: All aspects  
*Soil temperature class*: Mesic  
*Soil temperature regime*: Mesic

**Properties and Qualities**

*Runoff*: Medium  
*Parent material*: Fine-loamy residuum weathered from sandstone  
*Restrictive feature(s)*: Lithic bedrock at a depth of 20 to 40 inches  
*Frequency of flooding*: None  
*Frequency of ponding*: None  
*Depth to water table*: More than 72 inches  
*Drainage class*: Well drained  
*Shrink-swell potential*: Low (about 1.5 LEP)  
*Salinity maximum*: Not saline  
*Sodicity maximum*: Not sodic  
*Calcium carbonate equivalent (maximum weight percentage)*: 0  
*Available water capacity*: Low (about 4.5 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated)*: 4e  
*Meets hydric soil criteria*: No  
*Hydrologic soil group*: B

**Vegetation**

*Existing plants*: Red maple, pignut hickory, flowering dogwood, white ash, eastern hophornbeam, sourwood, mayapple, black cherry, chestnut oak, black oak, sassafras, greenbrier, blueberry, American cranberrybush, and grape

**Typical Profile**

0 to 3 inches; loam  
3 to 30 inches; clay loam  
30 to 37 inches; unweathered bedrock

**Minor Components**

**Ramsey soils**

*Percent of map unit*: 8 percent  
*Representative aspect*: North  
*Meets hydric soil criteria*: No

**Gilpin soils**

*Percent of map unit*: 6 percent  
*Representative aspect*: North  
*Meets hydric soil criteria*: No

**Rock outcrop**

*Percent of map unit*: 1 percent  
*Representative aspect*: North  
*Meets hydric soil criteria*: No

**2439100—Lily-Gilpin complex, 5 to 12 percent slopes**

**Map Unit Setting**

*Major land resource area (MLRA)*: 125—Cumberland Plateau and Mountains  
*Elevation*: 750 to 3,320 feet

## Soil Survey of Obed Wild and Scenic River, Tennessee

*Mean annual precipitation:* 48 to 61 inches  
*Mean annual air temperature:* 41 to 67 degrees F  
*Frost-free period:* 139 to 187 days

### Map Unit Composition

Lily and similar soils: 65 percent  
Gilpin and similar soils: 30 percent  
Dissimilar minor components: 5 percent

### Description of Lily Soil

#### Taxonomic Classification

Fine-loamy, siliceous, semiactive, mesic Typic Hapludults

#### Setting

*Landscape:* Mountains  
*Landform:* Ridges  
*Landform position (three-dimensional):* Interfluve  
*Slope range:* 5 to 12 percent  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

#### Properties and Qualities

*Runoff:* Medium  
*Parent material:* Fine-loamy residuum weathered from sandstone  
*Restrictive feature(s):* Lithic bedrock at a depth of 20 to 40 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Low (about 4.5 inches)

#### Interpretive Groups

*Land capability subclass (nonirrigated):* 3e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* B

#### Vegetation

*Existing plants:* Red maple, pignut hickory, flowering dogwood, white ash, eastern hophornbeam, sourwood, mayapple, black cherry, chestnut oak, black oak, sassafras, greenbrier, blueberry, American cranberrybush, and grape

#### Typical Profile

0 to 3 inches; loam  
3 to 30 inches; clay loam  
30 to 37 inches; unweathered bedrock

## Description of Gilpin Soil

### Taxonomic Classification

Fine-loamy, mixed, active, mesic Typic Hapludults

### Setting

*Landscape:* Mountains

*Landform:* Ridges

*Landform position (three-dimensional):* Interfluve

*Slope range:* 5 to 12 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

### Properties and Qualities

*Runoff:* Medium

*Parent material:* Fine-loamy residuum weathered from interbedded sedimentary rock

*Restrictive feature(s):* Paralithic bedrock at a depth of 20 to 40 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Low (about 3.7 inches)

### Interpretive Groups

*Land capability subclass (nonirrigated):* 3e

*Meets hydric soil criteria:* No

*Hydrologic soil group:* C

### Vegetation

*Existing plants:* Common pawpaw, flowering dogwood, eastern hophornbeam, Virginia creeper, roundleaf greenbrier, eastern poison ivy, mapleleaf viburnum, and summer grape

### Typical Profile

0 to 6 inches; silt loam

6 to 21 inches; silty clay loam

21 to 25 inches; channery silty clay loam

25 to 35 inches; weathered bedrock

## Minor Components

### Sequoia soils

*Percent of map unit:* 3 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

### Ramsey soils

*Percent of map unit:* 2 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

## 2439101—Lily-Gilpin complex, 12 to 20 percent slopes

### Map Unit Setting

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 187 days

### Map Unit Composition

Lily and similar soils: 60 percent

Gilpin and similar soils: 35 percent

Dissimilar minor components: 5 percent

### Description of Lily Soil

#### Taxonomic Classification

Fine-loamy, siliceous, semiactive, mesic Typic Hapludults

#### Setting

*Landscape:* Mountains

*Landform:* Hillsides or mountainsides

*Landform position (three-dimensional):* Side slope

*Slope range:* 12 to 20 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

#### Properties and Qualities

*Runoff:* Medium

*Parent material:* Fine-loamy residuum weathered from sandstone

*Restrictive feature(s):* Lithic bedrock at a depth of 20 to 40 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Low (about 4.5 inches)

#### Interpretive Groups

*Land capability subclass (nonirrigated):* 4e

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B

#### Vegetation

*Existing plants:* Red maple, pignut hickory, flowering dogwood, white ash, eastern hophornbeam, sourwood, mayapple, black cherry, chestnut oak, black oak, sassafras, greenbrier, blueberry, American cranberrybush, and grape

#### Typical Profile

0 to 3 inches; loam

3 to 30 inches; clay loam  
30 to 37 inches; unweathered bedrock

### **Description of Gilpin Soil**

#### **Taxonomic Classification**

Fine-loamy, mixed, active, mesic Typic Hapludults

#### **Setting**

*Landscape:* Mountains  
*Landform:* Hillsides or mountainsides  
*Landform position (three-dimensional):* Side slope  
*Slope range:* 12 to 20 percent  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

#### **Properties and Qualities**

*Runoff:* Medium  
*Parent material:* Fine-loamy residuum weathered from interbedded sedimentary rock  
*Restrictive feature(s):* Paralithic bedrock at a depth of 20 to 40 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Low (about 3.7 inches)

#### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 4e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* C

#### **Vegetation**

*Existing plants:* Roundleaf greenbrier, eastern poison ivy, mapleleaf viburnum, summer grape, common pawpaw, flowering dogwood, eastern hophornbeam, and Virginia creeper

#### **Typical Profile**

0 to 6 inches; silt loam  
6 to 21 inches; silty clay loam  
21 to 25 inches; channery silty clay loam  
25 to 35 inches; weathered bedrock

### **Minor Components**

#### **Ramsey soils**

*Percent of map unit:* 2 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

#### **Sequoia soils**

*Percent of map unit:* 2 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Petros soils**

*Percent of map unit:* 1 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

## **2439102—Lily-Gilpin complex, 20 to 35 percent slopes**

### **Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 187 days

### **Map Unit Composition**

Lily and similar soils: 55 percent

Gilpin and similar soils: 35 percent

Dissimilar minor components: 10 percent

### **Description of Lily Soil**

#### **Taxonomic Classification**

Fine-loamy, siliceous, semiactive, mesic Typic Hapludults

#### **Setting**

*Landscape:* Mountains

*Landform:* Hillsides or mountainsides

*Landform position (three-dimensional):* Side slope

*Slope range:* 20 to 35 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

#### **Properties and Qualities**

*Runoff:* High

*Parent material:* Fine-loamy residuum weathered from sandstone

*Restrictive feature(s):* Lithic bedrock at a depth of 20 to 40 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Low (about 4.5 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 6e

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B

**Vegetation**

*Existing plants:* Red maple, pignut hickory, flowering dogwood, white ash, eastern hophornbeam, sourwood, mayapple, black cherry, chestnut oak, black oak, sassafras, greenbrier, blueberry, American cranberrybush, and grape

**Typical Profile**

0 to 3 inches; loam

3 to 30 inches; clay loam

30 to 37 inches; unweathered bedrock

**Description of Gilpin Soil**

**Taxonomic Classification**

Fine-loamy, mixed, active, mesic Typic Hapludults

**Setting**

*Landscape:* Mountains

*Landform:* Hillsides or mountainsides

*Landform position (three-dimensional):* Side slope

*Slope range:* 20 to 35 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

**Properties and Qualities**

*Runoff:* High

*Parent material:* Fine-loamy residuum weathered from interbedded sedimentary rock

*Restrictive feature(s):* Paralithic bedrock at a depth of 20 to 40 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Low (about 3.7 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 6e

*Meets hydric soil criteria:* No

*Hydrologic soil group:* C

**Vegetation**

*Existing plants:* Roundleaf greenbrier, eastern poison ivy, mapleleaf viburnum, summer grape, common pawpaw, flowering dogwood, eastern hophornbeam, and Virginia creeper

**Typical Profile**

0 to 6 inches; silt loam

6 to 21 inches; silty clay loam

21 to 25 inches; channery silty clay loam  
25 to 35 inches; weathered bedrock

#### Minor Components

##### **Sequoia soils**

*Percent of map unit:* 5 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

##### **Ramsey soils**

*Percent of map unit:* 3 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

##### **Petros soils**

*Percent of map unit:* 2 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

### **2439103—Lily-Ramsey complex, 5 to 12 percent slopes**

#### Map Unit Setting

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains  
*Elevation:* 750 to 3,320 feet  
*Mean annual precipitation:* 48 to 61 inches  
*Mean annual air temperature:* 41 to 67 degrees F  
*Frost-free period:* 139 to 187 days

#### Map Unit Composition

Lily and similar soils: 60 percent  
Ramsey and similar soils: 30 percent  
Dissimilar minor components: 10 percent

#### Description of Lily Soil

##### **Taxonomic Classification**

Fine-loamy, siliceous, semiactive, mesic Typic Hapludults

##### **Setting**

*Landscape:* Mountains  
*Landform:* Ridges  
*Landform position (three-dimensional):* Interfluvium  
*Slope range:* 5 to 12 percent  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

##### **Properties and Qualities**

*Runoff:* Medium  
*Parent material:* Fine-loamy residuum weathered from sandstone  
*Restrictive feature(s):* Lithic bedrock at a depth of 20 to 40 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None



## Soil Survey of Obed Wild and Scenic River, Tennessee

*Depth to water table:* More than 72 inches  
*Drainage class:* Well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Low (about 4.5 inches)

### Interpretive Groups

*Land capability subclass (nonirrigated):* 6e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* B

### Vegetation

*Existing plants:* Red maple, pignut hickory, flowering dogwood, white ash, eastern hophornbeam, sourwood, mayapple, black cherry, chestnut oak, black oak, sassafras, greenbrier, blueberry, American cranberrybush, and grape

### Typical Profile

0 to 3 inches; loam  
3 to 30 inches; clay loam  
30 to 37 inches; unweathered bedrock

## Description of Ramsey Soil

### Taxonomic Classification

Loamy, siliceous, subactive, mesic Lithic Dystrudepts

### Setting

*Landscape:* Mountains  
*Landform:* Ridges  
*Landform position (three-dimensional):* Interfluve  
*Slope range:* 5 to 12 percent  
*Down-slope shape:* Convex  
*Across-slope shape:* Concave  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

### Properties and Qualities

*Runoff:* Very low  
*Parent material:* Loamy residuum weathered from sandstone  
*Restrictive feature(s):* Lithic bedrock at a depth of 7 to 20 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Somewhat excessively drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Very low (about 1.8 inches)

### Interpretive Groups

*Land capability subclass (nonirrigated):* 6e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* D

**Vegetation**

*Existing plants:* Huckleberry, mountain laurel, sourwood, blackberry, greenbrier, eastern poison ivy, and grape

**Typical Profile**

0 to 4 inches; loam

4 to 10 inches; fine sandy loam

10 to 16 inches; channery sandy loam

16 to 18 inches; unweathered bedrock

**Minor Components**

**Lonewood soils**

*Percent of map unit:* 5 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Wernock soils**

*Percent of map unit:* 5 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**2439104—Lily-Ramsey complex, 12 to 20 percent slopes**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 187 days

**Map Unit Composition**

Lily and similar soils: 55 percent

Ramsey and similar soils: 40 percent

Dissimilar minor components: 5 percent

**Description of Lily Soil**

**Taxonomic Classification**

Fine-loamy, siliceous, semiactive, mesic Typic Hapludults

**Setting**

*Landscape:* Mountains

*Landform:* Hillsides or mountainsides

*Landform position (three-dimensional):* Side slope

*Slope range:* 12 to 20 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

**Properties and Qualities**

*Runoff:* Medium

*Parent material:* Fine-loamy residuum weathered from sandstone

*Restrictive feature(s):* Lithic bedrock at a depth of 20 to 40 inches

## Soil Survey of Obed Wild and Scenic River, Tennessee

*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Low (about 4.5 inches)

### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 6e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* B

### **Vegetation**

*Existing plants:* Red maple, pignut hickory, flowering dogwood, white ash, eastern hophornbeam, sourwood, mayapple, black cherry, chestnut oak, black oak, sassafras, greenbrier, blueberry, American cranberrybush, and grape

### **Typical Profile**

0 to 3 inches; loam  
3 to 30 inches; clay loam  
30 to 37 inches; unweathered bedrock

## **Description of Ramsey Soil**

### **Taxonomic Classification**

Loamy, siliceous, subactive, mesic Lithic Dystrudepts

### **Setting**

*Landscape:* Mountains  
*Landform:* Hillsides or mountainsides  
*Landform position (three-dimensional):* Side slope  
*Slope range:* 12 to 20 percent  
*Down-slope shape:* Convex  
*Across-slope shape:* Concave  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

### **Properties and Qualities**

*Runoff:* Very low  
*Parent material:* Loamy residuum weathered from sandstone  
*Restrictive feature(s):* Lithic bedrock at a depth of 7 to 20 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Somewhat excessively drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Very low (about 1.8 inches)

### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 6e

*Meets hydric soil criteria:* No

*Hydrologic soil group:* D

**Vegetation**

*Existing plants:* Huckleberry, mountain laurel, sourwood, blackberry, greenbrier, eastern poison ivy, and grape

**Typical Profile**

0 to 4 inches; loam

4 to 10 inches; fine sandy loam

10 to 16 inches; channery sandy loam

16 to 18 inches; unweathered bedrock

**Minor Components**

**Lonewood soils**

*Percent of map unit:* 3 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Wernock soils**

*Percent of map unit:* 2 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**2439105—Lily-Ramsey complex, 20 to 35 percent slopes**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 187 days

**Map Unit Composition**

Lily and similar soils: 50 percent

Ramsey and similar soils: 40 percent

Dissimilar minor components: 10 percent

**Description of Lily Soil**

**Taxonomic Classification**

Fine-loamy, siliceous, semiactive, mesic Typic Hapludults

**Setting**

*Landscape:* Mountains

*Landform:* Hillsides or mountainsides

*Landform position (three-dimensional):* Side slope

*Slope range:* 20 to 35 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

**Properties and Qualities**

*Runoff:* High

*Parent material:* Fine-loamy residuum weathered from sandstone  
*Restrictive feature(s):* Lithic bedrock at a depth of 20 to 40 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Low (about 4.5 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 7e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* B

**Vegetation**

*Existing plants:* Red maple, pignut hickory, flowering dogwood, white ash, eastern hophornbeam, sourwood, mayapple, black cherry, chestnut oak, black oak, sassafras, greenbrier, blueberry, American cranberrybush, and grape

**Typical Profile**

0 to 3 inches; loam  
3 to 30 inches; clay loam  
30 to 37 inches; unweathered bedrock

**Description of Ramsey Soil**

**Taxonomic Classification**

Loamy, siliceous, subactive, mesic Lithic Dystrudepts

**Setting**

*Landscape:* Mountains  
*Landform:* Hillsides or mountainsides  
*Landform position (three-dimensional):* Side slope  
*Slope range:* 20 to 35 percent  
*Down-slope shape:* Convex  
*Across-slope shape:* Concave  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

**Properties and Qualities**

*Runoff:* Medium  
*Parent material:* Loamy residuum weathered from sandstone  
*Restrictive feature(s):* Lithic bedrock at a depth of 7 to 20 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Somewhat excessively drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Very low (about 1.8 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated): 7e*

*Meets hydric soil criteria: No*

*Hydrologic soil group: D*

**Vegetation**

*Existing plants:* Huckleberry, mountain laurel, sourwood, blackberry, greenbrier, eastern poison ivy, and grape

**Typical Profile**

0 to 4 inches; loam

4 to 10 inches; fine sandy loam

10 to 16 inches; channery sandy loam

16 to 18 inches; unweathered bedrock

**Minor Components**

**Lonewood soils**

*Percent of map unit:* 5 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Wernock soils**

*Percent of map unit:* 5 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**2439107—Lonewood silt loam, 5 to 12 percent slopes**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 187 days

**Map Unit Composition**

Lonewood and similar soils: 85 percent

Dissimilar minor components: 15 percent

**Description of Lonewood Soil**

**Taxonomic Classification**

Fine-loamy, siliceous, semiactive, mesic Typic Hapludults

**Setting**

*Landscape:* Mountains

*Landform:* Ridges

*Landform position (three-dimensional):* Interfluve

*Slope range:* 5 to 12 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

**Properties and Qualities**

*Runoff:* Medium

*Parent material:* Fine-loamy residuum weathered from sandstone

*Restrictive feature(s):* Paralithic bedrock at a depth of 40 to 72 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* High (about 9.1 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 3e

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B

**Vegetation**

*Existing plants:* Flowering dogwood, honeysuckle, sourwood, sumac, and sassafras

**Typical Profile**

0 to 8 inches; silt loam

8 to 28 inches; silt loam

28 to 55 inches; clay loam

55 to 65 inches; weathered bedrock

**Minor Components**

**Lily soils**

*Percent of map unit:* 7 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Gilpin soils**

*Percent of map unit:* 5 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Wernock soils**

*Percent of map unit:* 3 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**2439108—Pope-Philo complex, frequently flooded**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 214 days

**Map Unit Composition**

Pope and similar soils: 50 percent

Philo and similar soils: 45 percent  
Dissimilar minor components: 5 percent

### **Description of Pope Soil**

#### **Taxonomic Classification**

Coarse-loamy, mixed, active, mesic Fluventic Dystrudepts

#### **Setting**

*Landscape:* Mountains

*Landform:* Flood plains

*Landform position (three-dimensional):* Talf

*Slope range:* 0 to 3 percent

*Down-slope shape:* Linear

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

#### **Properties and Qualities**

*Runoff:* Very low

*Parent material:* Coarse-loamy alluvium derived from sandstone and shale

*Restrictive feature(s):* None within a depth of 60 inches

*Frequency of flooding:* Frequent

*Frequency of ponding:* None

*Depth to water table:* About 60 to 72 inches (see table 18)

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Moderate (about 8.8 inches)

#### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 2w

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B

#### **Vegetation**

*Existing plants:* Red maple, sugar maple, common pawpaw, flowering dogwood,  
American beech, wild hydrangea, northern spicebush, sourwood, Virginia creeper,  
Christmas fern, American basswood, eastern poison ivy, New York fern, wahoo,  
and American hornbeam

#### **Typical Profile**

0 to 8 inches; loam

8 to 43 inches; loam

43 to 60 inches; very gravelly sandy loam

### **Description of Philo Soil**

#### **Taxonomic Classification**

Coarse-loamy, mixed, active, mesic Fluvaquentic Dystrudepts

#### **Setting**

*Landscape:* Mountains

*Landform:* Flood plains

*Landform position (three-dimensional):* Dip



*Slope range:* 0 to 3 percent  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

**Properties and Qualities**

*Runoff:* Very low  
*Parent material:* Coarse-loamy alluvium derived from interbedded sedimentary rock  
*Restrictive feature(s):* None within a depth of 60 inches  
*Frequency of flooding:* Frequent  
*Frequency of ponding:* None  
*Depth to water table:* About 18 to 36 inches (see table 18)  
*Drainage class:* Moderately well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* Moderate (about 7.5 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 2w  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* B

**Vegetation**

*Existing plants:* Red maple, American hornbeam, sedge, white ash, and polystichum

**Typical Profile**

0 to 6 inches; loam  
6 to 36 inches; loam  
36 to 60 inches; gravelly sandy loam

**Minor Components**

**Rowdy soils**

*Percent of map unit:* 3 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

**Atkins soils**

*Percent of map unit:* 2 percent  
*Landform:* Flood plains  
*Representative aspect:* North  
*Slope range:* 0 to 2 percent  
*Meets hydric soil criteria:* Yes

**2439114—Shelocta silt loam, 5 to 12 percent slopes**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains  
*Elevation:* 750 to 3,320 feet  
*Mean annual precipitation:* 48 to 61 inches  
*Mean annual air temperature:* 41 to 67 degrees F  
*Frost-free period:* 139 to 187 days

### Map Unit Composition

Shelocta and similar soils: 90 percent  
Dissimilar minor components: 10 percent

### Description of Shelocta Soil

#### Taxonomic Classification

Fine-loamy, mixed, active, mesic Typic Hapludults

#### Setting

*Landscape:* Mountains  
*Landform:* Hillsides or mountainsides  
*Landform position (three-dimensional):* Head slope  
*Slope range:* 5 to 12 percent  
*Down-slope shape:* Concave  
*Across-slope shape:* Linear  
*Representative aspect:* North  
*Aspect range:* All aspects  
*Soil temperature class:* Mesic  
*Soil temperature regime:* Mesic

#### Properties and Qualities

*Runoff:* Medium  
*Parent material:* Fine-loamy colluvium derived from sandstone and shale  
*Restrictive feature(s):* None within a depth of 60 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Depth to water table:* More than 72 inches  
*Drainage class:* Well drained  
*Shrink-swell potential:* Low (about 1.5 LEP)  
*Salinity maximum:* Not saline  
*Sodicity maximum:* Not sodic  
*Calcium carbonate equivalent (maximum weight percentage):* 0  
*Available water capacity:* High (about 10.1 inches)

#### Interpretive Groups

*Land capability subclass (nonirrigated):* 3e  
*Meets hydric soil criteria:* No  
*Hydrologic soil group:* B

#### Vegetation

*Existing plants:* Red maple, hickory, flowering dogwood, American beech, sourwood, Virginia creeper, Christmas fern, sassafras, greenbrier, eastern poison ivy, blueberry, and ticktrefoil

#### Typical Profile

0 to 10 inches; silt loam  
10 to 65 inches; channery silty clay loam  
65 to 75 inches; weathered bedrock

### Minor Components

#### Gilpin soils

*Percent of map unit:* 6 percent  
*Representative aspect:* North  
*Meets hydric soil criteria:* No

#### Highsplint soils

*Percent of map unit:* 3 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Rock outcrop**

*Percent of map unit:* 1 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

## **2439115—Shelocta silt loam, 12 to 20 percent slopes**

### **Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 187 days

### **Map Unit Composition**

Shelocta and similar soils: 90 percent

Dissimilar minor components: 10 percent

### **Description of Shelocta Soil**

#### **Taxonomic Classification**

Fine-loamy, mixed, active, mesic Typic Hapludults

#### **Setting**

*Landscape:* Mountains

*Landform:* Hillsides or mountainsides

*Landform position (three-dimensional):* Head slope

*Slope range:* 12 to 20 percent

*Down-slope shape:* Concave

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

#### **Properties and Qualities**

*Runoff:* Medium

*Parent material:* Fine-loamy colluvium derived from sandstone and shale

*Restrictive feature(s):* None within a depth of 60 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* High (about 10.1 inches)

#### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 4e

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B

**Vegetation**

*Existing plants:* Red maple, hickory, flowering dogwood, ticktrefoil, American beech, sourwood, Virginia creeper, Christmas fern, sassafras, greenbrier, eastern poison ivy, and blueberry

**Typical Profile**

0 to 10 inches; silt loam

10 to 65 inches; channery silty clay loam

65 to 75 inches; weathered bedrock

**Minor Components**

**Bouldin soils**

*Percent of map unit:* 6 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Gilpin soils**

*Percent of map unit:* 3 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Rock outcrop**

*Percent of map unit:* 1 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**2439116—Shelocta silt loam, 20 to 35 percent slopes**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 187 days

**Map Unit Composition**

Shelocta and similar soils: 90 percent

Dissimilar minor components: 10 percent

**Description of Shelocta Soil**

**Taxonomic Classification**

Fine-loamy, mixed, active, mesic Typic Hapludults

**Setting**

*Landscape:* Mountains

*Landform:* Hillsides or mountainsides

*Landform position (three-dimensional):* Mountain base

*Slope range:* 20 to 35 percent

*Down-slope shape:* Concave

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

**Properties and Qualities**

*Runoff:* High

*Parent material:* Fine-loamy colluvium derived from sandstone and shale

*Restrictive feature(s):* None within a depth of 60 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* High (about 10.1 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated):* 6e

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B

**Vegetation**

*Existing plants:* Red maple, hickory, flowering dogwood, ticktrefoil, American beech, sourwood, Virginia creeper, Christmas fern, sassafras, greenbrier, eastern poison ivy, and blueberry

**Typical Profile**

0 to 10 inches; silt loam

10 to 65 inches; channery silty clay loam

65 to 75 inches; weathered bedrock

**Minor Components**

**Bouldin soils**

*Percent of map unit:* 6 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Gilpin soils**

*Percent of map unit:* 3 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**Rock outcrop**

*Percent of map unit:* 1 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

**2439117—Water**

**Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

**Map Unit Composition**

Water: 100 percent

## **2439118—Wernock silt loam, 2 to 5 percent slopes**

### **Map Unit Setting**

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 187 days

### **Map Unit Composition**

Wernock and similar soils: 90 percent

Dissimilar minor components: 10 percent

### **Description of Wernock Soil**

#### **Taxonomic Classification**

Fine-silty, mixed, semiactive, mesic Typic Hapludults

#### **Setting**

*Landscape:* Mountains

*Landform:* Ridges

*Landform position (three-dimensional):* Interfluve

*Slope range:* 2 to 5 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

#### **Properties and Qualities**

*Runoff:* Low

*Parent material:* Fine-silty residuum weathered from sandstone and siltstone

*Restrictive feature(s):* Paralithic bedrock at a depth of 30 to 40 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Moderate (about 7.1 inches)

#### **Interpretive Groups**

*Land capability subclass (nonirrigated):* 2e

*Meets hydric soil criteria:* No

*Hydrologic soil group:* B

#### **Typical Profile**

0 to 12 inches; silt loam

12 to 27 inches; silty clay loam

27 to 35 inches; silty clay loam

35 to 45 inches; weathered bedrock

### Minor Components

#### Lily soils

*Percent of map unit:* 6 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

#### Lonewood soils

*Percent of map unit:* 4 percent

*Representative aspect:* North

*Meets hydric soil criteria:* No

## 2439119—Wernock silt loam, 5 to 12 percent slopes

### Map Unit Setting

*Major land resource area (MLRA):* 125—Cumberland Plateau and Mountains

*Elevation:* 750 to 3,320 feet

*Mean annual precipitation:* 48 to 61 inches

*Mean annual air temperature:* 41 to 67 degrees F

*Frost-free period:* 139 to 187 days

### Map Unit Composition

Wernock and similar soils: 90 percent

Dissimilar minor components: 10 percent

### Description of Wernock Soil

#### Taxonomic Classification

Fine-silty, mixed, semiactive, mesic Typic Hapludults

#### Setting

*Landscape:* Mountains

*Landform:* Ridges

*Landform position (three-dimensional):* Side slope

*Slope range:* 5 to 12 percent

*Down-slope shape:* Convex

*Across-slope shape:* Linear

*Representative aspect:* North

*Aspect range:* All aspects

*Soil temperature class:* Mesic

*Soil temperature regime:* Mesic

#### Properties and Qualities

*Runoff:* Medium

*Parent material:* Fine-silty residuum weathered from sandstone and siltstone

*Restrictive feature(s):* Paralithic bedrock at a depth of 30 to 40 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Depth to water table:* More than 72 inches

*Drainage class:* Well drained

*Shrink-swell potential:* Low (about 1.5 LEP)

*Salinity maximum:* Not saline

*Sodicity maximum:* Not sodic

*Calcium carbonate equivalent (maximum weight percentage):* 0

*Available water capacity:* Moderate (about 7.1 inches)

**Interpretive Groups**

*Land capability subclass (nonirrigated): 3e*

*Meets hydric soil criteria: No*

*Hydrologic soil group: B*

**Typical Profile**

0 to 12 inches; silt loam

12 to 27 inches; silty clay loam

27 to 35 inches; silty clay loam

35 to 45 inches; weathered bedrock

**Minor Components**

**Lily soils**

*Percent of map unit: 6 percent*

*Representative aspect: North*

*Meets hydric soil criteria: No*

**Lonewood soils**

*Percent of map unit: 4 percent*

*Representative aspect: North*

*Meets hydric soil criteria: No*



# Use and Management of the Soils

---

This soil survey is an inventory and evaluation of the soils in Obed Wild and Scenic River. It can be used to adjust land uses to the limitations and potentials of natural resources and the environment. Also, it can help to prevent soil-related failures in land uses.

In preparing a soil survey, soil scientists, conservationists, engineers, and others collect extensive field data about the nature and behavioral characteristics of the soils. They collect data on erosion, droughtiness, flooding, and other factors that affect various soil uses and management. Field experience and collected data on soil properties and performance are used as a basis in predicting soil behavior.

Information in this section can be used to plan the use and management of soils as sites for buildings, sanitary facilities, highways and other transportation systems, and recreational facilities. It can be used to identify the potentials and limitations of each soil for specific land uses and to help prevent construction failures caused by unfavorable soil properties.

Planners and others using soil survey information can evaluate the effect of specific land uses on productivity and on the environment in all or part of the park. The survey can help planners to maintain or create a land use pattern in harmony with the natural soil.

Contractors can use this survey to locate sources of sand and gravel, roadfill, and topsoil. They can use it to identify areas where bedrock, wetness, or very firm soil layers can cause difficulty in excavation.

Health officials, highway officials, engineers, and others may also find this survey useful. The survey can help them plan the safe disposal of wastes and locate sites for pavements, sidewalks, campgrounds, playgrounds, and trees and shrubs.

## Interpretive Ratings

The interpretive tables in this survey rate the soils in the park for various uses. Many of the tables identify the limitations that affect specified uses and indicate the severity of those limitations. The ratings in these tables are both verbal and numerical.

## Rating Class Terms

Rating classes are expressed in the tables in terms that indicate the extent to which the soils are limited by all of the soil features that affect a specified use or in terms that indicate the suitability of the soils for the use. Thus, the tables may show limitation classes or suitability classes. Terms for the limitation classes are *not limited*, *slightly limited*, *somewhat limited*, and *very limited*. The suitability ratings are expressed as *well suited*, *moderately well suited*, *poorly suited*, and *unsuited* or as *good*, *fair*, and *poor*.

## Numerical Ratings

Numerical ratings in the tables indicate the relative severity of individual limitations. The ratings are shown as decimal fractions ranging from 0.00 to 1.00. They indicate gradations between the point at which a soil feature has the greatest negative impact

on the use and the point at which the soil feature is not a limitation. The limitations appear in order from the most limiting to the least limiting. Thus, if more than one limitation is identified, the most severe limitation is listed first and the least severe one is listed last.

## Land Capability Classification

Land capability classification shows, in a general way, the suitability of soils for most kinds of field crops. Crops that require special management are excluded. The soils are grouped according to their limitations for field crops, the risk of damage if they are used for crops, and the way they respond to management. The criteria used in grouping the soils do not include major and generally expensive landforming that would change slope, depth, or other characteristics of the soils, nor do they include possible but unlikely major reclamation projects. Capability classification is not a substitute for interpretations designed to show suitability and limitations of groups of soils for rangeland, for forestland, or for engineering purposes.

In the capability system, soils are generally grouped at three levels—capability class, subclass, and unit (USDA-SCS, 1961). Only class and subclass are used in this survey.

*Capability classes*, the broadest groups, are designated by the numbers 1 through 8. The numbers indicate progressively greater limitations and narrower choices for practical use. The classes are defined as follows:

Class 1 soils have slight limitations that restrict their use.

Class 2 soils have moderate limitations that restrict the choice of plants or that require moderate conservation practices.

Class 3 soils have severe limitations that restrict the choice of plants or that require special conservation practices, or both.

Class 4 soils have very severe limitations that restrict the choice of plants or that require very careful management, or both.

Class 5 soils are subject to little or no erosion but have other limitations, impractical to remove, that restrict their use mainly to pasture, rangeland, forestland, or wildlife habitat.

Class 6 soils have severe limitations that make them generally unsuitable for cultivation and that restrict their use mainly to pasture, rangeland, forestland, or wildlife habitat.

Class 7 soils have very severe limitations that make them unsuitable for cultivation and that restrict their use mainly to grazing, forestland, or wildlife habitat.

Class 8 soils and miscellaneous areas have limitations that preclude commercial plant production and that restrict their use to recreational purposes, wildlife habitat, watershed, or esthetic purposes.

*Capability subclasses* are soil groups within one class. They are designated by adding a small letter, *e*, *w*, *s*, or *c*, to the class numeral, for example, 2*e*. The letter *e* shows that the main hazard is the risk of erosion unless close-growing plant cover is maintained; *w* shows that water in or on the soil interferes with plant growth or cultivation (in some soils the wetness can be partly corrected by artificial drainage); *s* shows that the soil is limited mainly because it is shallow, droughty, or stony; and *c*, used in only some parts of the United States, shows that the chief limitation is climate that is very cold or very dry.

In class 1 there are no subclasses because the soils of this class have few limitations. Class 5 contains only the subclasses indicated by *w*, *s*, or *c* because the soils in class 5 are subject to little or no erosion. They have other limitations that restrict their use to pasture, rangeland, forestland, wildlife habitat, or recreation.

The capability classification of map units in this park is given in the section “Detailed Soil Map Units” and in table 2.

## Prime and Other Important Farmland

Table 3 lists the map units in the park that are considered important farmlands. Important farmlands consist of prime farmland, unique farmland, and farmland of statewide or local importance. This list does not constitute a recommendation for a particular land use.

In an effort to identify the extent and location of important farmlands, the Natural Resources Conservation Service, in cooperation with other interested Federal, State, and local government organizations, has inventoried land that can be used for the production of the Nation's food supply.

*Prime farmland* is of major importance in meeting the Nation's short- and long-range needs for food and fiber. Because the supply of high-quality farmland is limited, the U.S. Department of Agriculture recognizes that responsible levels of government, as well as individuals, should encourage and facilitate the wise use of our Nation's prime farmland.

Prime farmland, as defined by the U.S. Department of Agriculture, is land that has the best combination of physical and chemical characteristics for producing food, feed, forage, fiber, and oilseed crops and is available for these uses. It could be cultivated land, pastureland, forestland, or other land, but it is not urban or built-up land or water areas. The soil quality, growing season, and moisture supply are those needed for the soil to economically produce sustained high yields of crops when proper management, including water management, and acceptable farming methods are applied. In general, prime farmland has an adequate and dependable supply of moisture from precipitation or irrigation, a favorable temperature and growing season, acceptable acidity or alkalinity, an acceptable salt and sodium content, and few or no rocks. The water supply is dependable and of adequate quality. Prime farmland is permeable to water and air. It is not excessively erodible or saturated with water for long periods, and it either is not frequently flooded during the growing season or is protected from flooding. Slope ranges mainly from 0 to 6 percent. More detailed information about the criteria for prime farmland is available at the local office of the Natural Resources Conservation Service.

For some of the soils identified in the table as prime farmland, measures that overcome a hazard or limitation, such as flooding, wetness, and droughtiness, are needed. Onsite evaluation is needed to determine whether or not the hazard or limitation has been overcome by corrective measures.

A recent trend in land use in some areas has been the loss of some prime farmland to industrial and urban uses. The loss of prime farmland to other uses puts pressure on marginal lands, which generally are more erodible, droughty, and less productive and cannot be easily cultivated.

*Unique farmland* is land other than prime farmland that is used for the production of specific high-value food and fiber crops, such as citrus, tree nuts, olives, cranberries, and other fruits and vegetables. It has the special combination of soil quality, growing season, moisture supply, temperature, humidity, air drainage, elevation, and aspect needed for the soil to economically produce sustainable high yields of these crops when properly managed. The water supply is dependable and of adequate quality. Nearness to markets is an additional consideration. Unique farmland is not based on national criteria. It commonly is in areas where there is a special microclimate, such as the wine country in California.

In some areas, land that does not meet the criteria for prime or unique farmland is considered to be *farmland of statewide importance* for the production of food, feed, fiber, forage, and oilseed crops. The criteria for defining and delineating farmland of statewide importance are determined by the appropriate State agencies. Generally, this land includes areas of soils that nearly meet the requirements for prime farmland and that economically produce high yields of crops when treated and managed according to acceptable farming methods. Some areas may produce as high a yield

as prime farmland if conditions are favorable. Farmland of statewide importance may include tracts of land that have been designated for agriculture by State law.

In some areas that are not identified as having national or statewide importance, land is considered to be *farmland of local importance* for the production of food, feed, fiber, forage, and oilseed crops. This farmland is identified by the appropriate local agencies. Farmland of local importance may include tracts of land that have been designated for agriculture by local ordinance.

## Hydric Soils

Table 4 lists the map unit components that are rated as hydric soils in the park. This list can help in planning land uses; however, onsite investigation is recommended to determine the hydric soils on a specific site (National Research Council, 1995; USDA-NRCS, 2010).

The three essential characteristics of wetlands are hydrophytic vegetation, hydric soils, and wetland hydrology (Cowardin and others, 1979; U.S. Army Corps of Engineers, 1987; National Research Council, 1995; Tiner, 1985). Criteria for all of the characteristics must be met for areas to be identified as wetlands. Undrained hydric soils that have natural vegetation should support a dominant population of ecological wetland plant species. Hydric soils that have been converted to other uses should be capable of being restored to wetlands.

Hydric soils are defined by the National Technical Committee for Hydric Soils (NTCHS) as soils that formed under conditions of saturation, flooding, or ponding long enough during the growing season to develop anaerobic conditions in the upper part (Federal Register, 1994). These soils, under natural conditions, are either saturated or inundated long enough during the growing season to support the growth and reproduction of hydrophytic vegetation.

The NTCHS definition identifies general soil properties that are associated with wetness. In order to determine whether a specific soil is a hydric soil or nonhydric soil, however, more specific information, such as information about the depth and duration of the water table, is needed. Thus, criteria that identify those estimated soil properties unique to hydric soils have been established (Federal Register, 2002). These criteria are used to identify map unit components that normally are associated with wetlands. The criteria used are selected estimated soil properties that are described in "Soil Taxonomy" (Soil Survey Staff, 1999) and "Keys to Soil Taxonomy" (Soil Survey Staff, 2010) and in the "Soil Survey Manual" (Soil Survey Division Staff, 1993).

If soils are wet enough for a long enough period of time to be considered hydric, they should exhibit certain properties that can be easily observed in the field. These visible properties are indicators of hydric soils. The indicators used to make onsite determinations of hydric soils are specified in "Field Indicators of Hydric Soils in the United States" (USDA-NRCS, 2010).

Hydric soils are identified by examining and describing the soil to a depth of about 20 inches. This depth may be greater if determination of an appropriate indicator so requires. It is always recommended that soils be excavated and described to the depth necessary for an understanding of the redoximorphic processes. Then, using the completed soil descriptions, soil scientists can compare the soil features required by each indicator and specify which indicators have been matched with the conditions observed in the soil. The soil can be identified as a hydric soil if at least one of the approved indicators is present.

Map units that are dominantly made up of hydric soils may have small areas, or inclusions, of nonhydric soils in the higher positions on the landform, and map units dominantly made up of nonhydric soils may have inclusions of hydric soils in the lower positions on the landform.

The criteria for hydric soils are represented by codes in the table (for example, 2B3). Definitions for the codes are as follows:

1. All Histels except for Folistels and Histosols except for Folists.
2. Soils in Aquic suborders, great groups, or subgroups, Albolls suborder, Historthels great group, Histoturbels great group, Pachic subgroups, or Cumulic subgroups that:
  - A. are somewhat poorly drained and have a water table at the surface (0.0 feet) during the growing season, or
  - B. are poorly drained or very poorly drained and have either:
    - 1) a water table at the surface (0.0 feet) during the growing season if textures are coarse sand, sand, or fine sand in all layers within a depth of 20 inches, or
    - 2) a water table at a depth of 0.5 foot or less during the growing season if saturated hydraulic conductivity ( $K_{sat}$ ) is equal to or greater than 6.0 in/hr in all layers within a depth of 20 inches, or
    - 3) a water table at a depth of 1.0 foot or less during the growing season if saturated hydraulic conductivity ( $K_{sat}$ ) is less than 6.0 in/hr in any layer within a depth of 20 inches.
3. Soils that are frequently ponded for periods of long or very long duration during the growing season.
4. Soils that are frequently flooded for periods of long or very long duration during the growing season.

## Land Management

In table 5, parts I through IV, interpretive ratings are given for various aspects of land management. The ratings are both verbal and numerical.

Some rating class terms indicate the degree to which the soils are suited to a specified land management practice. *Well suited* indicates that the soil has features that are favorable for the specified practice and has no limitations. Good performance can be expected, and little or no maintenance is needed. *Moderately suited* indicates that the soil has features that are moderately favorable for the specified practice. One or more soil properties are less than desirable, and fair performance can be expected. Some maintenance is needed. *Poorly suited* indicates that the soil has one or more properties that are unfavorable for the specified practice. Overcoming the unfavorable properties requires special design, extra maintenance, and costly alteration. *Unsuited* indicates that the expected performance of the soil is unacceptable for the specified practice or that extreme measures are needed to overcome the undesirable soil properties.

Numerical ratings in the table indicate the severity of individual limitations. The ratings are shown as decimal fractions ranging from 0.01 to 1.00. They indicate gradations between the point at which a soil feature has the greatest negative impact on the specified land management practice (1.00) and the point at which the soil feature is not a limitation (0.00).

Rating class terms for *fire damage* and *seedling mortality* are expressed as low, moderate, and high. Where these terms are used, the numerical ratings indicate gradations between the point at which the potential for fire damage or seedling mortality is highest (1.00) and the point at which the potential is lowest (0.00).

Rating class terms for *hazard of erosion* are expressed as slight, moderate, severe, and very severe. Where these terms are used, the numerical ratings indicate gradations between the point at which the potential for erosion is highest (1.00) and the point at which the potential is lowest (0.00).

The paragraphs that follow indicate the soil properties considered in rating the soils for land management practices.

Ratings in the columns *suitability for hand planting* and *suitability for mechanical planting* are based on slope, depth to a restrictive layer, content of sand, plasticity

index, rock fragments on or below the surface, depth to a water table, and ponding. The soils are described as well suited, moderately suited, poorly suited, or unsuited to these methods of planting. It is assumed that necessary site preparation is completed before seedlings are planted.

Ratings in the column *soil rutting hazard* are based on depth to a water table, rock fragments on or below the surface, the Unified classification, depth to a restrictive layer, and slope. Ruts form as a result of the operation of planting equipment. The hazard is described as slight, moderate, or severe. A rating of *slight* indicates that the soil is subject to little or no rutting, *moderate* indicates that rutting is likely, and *severe* indicates that ruts form readily.

Ratings in the column *hazard of erosion* are based on slope and on soil erodibility factor K. The soil loss is caused by sheet or rill erosion in areas where 50 to 75 percent of the surface has been exposed by different kinds of disturbance. The hazard is described as slight, moderate, severe, or very severe. A rating of *slight* indicates that erosion is unlikely under ordinary climatic conditions; *moderate* indicates that some erosion is likely and that erosion-control measures may be needed; *severe* indicates that erosion is very likely and that erosion-control measures, including revegetation of bare areas, are advised; and *very severe* indicates that significant erosion is expected, loss of soil productivity and off-site damage are likely, and erosion-control measures are costly and generally impractical.

Ratings in the column *hazard of erosion on roads and trails* are based on the soil erodibility factor K, slope, and content of rock fragments. The ratings apply to unsurfaced roads and trails. The hazard is described as slight, moderate, or severe. A rating of *slight* indicates that little or no erosion is likely; *moderate* indicates that some erosion is likely, that the roads or trails may require occasional maintenance, and that simple erosion-control measures are needed; and *severe* indicates that significant erosion is expected, that the roads or trails require frequent maintenance, and that costly erosion-control measures are needed.

Ratings in the column *suitability for roads (natural surface)* are based on slope, rock fragments on the surface, plasticity index, content of sand, the Unified classification, depth to a water table, ponding, flooding, and the hazard of soil slippage. The ratings indicate the suitability for using the natural surface of the soil for roads. The soils are described as well suited, moderately suited, or poorly suited to this use.

Ratings in the column *suitability for mechanical site preparation (deep)* are based on slope, depth to a restrictive layer, rock fragments on or below the surface, depth to a water table, and ponding. The soils are described as well suited, poorly suited, or unsuited to this management activity. The part of the soil from the surface to a depth of about 3 feet is considered in the ratings.

Ratings in the column *suitability for mechanical site preparation (surface)* are based on slope, depth to a restrictive layer, plasticity index, rock fragments on or below the surface, depth to a water table, and ponding. The soils are described as well suited, poorly suited, or unsuited to this management activity. The part of the soil from the surface to a depth of about 1 foot is considered in the ratings.

Ratings in the column *potential for damage to soil by fire* are based on texture of the surface layer, content of rock fragments and organic matter in the surface layer, thickness of the surface layer, and slope. The soils are described as having a low, moderate, or high potential for this kind of damage. The ratings indicate an evaluation of the potential impact of prescribed fires or wildfires that are intense enough to remove the duff layer and consume organic matter in the surface layer.

Ratings in the column *potential for seedling mortality* are based on flooding, ponding, depth to a water table, content of lime, reaction, salinity, available water capacity, soil moisture regime, soil temperature regime, aspect, and slope. The soils are described as having a low, moderate, or high potential for seedling mortality.

## Recreation

The soils of the park are rated in table 6, parts I and II, according to limitations that affect their suitability for recreation. The ratings are both verbal and numerical. Rating class terms indicate the extent to which the soils are limited by all of the soil features that affect the recreational uses. *Not limited* indicates that the soil has features that are very favorable for the specified use. Good performance and very low maintenance can be expected. *Somewhat limited* indicates that the soil has features that are moderately favorable for the specified use. The limitations can be overcome or minimized by special planning, design, or installation. Fair performance and moderate maintenance can be expected. *Very limited* indicates that the soil has one or more features that are unfavorable for the specified use. The limitations generally cannot be overcome without major soil reclamation, special design, or expensive installation procedures. Poor performance and high maintenance can be expected.

Numerical ratings in the table indicate the severity of individual limitations. The ratings are shown as decimal fractions ranging from 0.01 to 1.00. They indicate gradations between the point at which a soil feature has the greatest negative impact on the use (1.00) and the point at which the soil feature is not a limitation (0.00).

The ratings in the table are based on restrictive soil features, such as wetness, slope, and texture of the surface layer. Susceptibility to flooding is considered. Not considered in the ratings, but important in evaluating a site, are the location and accessibility of the area, the size and shape of the area and its scenic quality, vegetation, access to water, potential water impoundment sites, and access to public sewer lines. The capacity of the soil to absorb septic tank effluent and the ability of the soil to support vegetation also are important. Soils that are subject to flooding are limited for recreational uses by the duration and intensity of flooding and the season when flooding occurs. In planning recreational facilities, onsite assessment of the height, duration, intensity, and frequency of flooding is essential.

The information in table 6 can be supplemented by other information in this survey, for example, interpretations for building site development, construction materials, and water management.

*Camp areas* require site preparation, such as shaping and leveling the tent and parking areas, stabilizing roads and intensively used areas, and installing sanitary facilities and utility lines. Camp areas are subject to heavy foot traffic and some vehicular traffic. The ratings are based on the soil properties that affect the ease of developing camp areas and the performance of the areas after development. Slope, stoniness, and depth to bedrock or a cemented pan are the main concerns affecting the development of camp areas. The soil properties that affect the performance of the areas after development are those that influence trafficability and promote the growth of vegetation, especially in heavily used areas. For good trafficability, the surface of camp areas should absorb rainfall readily, remain firm under heavy foot traffic, and not be dusty when dry. The soil properties that influence trafficability are texture of the surface layer, depth to a water table, ponding, flooding, permeability, and large stones. The soil properties that affect the growth of plants are depth to bedrock or a cemented pan, permeability, and toxic substances in the soil.

*Picnic areas* are subject to heavy foot traffic. Most vehicular traffic is confined to access roads and parking areas. The ratings are based on the soil properties that affect the ease of developing picnic areas and that influence trafficability and the growth of vegetation after development. Slope and stoniness are the main concerns affecting the development of picnic areas. For good trafficability, the surface of picnic areas should absorb rainfall readily, remain firm under heavy foot traffic, and not be dusty when dry. The soil properties that influence trafficability are texture of the surface layer, depth to a water table, ponding, flooding, permeability, and large stones. The soil properties that affect the growth of plants are depth to bedrock or a cemented pan, permeability, and toxic substances in the soil.

*Foot traffic and equestrian trails* for hiking and horseback riding should require little or no slope modification through cutting and filling. The ratings are based on the soil properties that affect trafficability and erodibility. These properties are stoniness, depth to a water table, ponding, flooding, slope, and texture of the surface layer.

*Mountain bike and off-road vehicle trails* require little or no site preparation. They are not covered with surfacing material or vegetation. Considerable compaction of the soil material is likely. The ratings are based on the soil properties that influence erodibility, trafficability, dustiness, and the ease of revegetation. These properties are stoniness, depth to a water table, ponding, slope, flooding, and texture of the surface layer.

## Engineering

This section provides information for planning land uses related to urban development and to water management. Soils are rated for various uses, and the most limiting features are identified. Ratings are given for building site development, landscaping, sanitary facilities, construction materials, and water management. The ratings are based on observed performance of the soils and on the estimated data and test data in the "Soil Properties" section.

*Information in this section is intended for land use planning, for evaluating land use alternatives, and for planning site investigations prior to design and construction. The information, however, has limitations. For example, estimates and other data generally apply only to that part of the soil between the surface and a depth of 5 to 7 feet. Because of the map scale, small areas of different soils may be included within the mapped areas of a specific soil.*

*The information is not site specific and does not eliminate the need for onsite investigation of the soils or for testing and analysis by personnel experienced in the design and construction of engineering works.*

Government ordinances and regulations that restrict certain land uses or impose specific design criteria were not considered in preparing the information in this section. Local ordinances and regulations should be considered in planning, in site selection, and in design.

Soil properties, site features, and observed performance were considered in determining the ratings in this section. During the fieldwork for this soil survey, determinations were made about particle-size distribution, liquid limit, plasticity index, soil reaction, depth to bedrock, hardness of bedrock within 5 to 7 feet of the surface, soil wetness, depth to a water table, ponding, slope, likelihood of flooding, natural soil structure aggregation, and soil density. Data were collected about kinds of clay minerals, mineralogy of the sand and silt fractions, and the kinds of adsorbed cations. Estimates were made for erodibility, permeability, corrosivity, shrink-swell potential, available water capacity, and other behavioral characteristics affecting engineering uses.

This information can be used to evaluate the potential of areas for residential, commercial, and recreational uses; make preliminary estimates of construction conditions; evaluate alternative routes for roads, streets, highways, pipelines, and underground cables; evaluate alternative sites for septic tank absorption fields and sewage lagoons; plan detailed onsite investigations of soils and geology; locate potential sources of gravel, sand, earthfill, and topsoil; plan drainage systems, ponds, and other structures for soil and water conservation; and predict performance of proposed small structures and pavements by comparing the performance of existing similar structures on the same or similar soils.

The information in the tables, along with the soil maps, the soil descriptions, and other data provided in this survey, can be used to make additional interpretations.

Some of the terms used in this soil survey have a special meaning in soil science and are defined in the Glossary.



## Dwellings and Small Commercial Buildings

Soil properties influence the development of building sites, including the selection of the site, the design of the structure, construction, performance after construction, and maintenance. Table 7 shows the degree and kind of soil limitations that affect dwellings and small commercial buildings.

The ratings in the table are both verbal and numerical. Rating class terms indicate the extent to which the soils are limited by all of the soil features that affect building site development. *Not limited* indicates that the soil has features that are very favorable for the specified use. Good performance and very low maintenance can be expected. *Somewhat limited* indicates that the soil has features that are moderately favorable for the specified use. The limitations can be overcome or minimized by special planning, design, or installation. Fair performance and moderate maintenance can be expected. *Very limited* indicates that the soil has one or more features that are unfavorable for the specified use. The limitations generally cannot be overcome without major soil reclamation, special design, or expensive installation procedures. Poor performance and high maintenance can be expected.

Numerical ratings in the table indicate the severity of individual limitations. The ratings are shown as decimal fractions ranging from 0.01 to 1.00. They indicate gradations between the point at which a soil feature has the greatest negative impact on the use (1.00) and the point at which the soil feature is not a limitation (0.00).

*Dwellings* are single-family houses of three stories or less. For dwellings without basements, the foundation is assumed to consist of spread footings of reinforced concrete built on undisturbed soil at a depth of 2 feet or at the depth of maximum frost penetration, whichever is deeper. For dwellings with basements, the foundation is assumed to consist of spread footings of reinforced concrete built on undisturbed soil at a depth of about 7 feet. The ratings for dwellings are based on the soil properties that affect the capacity of the soil to support a load without movement and on the properties that affect excavation and construction costs. The properties that affect the load-supporting capacity include depth to a water table, ponding, flooding, subsidence, linear extensibility (shrink-swell potential), and compressibility. Compressibility is inferred from the Unified classification. The properties that affect the ease and amount of excavation include depth to a water table, ponding, flooding, slope, depth to bedrock or a cemented pan, hardness of bedrock or a cemented pan, and the amount and size of rock fragments.

*Small commercial buildings* are structures that are less than three stories high and do not have basements. The foundation is assumed to consist of spread footings of reinforced concrete built on undisturbed soil at a depth of 2 feet or at the depth of maximum frost penetration, whichever is deeper. The ratings are based on the soil properties that affect the capacity of the soil to support a load without movement and on the properties that affect excavation and construction costs. The properties that affect the load-supporting capacity include depth to a water table, ponding, flooding, subsidence, linear extensibility (shrink-swell potential), and compressibility (which is inferred from the Unified classification). The properties that affect the ease and amount of excavation include flooding, depth to a water table, ponding, slope, depth to bedrock or a cemented pan, hardness of bedrock or a cemented pan, and the amount and size of rock fragments.

## Roads and Streets, Shallow Excavations, and Landscaping

Soil properties influence the development of building sites, including the selection of the site, the design of the structure, construction, performance after construction, and maintenance. Table 8 shows the degree and kind of soil limitations that affect local roads and streets, shallow excavations, and landscaping.

The ratings in the table are both verbal and numerical. Rating class terms indicate the extent to which the soils are limited by all of the soil features that affect building site development. *Not limited* indicates that the soil has features that are very favorable for the specified use. Good performance and very low maintenance can be expected. *Somewhat limited* indicates that the soil has features that are moderately favorable for the specified use. The limitations can be overcome or minimized by special planning, design, or installation. Fair performance and moderate maintenance can be expected. *Very limited* indicates that the soil has one or more features that are unfavorable for the specified use. The limitations generally cannot be overcome without major soil reclamation, special design, or expensive installation procedures. Poor performance and high maintenance can be expected.

Numerical ratings in the table indicate the severity of individual limitations. The ratings are shown as decimal fractions ranging from 0.01 to 1.00. They indicate gradations between the point at which a soil feature has the greatest negative impact on the use (1.00) and the point at which the soil feature is not a limitation (0.00).

*Local roads and streets* have an all-weather surface and carry automobile and light truck traffic all year. They have a subgrade of cut or fill soil material; a base of gravel, crushed rock, or soil material stabilized by lime or cement; and a surface of flexible material (asphalt), rigid material (concrete), or gravel with a binder. The ratings are based on the soil properties that affect the ease of excavation and grading and the traffic-supporting capacity. The properties that affect the ease of excavation and grading are depth to bedrock or a cemented pan, hardness of bedrock or a cemented pan, depth to a water table, ponding, flooding, the amount of large stones, and slope. The properties that affect the traffic-supporting capacity are soil strength (as inferred from the AASHTO group index number), subsidence, linear extensibility (shrink-swell potential), the potential for frost action, depth to a water table, and ponding.

*Shallow excavations* are trenches or holes dug to a maximum depth of 5 or 6 feet for graves, utility lines, open ditches, or other purposes. The ratings are based on the soil properties that influence the ease of digging and the resistance to sloughing. Depth to bedrock or a cemented pan, hardness of bedrock or a cemented pan, the amount of large stones, and dense layers influence the ease of digging, filling, and compacting. Depth to the seasonal high water table, flooding, and ponding may restrict the period when excavations can be made. Slope influences the ease of using machinery. Soil texture, depth to the water table, and linear extensibility (shrink-swell potential) influence the resistance to sloughing.

*Landscaping* requires soils on which turf, trees, and shrubs can be established and maintained. Irrigation is not considered in the ratings. The ratings are based on the soil properties that affect plant growth and trafficability after vegetation is established. The properties that affect plant growth are reaction; depth to a water table; ponding; depth to bedrock or a cemented pan; the available water capacity in the upper 40 inches; the content of salts, sodium, or calcium carbonate; and sulfidic materials. The properties that affect trafficability are flooding, depth to a water table, ponding, slope, stoniness, and the amount of sand, clay, or organic matter in the surface layer.

## Sewage Disposal

Table 9 shows the degree and kind of soil limitations that affect septic tank absorption fields and sewage lagoons. The ratings are both verbal and numerical. Rating class terms indicate the extent to which the soils are limited by all of the soil features that affect these uses. *Not limited* indicates that the soil has features that are very favorable for the specified use. Good performance and very low maintenance can be expected. *Somewhat limited* indicates that the soil has features that are moderately favorable for the specified use. The limitations can be overcome or minimized by special planning, design, or installation. Fair performance and moderate maintenance can be expected. *Very limited* indicates that the soil has one or more features that

are unfavorable for the specified use. The limitations generally cannot be overcome without major soil reclamation, special design, or expensive installation procedures. Poor performance and high maintenance can be expected.

Numerical ratings in the table indicate the severity of individual limitations. The ratings are shown as decimal fractions ranging from 0.01 to 1.00. They indicate gradations between the point at which a soil feature has the greatest negative impact on the use (1.00) and the point at which the soil feature is not a limitation (0.00).

*Septic tank absorption fields* are areas in which effluent from a septic tank is distributed into the soil through subsurface tiles or perforated pipe. Only that part of the soil between depths of 24 and 72 inches or between a depth of 24 inches and a restrictive layer is evaluated. The ratings are based on the soil properties that affect absorption of the effluent, construction and maintenance of the system, and public health. Saturated hydraulic conductivity ( $K_{sat}$ ), depth to a water table, ponding, depth to bedrock or a cemented pan, and flooding affect absorption of the effluent. Stones and boulders, ice, and bedrock or a cemented pan interfere with installation. Subsidence interferes with installation and maintenance. Excessive slope may cause lateral seepage and surfacing of the effluent in downslope areas.

Some soils are underlain by loose sand and gravel or fractured bedrock at a depth of less than 4 feet below the distribution lines. In these soils the absorption field may not adequately filter the effluent, particularly when the system is new. As a result, the ground water may become contaminated.

*Sewage lagoons* are shallow ponds constructed to hold sewage while aerobic bacteria decompose the solid and liquid wastes. Lagoons should have a nearly level floor surrounded by cut slopes or embankments of compacted soil. Nearly impervious soil material for the lagoon floor and sides is required to minimize seepage and contamination of ground water. Considered in the ratings are slope, saturated hydraulic conductivity ( $K_{sat}$ ), depth to a water table, ponding, depth to bedrock or a cemented pan, flooding, large stones, and content of organic matter.

Saturated hydraulic conductivity ( $K_{sat}$ ) is a critical property affecting the suitability for sewage lagoons. Most porous soils eventually become sealed when they are used as sites for sewage lagoons. Until sealing occurs, however, the hazard of pollution is severe. Soils that have a  $K_{sat}$  rate of more than 14 micrometers per second are too porous for the proper functioning of sewage lagoons. In these soils, seepage of the effluent can result in contamination of the ground water. Ground-water contamination is also a hazard if fractured bedrock is within a depth of 40 inches, if the water table is high enough to raise the level of sewage in the lagoon, or if floodwater overtops the lagoon.

A high content of organic matter is detrimental to proper functioning of the lagoon because it inhibits aerobic activity. Slope, bedrock, and cemented pans can cause construction problems, and large stones can hinder compaction of the lagoon floor. If the lagoon is to be uniformly deep throughout, the slope must be gentle enough and the soil material must be thick enough over bedrock or a cemented pan to make land smoothing practical.

## Source of Gravel and Sand

Table 10 gives information about the soils as potential sources of gravel and sand. Normal compaction, minor processing, and other standard construction practices are assumed.

Sand and gravel are natural aggregates suitable for commercial use with a minimum of processing. They are used in many kinds of construction. Specifications for each use vary widely. Only the likelihood of finding material in suitable quantity is evaluated. The suitability of the material for specific purposes is not evaluated, nor are factors that affect excavation of the material. The properties used to evaluate the soil as a source of sand or gravel are gradation of grain sizes (as indicated by the Unified

classification of the soil), the thickness of suitable material, and the content of rock fragments. If the bottom layer of the soil contains sand or gravel, the soil is considered a likely source regardless of thickness. The assumption is that the sand or gravel layer below the depth of observation exceeds the minimum thickness. The ratings are for the whole soil, from the surface to a depth of about 6 feet.

The soils are rated *good*, *fair*, or *poor* as potential sources of sand and gravel. A rating of *good* or *fair* means that the source material is likely to be in or below the soil. The bottom layer and the thickest layer of the soils are assigned numerical ratings. These ratings indicate the likelihood that the layer is a source of sand or gravel. The number 0.00 indicates that the layer is a poor source. The number 1.00 indicates that the layer is a good source. A number between 0.00 and 1.00 indicates the degree to which the layer is a likely source.

### **Source of Reclamation Material, Roadfill, and Topsoil**

Table 11 gives information about the soils as potential sources of reclamation material, roadfill, and topsoil. Normal compaction, minor processing, and other standard construction practices are assumed.

The soils are rated *good*, *fair*, or *poor* as potential sources of reclamation material, roadfill, and topsoil. The features that limit the soils as sources of these materials are specified in the table. Numerical ratings between 0.00 and 0.99 are given after the specified features. These numbers indicate the degree to which the features limit the soils as sources of topsoil, reclamation material, or roadfill. The lower the number, the greater the limitation.

*Reclamation material* is used in areas that have been drastically disturbed by surface mining or similar activities. When these areas are reclaimed, layers of soil material or unconsolidated geological material, or both, are replaced in a vertical sequence. The reconstructed soil favors plant growth. The ratings in the table do not apply to quarries and other mined areas that require an offsite source of reconstruction material. The ratings are based on the soil properties that affect erosion and stability of the surface and the productive potential of the reconstructed soil. These properties include the content of sodium, salts, and calcium carbonate; reaction; available water capacity; erodibility; texture; content of rock fragments; and content of organic matter and other features that affect fertility.

*Roadfill* is soil material that is excavated in one place and used in road embankments in another place. In this table, the soils are rated as a source of roadfill for low embankments, generally less than 6 feet high and less exacting in design than higher embankments. The ratings are for the whole soil, from the surface to a depth of about 5 feet. It is assumed that soil layers will be mixed when the soil material is excavated and spread.

The ratings are based on the amount of suitable material and on soil properties that affect the ease of excavation and the performance of the material after it is in place. The thickness of the suitable material is a major consideration. The ease of excavation is affected by large stones, depth to a water table, and slope. How well the soil performs in place after it has been compacted and drained is determined by its strength (as inferred from the AASHTO classification of the soil) and linear extensibility (shrink-swell potential).

*Topsoil* is used to cover an area so that vegetation can be established and maintained. The upper 40 inches of a soil is evaluated for use as topsoil. Also evaluated is the reclamation potential of the borrow area. The ratings are based on the soil properties that affect plant growth; the ease of excavating, loading, and spreading the material; and reclamation of the borrow area. Toxic substances, soil reaction, and the properties that are inferred from soil texture, such as available water capacity and fertility, affect plant growth. The ease of excavating, loading, and spreading is affected by rock fragments, slope, depth to a water table, soil texture, and thickness of suitable

material. Reclamation of the borrow area is affected by slope, depth to a water table, rock fragments, depth to bedrock or a cemented pan, and toxic material.

The surface layer of most soils is generally preferred for topsoil because of its organic matter content. Organic matter greatly increases the absorption and retention of moisture and nutrients for plant growth.

## Ponds and Embankments

Table 12 gives information on the soil properties and site features that affect water management. The degree and kind of soil limitations are given for pond reservoir areas; embankments, dikes, and levees; and aquifer-fed excavated ponds. The ratings are both verbal and numerical. Rating class terms indicate the extent to which the soils are limited by all of the soil features that affect these uses. *Not limited* indicates that the soil has features that are very favorable for the specified use. Good performance and very low maintenance can be expected. *Somewhat limited* indicates that the soil has features that are moderately favorable for the specified use. The limitations can be overcome or minimized by special planning, design, or installation. Fair performance and moderate maintenance can be expected. *Very limited* indicates that the soil has one or more features that are unfavorable for the specified use. The limitations generally cannot be overcome without major soil reclamation, special design, or expensive installation procedures. Poor performance and high maintenance can be expected.

Numerical ratings in the table indicate the severity of individual limitations. The ratings are shown as decimal fractions ranging from 0.01 to 1.00. They indicate gradations between the point at which a soil feature has the greatest negative impact on the use (1.00) and the point at which the soil feature is not a limitation (0.00).

*Pond reservoir areas* hold water behind a dam or embankment. Soils best suited to this use have low seepage potential in the upper 60 inches. The seepage potential is determined by the saturated hydraulic conductivity ( $K_{sat}$ ) of the soil and the depth to fractured bedrock or other permeable material. Excessive slope can affect the storage capacity of the reservoir area.

*Embankments, dikes, and levees* are raised structures of soil material, generally less than 20 feet high, constructed to impound water or to protect land against overflow. Embankments that have zoned construction (core and shell) are not considered. In this table, the soils are rated as a source of material for embankment fill. The ratings apply to the soil material below the surface layer to a depth of 5 or 6 feet. It is assumed that soil layers will be uniformly mixed and compacted during construction.

The ratings do not indicate the ability of the natural soil to support an embankment. Soil properties to a depth even greater than the height of the embankment can affect performance and safety of the embankment. Generally, deeper onsite investigation is needed to determine these properties.

Soil material in embankments must be resistant to seepage, piping, and erosion and have favorable compaction characteristics. Unfavorable features include less than 5 feet of suitable material and a high content of stones or boulders, organic matter, or salts or sodium. A high water table affects the amount of usable material. It also affects trafficability.

*Aquifer-fed excavated ponds* are pits or dugouts that extend to a ground-water aquifer or to a depth below a permanent water table. Excluded are ponds that are fed only by surface runoff and embankment ponds that impound water 3 feet or more above the original surface. Excavated ponds are affected by depth to a permanent water table,  $K_{sat}$  of the aquifer, and quality of the water as inferred from the salinity of the soil. Depth to bedrock and the content of large stones affect the ease of excavation.



# Soil Properties

---

Data relating to soil properties are collected during the course of the soil survey.

Soil properties are ascertained by field examination of the soils and by laboratory index testing of some benchmark soils. Established standard procedures are followed. During the survey, many shallow borings are made and examined to identify and classify the soils and to delineate them on the soil maps. Samples are taken from some typical profiles and tested in the laboratory to determine particle-size distribution, plasticity, and compaction characteristics.

Estimates of soil properties are based on field examinations, on laboratory tests of samples from the survey area, and on laboratory tests of samples of similar soils in nearby areas. Tests verify field observations, verify properties that cannot be estimated accurately by field observation, and help to characterize key soils.

The estimates of soil properties are shown in tables. They include engineering properties, physical and chemical properties, and pertinent soil and water features.

## Engineering Properties

Table 13 gives the engineering classifications and the range of engineering properties for the layers of each soil in the park.

*Depth* to the upper and lower boundaries of each layer is indicated.

*Texture* is given in the standard terms used by the U.S. Department of Agriculture. These terms are defined according to percentages of sand, silt, and clay in the fraction of the soil that is less than 2 millimeters in diameter. "Loam," for example, is soil that is 7 to 27 percent clay, 28 to 50 percent silt, and less than 52 percent sand. If the content of particles coarser than sand is 15 percent or more, an appropriate modifier is added, for example, "gravelly."

*Classification* of the soils is determined according to the Unified soil classification system (ASTM, 2005) and the system adopted by the American Association of State Highway and Transportation Officials (AASHTO, 2004).

The Unified system classifies soils according to properties that affect their use as construction material. Soils are classified according to particle-size distribution of the fraction less than 3 inches in diameter and according to plasticity index, liquid limit, and organic matter content. Sandy and gravelly soils are identified as GW, GP, GM, GC, SW, SP, SM, and SC; silty and clayey soils as ML, CL, OL, MH, CH, and OH; and highly organic soils as PT. Soils exhibiting engineering properties of two groups can have a dual classification, for example, CL-ML.

The AASHTO system classifies soils according to those properties that affect roadway construction and maintenance. In this system, the fraction of a mineral soil that is less than 3 inches in diameter is classified in one of seven groups from A-1 through A-7 on the basis of particle-size distribution, liquid limit, and plasticity index. Soils in group A-1 are coarse grained and low in content of fines (silt and clay). At the other extreme, soils in group A-7 are fine grained. Highly organic soils are classified in group A-8 on the basis of visual inspection.

If laboratory data are available, the A-1, A-2, and A-7 groups are further classified as A-1-a, A-1-b, A-2-4, A-2-5, A-2-6, A-2-7, A-7-5, or A-7-6. As an additional refinement, the suitability of a soil as subgrade material can be indicated by a group index number. Group index numbers range from 0 for the best subgrade material to 20 or higher for the poorest.

*Rock fragments* larger than 10 inches in diameter and 3 to 10 inches in diameter are indicated as a percentage of the total soil on a dry-weight basis. The percentages are estimates determined mainly by converting volume percentage in the field to weight percentage.

*Percentage (of soil particles) passing designated sieves* is the percentage of the soil fraction less than 3 inches in diameter based on an oven-dry weight. The sieves, numbers 4, 10, 40, and 200 (USA Standard Series), have openings of 4.76, 2.00, 0.420, and 0.074 millimeters, respectively. Estimates are based on laboratory tests of soils sampled in the survey area and in nearby areas and on estimates made in the field.

*Liquid limit and plasticity index* (Atterberg limits) indicate the plasticity characteristics of a soil. The estimates are based on test data from the survey area or from nearby areas and on field examination.

## Physical Soil Properties

Table 14 shows estimates of some physical characteristics and features that affect soil behavior. These estimates are given for the layers of each soil in the park. The estimates are based on field observations and on test data for these and similar soils.

*Depth* to the upper and lower boundaries of each layer is indicated.

Particle size is the effective diameter of a soil particle as measured by sedimentation, sieving, or micrometric methods. Particle sizes are expressed as classes with specific effective diameter class limits. The broad classes are sand, silt, and clay, ranging from the larger to the smaller.

*Sand* as a soil separate consists of mineral soil particles that are 0.05 millimeter to 2 millimeters in diameter. In this table, the estimated sand content of each soil layer is given as a percentage, by weight, of the soil material that is less than 2 millimeters in diameter.

*Silt* as a soil separate consists of mineral soil particles that are 0.002 to 0.05 millimeter in diameter. In this table, the estimated silt content of each soil layer is given as a percentage, by weight, of the soil material that is less than 2 millimeters in diameter.

*Clay* as a soil separate consists of mineral soil particles that are less than 0.002 millimeter in diameter. In this table, the estimated clay content of each soil layer is given as a percentage, by weight, of the soil material that is less than 2 millimeters in diameter.

The content of sand, silt, and clay affects the physical behavior of a soil. Particle size is important for engineering and agronomic interpretations, for determination of soil hydrologic qualities, and for soil classification.

The amount and kind of clay affect the fertility and physical condition of the soil and the ability of the soil to adsorb cations and to retain moisture. They influence shrink-swell potential, saturated hydraulic conductivity ( $K_{sat}$ ), plasticity, the ease of soil dispersion, and other soil properties. The amount and kind of clay in a soil also affect tillage and earthmoving operations.

*Moist bulk density* is the weight of soil (oven-dry) per unit volume. Volume is measured when the soil is at field moisture capacity, that is, the moisture content at  $1/3$ - or  $1/10$ -bar (33-kPa or 10-kPa) moisture tension. Weight is determined after the soil is dried at 105 degrees C. In the table, the estimated moist bulk density of each soil horizon is expressed in grams per cubic centimeter of soil material that is less than



2 millimeters in diameter. Bulk density data are used to compute linear extensibility, shrink-swell potential, available water capacity, total pore space, and other soil properties. The moist bulk density of a soil indicates the pore space available for water and roots. Depending on soil texture, a bulk density of more than 1.4 can restrict water storage and root penetration. Moist bulk density is influenced by texture, kind of clay, content of organic matter, and soil structure.

*Permeability* ( $K_{sat}$ ) refers to the ability of a soil to transmit water or air. The term "permeability," as used in soil surveys, indicates saturated hydraulic conductivity ( $K_{sat}$ ). The estimates in the table indicate the rate of water movement, in inches per hour, when the soil is saturated. They are based on soil characteristics observed in the field, particularly structure, porosity, and texture. Permeability is considered in the design of soil drainage systems and septic tank absorption fields.

*Available water capacity* refers to the quantity of water that the soil is capable of storing for use by plants. The capacity for water storage is given in inches of water per inch of soil for each soil layer. The capacity varies, depending on soil properties that affect retention of water. The most important properties are the content of organic matter, soil texture, bulk density, and soil structure. Available water capacity is an important factor in the choice of plants or crops to be grown and in the design and management of irrigation systems. Available water capacity is not an estimate of the quantity of water actually available to plants at any given time.

*Shrink-swell potential* is the potential for volume change in a soil with a loss or gain in moisture. Volume change occurs mainly because of the interaction of clay minerals with water and varies with the amount and type of clay minerals in the soil. The size of the load on the soil and the magnitude of the change in soil moisture content influence the amount of swelling of soils in place. Laboratory measurements of swelling of undisturbed clods were made for many soils. For others, swelling was estimated on the basis of the kind and amount of clay minerals in the soil and on the basis of measurements of similar soils.

If the shrink-swell potential is rated moderate to very high, shrinking and swelling can cause damage to buildings, roads, and other structures. Special design is often needed.

Shrink-swell potential classes are based on the change in length of an unconfined clod as moisture content is increased from air-dry to field capacity. The classes are *low*, a change of less than 3 percent; *moderate*, 3 to 6 percent; *high*, 6 to 9 percent; and *very high*, greater than 9 percent.

*Organic matter* is the plant and animal residue in the soil at various stages of decomposition. In this table, the estimated content of organic matter is expressed as a percentage, by weight, of the soil material that is less than 2 millimeters in diameter.

The content of organic matter in a soil can be maintained by returning crop residue to the soil. Organic matter has a positive effect on available water capacity, water infiltration, soil organism activity, and tilth. It is a source of nitrogen and other nutrients for crops and soil organisms.

## Erosion Properties

Table 15 shows estimates of some erosion factors that affect a soil's potential for different uses. These estimates are given for each layer of every soil for K factors and are given as one rating for the entire soil for the T factor. Values are reported for each soil in the park. Estimates are based on field observations and on test data for these and similar soils.

Erosion factors are shown in the table as the K factor ( $K_w$  and  $K_f$ ) and the T factor. Soil erosion factors  $K_w$  and  $K_f$  quantify soil detachment by runoff and raindrop impact. These erosion factors are indexes used to predict the long-term average soil loss from sheet and rill erosion under crop systems and conservation techniques. Factor K is

one of six factors used in the Universal Soil Loss Equation (USLE) and the Revised Universal Soil Loss Equation (RUSLE) to predict the average annual rate of soil loss by sheet and rill erosion in tons per acre per year. The estimates are based primarily on percentage of silt, sand, and organic matter and on soil structure and  $K_{sat}$ . Values of  $K$  range from 0.02 to 0.69. Other factors being equal, the higher the value, the more susceptible the soil is to sheet and rill erosion by water.

The procedure for determining the  $K_f$  factor is outlined in Agriculture Handbook 703, "Predicting Soil Erosion by Water: A Guide to Conservation Planning with the Revised Universal Soil Loss Equation (RUSLE)," USDA, Agricultural Research Service, 1997.

*Depth* to the upper and lower boundaries of each layer is indicated.

*Erosion factor  $K_w$*  indicates the erodibility of the whole soil. The estimates are modified by the presence of rock fragments. In horizons where total rock fragments are 15 percent or more, by volume, the  $K_w$  factor is always less than the  $K_f$  factor.

*Erosion factor  $K_f$*  indicates the erodibility of the fine-earth fraction, or the material less than 2 millimeters in size. Soil horizons that do not have rock fragments are assigned equal  $K_w$  and  $K_f$  factors.

*Erosion factor  $T$*  is an estimate of the maximum average annual rate of soil erosion by wind and/or water that can occur without affecting crop productivity over a sustained period. The rate is in tons per acre per year.

## Total Soil Carbon

Table 16 gives estimates of total soil carbon. Soil carbon occurs as organic and inorganic carbon.

Soil organic carbon (SOC) is carbon (C) in soil that originated from a biological source, such as plants, animals, or micro-organisms. SOC is found in both organic and mineral soil layers. The term "soil organic carbon" refers only to the carbon occurring in soil organic matter (SOM). Soil organic carbon makes up about one-half the weight of soil organic matter. The rest of SOM is mostly oxygen, nitrogen, and hydrogen.

Soil inorganic carbon (SIC) is carbon found in soil carbonates, typically as calcium carbonate layers in the soil or as clay-sized fractions throughout the soil. Carbonates in soils are most common in areas where evaporation rates exceed precipitation, as is the case in most desert environments. Typically, the carbonates accumulated from carbonatic dust or from solution during periods of wetter climates. Soil inorganic carbon also occurs in soils that formed in marl in all regions of the country.

The SOC and SIC contents are reported in kilograms per square meter to a depth of 2 meters or to a representative depth of either hard bedrock or a cemented horizon. The SOC and SIC values are on a whole soil basis, corrected for rock fragments.

SOC can be an indicator of overall soil fertility and soil quality that affects ecosystem function. SOM is the main reservoir for most plant nutrients, such as phosphorus and nitrogen. Managing for SOC by managing for SOM increases the content of these elements and improves soil resiliency.

Soil organic matter binds soil particles together and thus increases soil porosity and water infiltration and allows better root penetration and waterflow into the soil. Greater inflow of water reduces the hazard of erosion and the rate of surface water runoff.

Greater SOC levels improve not only soil quality but also the quality of air and water. Soil acts as a filter and improves water quality. Fertile soils that support plant life remove  $CO_2$  from the atmosphere and increase oxygen levels through photosynthesis. Maintaining the level of soil organic carbon reduces C release into the atmosphere and thus can lessen the effects of global warming.

SIC influences the types of plants that will grow. High SIC levels are commonly associated with a higher soil pH, which limits the types of plants that will thrive.

Like SOM, soil carbonates, the source of SIC, also bind soil particles together. They fill voids in the soil and thus can reduce soil porosity. Compacted soil carbonates may restrict root penetration and waterflow into the soil.

## Chemical Soil Properties

Table 17 shows estimates of some chemical characteristics and features that affect soil behavior. These estimates are given for the layers of each soil in the park. The estimates are based on field observations and on test data for these and similar soils.

*Depth* to the upper and lower boundaries of each layer is indicated.

Cation-exchange capacity is the total amount of extractable cations that can be held by the soil, expressed in terms of milliequivalents per 100 grams of soil at neutrality (pH 7.0) or at some other stated pH value. Soils having a low cation-exchange capacity hold fewer cations and may require more frequent applications of fertilizer than soils having a high cation-exchange capacity. The ability to retain cations reduces the hazard of ground-water pollution.

*Effective cation-exchange capacity* refers to the sum of extractable cations plus aluminum expressed in terms of milliequivalents per 100 grams of soil. It is determined for soils that have pH of less than 5.5.

*Soil reaction* is a measure of acidity or alkalinity. The pH of each soil horizon is based on many field tests. For many soils, values have been verified by laboratory analyses. Soil reaction is important in selecting crops and other plants, in evaluating soil amendments for fertility and stabilization, and in determining the risk of corrosion.

## Water Features

Table 18 gives estimates of various soil water features. The estimates are used in land use planning that involves engineering considerations.

*Hydrologic soil groups* are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The four hydrologic soil groups are:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas.

The *months* in the table indicate the portion of the year in which a water table, ponding, and/or flooding is most likely to be a concern.

*Water table* refers to a saturated zone in the soil. Table 18 indicates, by month, depth to the top (*upper limit*) and base (*lower limit*) of the saturated zone in most years. Estimates of the upper and lower limits are based mainly on observations of the water table at selected sites and on evidence of a saturated zone, namely grayish colors or mottles (redoximorphic features) in the soil. A saturated zone that lasts for less than a month is not considered a water table.

*Ponding* is standing water in a closed depression. Unless a drainage system is installed, the water is removed only by percolation, transpiration, or evaporation. The table indicates *surface water depth* and the *duration* and *frequency* of ponding. Duration is expressed as *very brief* if less than 2 days, *brief* if 2 to 7 days, *long* if 7 to 30 days, and *very long* if more than 30 days. Frequency is expressed as none, rare, occasional, and frequent. *None* means that ponding is not probable; *rare* that it is unlikely but possible under unusual weather conditions (the chance of ponding is nearly 0 percent to 5 percent in any year); *occasional* that it occurs, on the average, once or less in 2 years (the chance of ponding is 5 to 50 percent in any year); and *frequent* that it occurs, on the average, more than once in 2 years (the chance of ponding is more than 50 percent in any year).

*Flooding* is the temporary inundation of an area caused by overflowing streams, by runoff from adjacent slopes, or by tides. Water standing for short periods after rainfall or snowmelt is not considered flooding, and water standing in swamps and marshes is considered ponding rather than flooding.

*Duration* and *frequency* are estimated. Duration is expressed as *extremely brief* if 0.1 hour to 4 hours, *very brief* if 4 hours to 2 days, *brief* if 2 to 7 days, *long* if 7 to 30 days, and *very long* if more than 30 days. Frequency is expressed as none, very rare, rare, occasional, frequent, and very frequent. *None* means that flooding is not probable; *very rare* that it is very unlikely but possible under extremely unusual weather conditions (the chance of flooding is less than 1 percent in any year); *rare* that it is unlikely but possible under unusual weather conditions (the chance of flooding is 1 to 5 percent in any year); *occasional* that it occurs infrequently under normal weather conditions (the chance of flooding is 5 to 50 percent in any year); *frequent* that it is likely to occur often under normal weather conditions (the chance of flooding is more than 50 percent in any year but is less than 50 percent in all months in any year); and *very frequent* that it is likely to occur very often under normal weather conditions (the chance of flooding is more than 50 percent in all months of any year).

The information is based on evidence in the soil profile, namely thin strata of gravel, sand, silt, or clay deposited by floodwater; irregular decrease in organic matter content with increasing depth; and little or no horizon development.

Also considered are local information about the extent and levels of flooding and the relation of each soil on the landscape to historic floods. Information on the extent of flooding based on soil data is less specific than that provided by detailed engineering surveys that delineate flood-prone areas at specific flood frequency levels.

## Soil Features

Table 19 gives estimates of various soil features. The estimates are used in land use planning that involves engineering considerations.

A *restrictive layer* is a nearly continuous layer that has one or more physical, chemical, or thermal properties that significantly impede the movement of water and air through the soil or that restrict roots or otherwise provide an unfavorable root environment. Examples are bedrock, cemented layers, dense layers, and frozen layers. The table indicates the thickness and hardness of the restrictive layer, both of which significantly affect the ease of excavation. *Depth to top* is the vertical distance from the soil surface to the upper boundary of the restrictive layer.

*Potential for frost action* is the likelihood of upward or lateral expansion of the soil caused by the formation of segregated ice lenses (frost heave) and the subsequent collapse of the soil and loss of strength on thawing. Frost action occurs when moisture moves into the freezing zone of the soil. Temperature, texture, density, saturated hydraulic conductivity ( $K_{sat}$ ), content of organic matter, and depth to the water table are the most important factors considered in evaluating the potential for frost action. It is assumed that the soil is not insulated by vegetation or snow and is not artificially drained. Silty and highly structured, clayey soils that have a high water table in winter

are the most susceptible to frost action. Well drained, very gravelly, or very sandy soils are the least susceptible. Frost heave and low soil strength during thawing cause damage to pavements and other rigid structures.

*Risk of corrosion* pertains to potential soil-induced electrochemical or chemical action that corrodes or weakens uncoated steel or concrete. The rate of corrosion of uncoated steel is related to such factors as soil moisture, particle-size distribution, acidity, and electrical conductivity of the soil. The rate of corrosion of concrete is based mainly on the sulfate and sodium content, texture, moisture content, and acidity of the soil. Special site examination and design may be needed if the combination of factors results in a severe hazard of corrosion. The steel or concrete in installations that intersect soil boundaries or soil layers is more susceptible to corrosion than the steel or concrete in installations that are entirely within one kind of soil or within one soil layer.

For uncoated steel, the risk of corrosion, expressed as *low*, *moderate*, or *high*, is based on soil drainage class, total acidity, electrical resistivity near field capacity, and electrical conductivity of the saturation extract.

For concrete, the risk of corrosion also is expressed as *low*, *moderate*, or *high*. It is based on soil texture, acidity, and amount of sulfates in the saturation extract.



# Formation and Classification of the Soils

---

This section relates the soils in Obed Wild and Scenic River to the major factors of soil formation and describes the system of soil classification.

## Factors of Soil Formation

By Susan Burlew Southard, Natural Resources Conservation Service.

Soil covers the surface of the earth as a three-dimensional body of varying depth and is made up of different proportions of organic and mineral material, pore space with gases, and water. Soils differ in their appearance, productivity, and management requirements due to their chemical and physical properties. The characteristics and properties of soils are determined by physical and chemical processes that result from the interaction of five soil-forming factors. These factors of soil formation are interdependent, and few generalizations can be made regarding any one factor unless the effects of the other factors are known. The term “pedogenesis” is often used to connote the processes of soil formation.

The interacting soil-forming factors are parent material, climate, organisms, time, and relief or topography. *Parent material* is the source material in which soils formed. Soils are influenced by the texture and structure of the parent material and its mineralogical and chemical composition. *Climate* is predominantly the temperature and kind and amount of precipitation. *Organisms* are the plants and other organisms living in and on the soil, including humans. *Time* refers to how long the soil-forming factors have been operating. *Relief* or *topography* is the shape and elevation of the landscape. It affects internal and external soil properties, such as soil drainage, aeration, susceptibility to erosion, and the soil's exposure to the sun and wind (Jenny, 1941).

The processes of soil formation are sequences of overlapping events involving biogeochemical reactions that are energized by climate and spatially related to relief or topography (Buol and others, 2011). The physical and chemical properties of soils are altered by these reactions over time.

The influence of any one of these factors varies among all parks and within localities of a particular park. Soils may differ significantly from place to place in a park and within very short distances. In some instances parks may have vast stretches of the same type of soil because of uniform soil-forming factors.

## Parent Material

The unconsolidated mass in which soils form is called parent material. Parent material is a product of weathering of underlying bedrock or weathering of material that has been transported or formed in place. Organic soils are an example of soils forming in place from the accumulation and decomposition of plant material, such as wood and leaves. Weathering refers to the chemical and physical disintegration and decomposition of parent material. Few soils weather directly from the underlying rocks. More commonly, soils form in materials that have moved from elsewhere. Soils





**Figure 1.—Profile of a Ramsey soil. Ramsey soils are shallow to bedrock. The scale is in centimeters. (Image is from Big South Fork National River and Recreation Area.)**



**Figure 2.—An area of Lily-Ramsey complex, 5 to 12 percent slopes, showing the Ramsey soil and associated inclusions of Rock outcrop. Ramsey soils and sandstone rock outcrops are common on the Cumberland Plateau.**



generally have a dominant kind of parent material but are influenced by other types of parent material. Material may have been moved only a few feet by gravity (colluvial parent material) or transported long distances by wind (eolian parent material) or water (alluvial parent material). Soils are said to have “residual” parent material if they formed directly from underlying rocks. Soils formed in residuum may have the same general chemistry as the original rocks, depending on the degree of weathering that has occurred. Because of the chemistry of the acid parent material, most of the soils within Obed Wild and Scenic River are extremely acid to moderately acid (see table 17).

Some parent materials, such as mudstone, are soft and break down into smaller rocks easily, while others are much harder and resist weathering processes, such as silica-cemented sandstone. Soils forming from residuum in Obed Wild and Scenic River include the Gilpin soil, which formed from shale and mudstone. The Lily and Ramsey soils formed from highly resistant, high-silica sandstone of the Cumberland Plateau (fig. 1). The Ramsey soil is often mapped in a complex with sandstone rock outcroppings (fig. 2). The resistant sandstone caps most of the Cumberland Plateau and is more resistant than the shales and mudstones that form the hillslopes. These soils have restrictive layers (see table 19).

Most of the soils in Obed Wild and Scenic River formed from a combination of colluvium, residuum, and alluvium. Soils that weathered from bedrock are on the hillslopes; however, some of the residual soil material was transported from ridges and higher slope positions to lower slopes by gravity. This initial residual material then became colluvial material through the processes of hillslope erosion. The Bouldin soil is an example of a soil that formed in residuum and colluvium on hillslopes (fig. 3).

Alluvium is parent material deposited by water. Soils along Clear and Daddy's Creeks and along the Obed River formed predominantly from alluvium. Alluvial material is recent in age along the river and on flood plains where little soil development has occurred. Soils that formed in alluvium are typically very deep and less sloping than the surrounding terrain. Sediments along rivers and streams have different textures, depending on whether the water that deposited them moved quickly or slowly. Fast-moving water deposited gravel, rocks, and sand in the Obed River channel. Colluvial material deposited on the lowest toeslopes becomes alluvium when captured by flooding events and transported downstream by the currents.

The Craigsville soil has rounded rocks characteristic of a soil formed in alluvium (fig. 4). In Obed Wild and Scenic River, alluvial soils lie along the fast-moving river bottom or in positions on the slightly higher flood plain. The soils are rocky alongside the channel; on flood plains further away from the water, the soils generally have fewer large rocks. The Pope and Philo soils formed in alluvium and lie along some parts of the river channel. Slower-moving water leaves finer textured material as sediments. The Philo soil is slightly siltier than the Pope soil, and both are mostly free of rocks. The picnic ground at Nemo is situated on the Pope and Philo soils (fig. 5).

## Climate

Differences in climate can result in differences in soils. Temperature and moisture influence soil formation and are the two most commonly measured features of climate. Weathering is most active when soils are moist and warm since these soil conditions are conducive to rapid chemical reactions. Cooler temperatures result in slower chemical reactions. While average temperatures and precipitation are important, the extremes of weather in any given locale also play a major role in soil formation.

During periods of rainfall or snowmelt, water carrying dissolved or suspended solids moves through the soil in a process called leaching. The leaching process becomes active with the onset of rainfall or snowmelt. Different temperature and moisture amounts cause different patterns of weathering and leaching in the soil. Seasonal and



**Figure 3.—Profile of a Bouldin soil. Bouldin soils are very deep and formed in accumulated colluvial material on hillslopes. The sharp, angular rocks lying at different angles within the profile are indicative of soils formed in colluvium. The scale is in centimeters. (Image is from Big South Fork National River and Recreation Area.)**

daily changes in temperature affect moisture effectiveness, biological activity, rates of chemical reactions, and kinds of vegetation.

Present-day climate variations in the park are the result of topography and relief. In most areas of the United States, temperature generally decreases with elevation and precipitation generally increases with elevation. As the amount of precipitation increases, the extent of leaching and the amount of vegetation generally increase to a point where they then decrease because of decreasing temperatures. Colder





**Figure 4.—Profile of a Craigsville soil. Craigsville soils are very deep and formed in alluvium. They have the rounded cobbles and gravel characteristic of water-worked material. The scale is in centimeters. (Image is from New River Gorge National River in West Virginia.)**

temperatures result in less leaching because of decreased microbial growth, decreased vegetation, and possibly frozen soil. Fluctuations in temperature and moisture affect the rate of organic matter decomposition and accumulation and the weathering of minerals. For these reasons, cycling of bases is pronounced in areas of warm climate and large amounts of vegetation.

The climate of Obed Wild and Scenic River is humid and temperate. Local temperature variations occur between the valley bottoms and plateaus. All the soils in the park have a mesic (temperate) soil temperature regime and a udic (usually moist) soil moisture regime. Atkin soils are of very minor extent on the river and stream flood plains that have an aquic (usually wet) soil moisture regime. Because of wetness, these soils are considered hydric (see table 4).



Figure 5.—The Nemo picnic ground in an area of Pope-Philo complex, frequently flooded.

## Organisms

Plants, animals, micro-organisms, and humans affect the formation and shape of soils. Flora, such as fungi and bacteria, can help to decompose organic matter and add nutrients to the soil. Animals and micro-organisms mix soils and form burrows and pores. Plant roots open channels in the soils. Abandoned tunnels commonly are filled with loose material from the overlying horizons and transmit water more readily than the surrounding undisturbed soil material.

Different types of roots have different influences on soil properties. Grass roots are fibrous near the surface and easily decompose, adding organic matter to the soil. Fine grass roots can extend below the surface for many feet. Plant roots also help to develop soil structure and aggregate stability. Vegetation increases soil stability by protecting the surface against erosion. Taproots open pathways through dense layers. Micro-organisms affect chemical exchanges between roots and soil. Humans also can mix the soil extensively.

The large plants of the forested ecosystem of Obed Wild and Scenic River affect soil formation. The growing roots of trees help break up rocks and thus create channels that increase water penetration. The shallow Ramsey soil is associated with hard rock outcrop that is slowly being fractured by tree roots. Trees that are blown down help mix the soil when their roots are exposed. Trees also capture energy and substance, through photosynthesis, by the decomposition of plant residue, and by forming organic-mineral complexes, that are recycled many times within the ecosystem (Buol and others, 2011).

Native vegetation depends on climate, topography, and biological factors plus many soil factors, such as soil density, depth, chemistry, temperature, and moisture. In the forested ecosystem of Obed Wild and Scenic River, fallen leaves affect all soils in the park. Organisms decompose these leaves and mix them with the upper part of the soil, resulting in the cycling of nutrients and energy back to vegetation. The leaf litter, whether leaves or needles, helps prevent nutrient loss, conserves soil moisture, reduces raindrop impact, and limits frost penetration.

Humans have also had an effect on the soil-forming processes in Obed Wild and Scenic River. The Bethesda soil formed in acid strip mine material. This soil is commonly in mid-slope positions on hillslopes associated with seams in the shale. The parent material is a mixture of partially weathered fine earth and fragments of bedrock on human-modified hills. Rock fragments within the soil consist mainly of acid shale, siltstone, coal, and medium and fine grained sandstone.

## **Time**

Time for all these factors to interact with the soil also is a soil-forming factor. Soil formation processes are continuous. Over time, soils exhibit features that reflect the other soil-forming factors. Recently deposited material, such as material deposited by a flood or a very active, fast-flowing river (such as the Obed River), exhibits no soil development. Little development is seen in the Pope and Philo soils, which are mapped on the flood plain. The different horizons in a soil profile and the degree of development can be directly related to time. Terraces above the active flood plain, while similar to the flood plain, are more stable land surfaces; thus, soils on these terraces may exhibit more soil horizon development.

Soils such as the Bethesda soil on mine spoils have no diagnostic subsurface horizons. Mining activities have set the soil-forming time clock back to when the mine spoils were deposited by man.

The Gilpin (fig. 6), Wernock, Shelocta, Lily, Lonewood, and Jefferson soils, which have argillic diagnostic subsurface horizons, have distinctive profile characteristics because of favorable landscape positions and parent material. The argillic horizon has an accumulation of secondary silicate clays. It forms over time, depending on weathering intensity, and its expression in the soil varies according to climate and landscape position.

Although the Ramsey soil may be as stable as and in existence as long as the soils with argillic horizons in the park, it does not have an argillic horizon because it formed from weather-resistant silica-cemented sandstone.

## **Topography and Relief**

Topography refers to the shape of the landscape, and relief refers to differences in elevation. The overall landscape in a park, whether it consists of rolling hills, or steep gorges, is the result of erosion and depositional processes. These processes may have occurred in response to changes in climate and/or tectonic activities. Cyclic periods of landscape stability and instability influence the types of soils that form on the landscape.

Slope and aspect of the overall landscape can affect the moisture and temperature of the soil. Steep slopes facing the sun are warmer. In Obed Wild and Scenic River, gorges have steep slopes that are affected by differences in temperatures. North-facing slopes are wetter and cooler, and south-facing slopes are drier and warmer. This difference in local climate due to slope orientation with respect to the sun is called the aspect effect. Additionally, cold air can accumulate in river bottoms and gorges, making alluvial soils much cooler than soils on the hillslopes.

Steep soils may be eroded and lose their surface horizons as they form. Thus, soils may be thinner than more nearly level ones that receive deposits from areas upslope. Deeper, darker soils commonly occur on the bottom land where mineral and organic material is deposited. Soil-forming factors continue to affect soils even on stable landscapes. Materials are deposited on their surface, and materials are blown or washed away from their surface. Additions, removals, and alterations are slow or rapid, depending on climate, landscape position, and biological activity.

The area of Obed Wild and Scenic River includes some of the youngest geologic formations in Tennessee. Pennsylvanian-age bedded sandstone, shale, and siltstone





**Figure 6.—Profile of a Gilpin soil. Gilpin soils are moderately deep and formed in interbedded sandstone and siltstone. They have an argillic horizon in the 40-to-80-centimeter zone. The argillic horizon has bright brown colors. The scale is in centimeters. (Image is from Big South Fork National River and Recreation Area.)**

that underlie the park have been cut by the rivers to form the characteristic gorges. The broad plateaus formed from resistant sandstone. Most of the soils associated with the sandstone, such as the Lily soil, are shallow to moderately deep (see table 19). The shallow soils of the park are generally directly on sandstone, such as the Ramsey soil, or on siltstone or shale, such as the Petros soil.

Soils derived from interbedded sandstone, shale, and siltstone in Obed Wild and Scenic River are sloping (10 to 35 percent slopes) because some of the silty layers have more weatherable minerals that naturally erode and form the steep side slopes. These soils typically have partially weathered shale or siltstone layers below the developing soil horizons, whereas soils that formed on sandstone have a less weathered hard contact with the underlying rock. Figure 7 illustrates the general relationship between soil and topography in the vicinity of the Lilly Overlook. Figure 8 illustrates the general relationship between soil and topography at the confluence of the Obed and Emory Rivers near Rock Creek campground.

## Classification of the Soils

Soils are named and classified on the basis of physical and chemical properties in their horizons (layers). Color, texture, structure, and other properties of the soil to a depth of 2 meters are used to key the soil into a classification system. This system helps people to use soil information and also provides a common language for scientists.

Soils and their horizons differ from one another, depending on how and when they formed. Soil scientists use the five soil-forming factors to help predict where different soils may occur. The degree and expression of the soil horizons reflect the extent of interaction of the soil-forming factors with one or more of the soil-forming processes (Simonson, 1959).

When mapping soils, a soil scientist looks for areas with similar soil-forming factors to find similar soils. The properties of the soils are described. Soils with the same kind of properties are given taxonomic names. Soils are classified, mapped, and interpreted on the basis of various kinds of soil horizons and their arrangement. The distribution of soil orders corresponds with the general patterns of the soil-forming factors within the park.

The system of soil classification used by the National Cooperative Soil Survey has six categories (Soil Survey Staff, 1999 and 2010). Beginning with the broadest, these categories are the order, suborder, great group, subgroup, family, and series. Classification is based on soil properties observed in the field or inferred from those observations or from laboratory measurements. The categories are defined in the following paragraphs.



Figure 7.—View while looking southeast from the Lilly Overlook showing the relationship of soils to topography along Clear Creek. The Ramsey soil is associated with the sandstone capping of the Cumberland Plateau. The Gilpin and Petros soils, which are mapped together, are associated with interbedded shale, siltstone, and sandstone. The Lily soil is associated with the Ramsey soil in sandstone areas. Interbedded Pennsylvanian-age sandstones and shales on a dissected terrain, such as in Obed Wild and Scenic River, make delineating soils in a predictable pattern difficult.





Figure 8.—The confluence of the Obed and Emory Rivers near Rock Creek campground.

Erosion processes acting on interbedded sandstones, shales, and siltstones have created complex soil-landscape relationships. The Lily and Ramsey soils are associated mostly with sandstones. The Gilpin, Bouldin, and Petros soils are mostly associated with siltstones and shales. The gorges in the park have a mix of all hillslope soils. The level alluvial areas, however, have fairly predictable soil-landscape relationships. For example, the Pope and Philo soils occur in meanders and along confluences.

**ORDER.** Soil taxonomy at the highest hierarchical level identifies 12 soil orders. The names for the orders and taxonomic soil properties relate to Greek, Latin, or other root words that reveal something about the soil. The differences among orders reflect the dominant soil-forming processes and the degree of soil formation. Each order is identified by a word ending in *sol*. An example is Ultisol.

**SUBORDER.** Each order is divided into suborders primarily on the basis of properties that influence soil genesis and are important to plant growth or properties that reflect the most important variables within the orders. Sixty-four suborders are recognized at the next level of classification. The last syllable in the name of a suborder indicates the order. An example is Udult (*Ud*, meaning humid, plus *ult*, from Ultisol).

**GREAT GROUP.** Each suborder is divided into great groups on the basis of close similarities in kind, arrangement, and degree of development of pedogenic horizons; soil moisture and temperature regimes; type of saturation; and base status. There are about 300 great groups. Each great group is identified by the name of a suborder and by a prefix that indicates a property of the soil. An example is Hapludults (*Hapl*, meaning minimal horizonation, plus *udult*, the suborder of the Ultisols that has a udic moisture regime).

**SUBGROUP.** There are more than 2,400 subgroups. Each great group has a typical subgroup. The typical subgroup is the central concept of the great group; it is not necessarily the most extensive. Other subgroups are intergrades or extragrades. Intergrades are transitions to other orders, suborders, or great groups. Extragrades have some properties that are not representative of the great group but do not indicate transitions to any other taxonomic class. Each subgroup is identified by one or more



adjectives preceding the name of the great group. The adjective *Typic* identifies the subgroup that typifies the great group. An example is Typic Hapludults.

**FAMILY.** Families are established within a subgroup on the basis of physical and chemical properties and other characteristics that affect management. Generally, the properties for family placement are those of horizons below a traditional agronomic plow depth. Among the properties and characteristics considered are particle-size class, mineralogy class, cation-exchange activity class, soil temperature regime, soil depth, and reaction class. A family name consists of the name of a subgroup preceded by terms that indicate soil properties. An example is fine, mixed, semiactive, mesic Typic Hapludults.

**SERIES.** The soil series is the lowest category in the soil classification system. The series consists of soils within a family that have horizons similar in color, texture, structure, reaction, consistence, mineral and chemical composition, and arrangement in the profile. An example is the Sequoia series.

Most parks are mapped to the series level. The names of soil series are selected by the soil scientists during the course of mapping. The series names are commonly geographic place names or are coined. Because of access limitations and soil variability, soils in some remote areas are classified at the great group or subgroup level.

Table 20 indicates the order, suborder, great group, subgroup, and family of the soil series in the park.



# References

---

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487–00.

Buol, S.W., R.J. Southard, R.C. Graham, and P.A. McDaniel. 2011. Soil genesis and classification. 6th edition.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Jenny, Hans. 1941. Factors of soil formation.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Schoeneberger, P.J., D.A. Wysocki, E.C. Benham, and W.D. Broderson, editors. 2002. Field book for describing and sampling soils. Version 2.0. U.S. Department of Agriculture, Natural Resources Conservation Service.

Simonson, Roy W. 1959. Outline of a generalized theory of soil genesis. Soil Science Society of America Proceedings 23:152-156.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18.

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service. U.S. Department of Agriculture Handbook 436.

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service.

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

## Soil Survey of Obed Wild and Scenic River, Tennessee

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. <http://soils.usda.gov/technical/>

United States Department of Agriculture, Natural Resources Conservation Service. PLANTS database. National Plant Data Center. <http://plants.usda.gov>

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296.

United States Department of Agriculture, Natural Resources Conservation Service. 2010. Field indicators of hydric soils in the United States, Version 7.0. L.M. Vasilas, G.W. Hurt, and C.V. Noble, eds. USDA-NRCS in cooperation with the National Technical Committee for Hydric Soils.

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210.

# Glossary

---

- Aeration, soil.** The exchange of air in soil with air from the atmosphere. The air in a well aerated soil is similar to that in the atmosphere; the air in a poorly aerated soil is considerably higher in carbon dioxide and lower in oxygen.
- Aggregate, soil.** Many fine particles held in a single mass or cluster. Natural soil aggregates, such as granules, blocks, or prisms, are called peds. Clods are aggregates produced by tillage or logging.
- Alkali (sodic) soil.** A soil having so high a degree of alkalinity (pH 8.5 or higher) or so high a percentage of exchangeable sodium (15 percent or more of the total exchangeable bases), or both, that plant growth is restricted.
- Alluvial fan.** The fanlike deposit of a stream where it issues from a gorge upon a plain or of a tributary stream near or at its junction with its main stream.
- Alluvium.** Material, such as sand, silt, or clay, deposited on land by streams.
- Alpha,alpha-dipyridyl.** A dye that when dissolved in 1N ammonium acetate is used to detect the presence of reduced iron (Fe II) in the soil. A positive reaction indicates a type of redoximorphic feature.
- Aquic conditions.** Current soil wetness characterized by saturation, reduction, and redoximorphic features.
- Argillic horizon.** A subsoil horizon characterized by an accumulation of illuvial clay.
- Aspect.** The direction in which a slope faces.
- Available water capacity (available moisture capacity).** The capacity of soils to hold water available for use by most plants. It is commonly defined as the difference between the amount of soil water at field moisture capacity and the amount at wilting point. It is commonly expressed as inches of water per inch of soil. The capacity, in inches, in a 60-inch profile or to a limiting layer is expressed as:
- |                |              |
|----------------|--------------|
| Very low ..... | 0 to 3       |
| Low .....      | 3 to 6       |
| Moderate.....  | 6 to 9       |
| High .....     | 9 to 12      |
| Very high..... | more than 12 |
- Base saturation.** The degree to which material having cation-exchange properties is saturated with exchangeable bases (sum of Ca, Mg, Na, and K), expressed as a percentage of the total cation-exchange capacity.
- Bedrock.** The solid rock that underlies the soil and other unconsolidated material or that is exposed at the surface.
- Cation.** An ion carrying a positive charge of electricity. The common soil cations are calcium, potassium, magnesium, sodium, and hydrogen.
- Cation-exchange capacity.** The total amount of exchangeable cations that can be held by the soil, expressed in terms of milliequivalents per 100 grams of soil at neutrality (pH 7.0) or at some other stated pH value. The term, as applied to soils, is synonymous with base-exchange capacity but is more precise in meaning.
- Clay.** As a soil separate, the mineral soil particles less than 0.002 millimeter in diameter. As a soil textural class, soil material that is 40 percent or more clay, less than 45 percent sand, and less than 40 percent silt.

- Claypan.** A slowly permeable soil horizon that contains much more clay than the horizons above it. A claypan is commonly hard when dry and plastic or stiff when wet.
- Coarse textured soil.** Sand or loamy sand.
- Colluvium.** Soil material or rock fragments, or both, moved by creep, slide, or local wash and deposited at the base of steep slopes.
- Complex, soil.** A map unit of two or more kinds of soil or miscellaneous areas in such an intricate pattern or so small in area that it is not practical to map them separately at the selected scale of mapping. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas.
- Control section.** The part of the soil on which classification is based. The thickness varies among different kinds of soil, but for many it is that part of the soil profile between depths of 10 inches and 40 or 80 inches.
- Corrosion.** Soil-induced electrochemical or chemical action that dissolves or weakens concrete or uncoated steel.
- Depth, soil.** Generally, the thickness of the soil over bedrock. Very deep soils are more than 60 inches deep over bedrock; deep soils, 40 to 60 inches; moderately deep, 20 to 40 inches; shallow, 10 to 20 inches; and very shallow, less than 10 inches.
- Drainage class (natural).** Refers to the frequency and duration of wet periods under conditions similar to those under which the soil formed. Alterations of the water regime by human activities, either through drainage or irrigation, are not a consideration unless they have significantly changed the morphology of the soil. Seven classes of natural soil drainage are recognized—*excessively drained, somewhat excessively drained, well drained, moderately well drained, somewhat poorly drained, poorly drained, and very poorly drained*. These classes are defined in the “Soil Survey Manual.”
- Drainage, surface.** Runoff, or surface flow of water, from an area.
- Eluviation.** The movement of material in true solution or colloidal suspension from one place to another within the soil. Soil horizons that have lost material through eluviation are eluvial; those that have received material are illuvial.
- Eolian soil material.** Earthy parent material accumulated through wind action; commonly refers to sandy material in dunes or to loess in blankets on the surface.
- Erosion.** The wearing away of the land surface by water, wind, ice, or other geologic agents and by such processes as gravitational creep.  
*Erosion (geologic).* Erosion caused by geologic processes acting over long geologic periods and resulting in the wearing away of mountains and the building up of such landscape features as flood plains and coastal plains. Synonym: natural erosion.  
*Erosion (accelerated).* Erosion much more rapid than geologic erosion, mainly as a result of human or animal activities or of a catastrophe in nature, such as a fire, that exposes the surface.
- Escarpment.** A relatively continuous and steep slope or cliff breaking the general continuity of more gently sloping land surfaces and resulting from erosion or faulting. Synonym: scarp.
- Fertility, soil.** The quality that enables a soil to provide plant nutrients, in adequate amounts and in proper balance, for the growth of specified plants when light, moisture, temperature, tilth, and other growth factors are favorable.
- Fill slope.** A sloping surface consisting of excavated soil material from a road cut. It commonly is on the downhill side of the road.
- Fine textured soil.** Sandy clay, silty clay, or clay.
- Flood plain.** A nearly level alluvial plain that borders a stream and is subject to flooding unless protected artificially.

**Fluvial.** Of or pertaining to rivers; produced by river action, as a fluvial plain.

**Forb.** Any herbaceous plant not a grass or a sedge.

**Gravel.** Rounded or angular fragments of rock as much as 3 inches (2 millimeters to 7.6 centimeters) in diameter. An individual piece is a pebble.

**Gravelly soil material.** Material that has 15 to 35 percent, by volume, rounded or angular rock fragments, not prominently flattened, as much as 3 inches (7.6 centimeters) in diameter.

**Ground water.** Water filling all the unblocked pores of the material below the water table.

**Hard bedrock.** Bedrock that cannot be excavated except by blasting or by the use of special equipment that is not commonly used in construction.

**Hill.** A natural elevation of the land surface, rising as much as 1,000 feet above surrounding lowlands, commonly of limited summit area and having a well defined outline; hillsides generally have slopes of more than 15 percent. The distinction between a hill and a mountain is arbitrary and is dependent on local usage.

**Horizon, soil.** A layer of soil, approximately parallel to the surface, having distinct characteristics produced by soil-forming processes. In the identification of soil horizons, an uppercase letter represents the major horizons. Numbers or lowercase letters that follow represent subdivisions of the major horizons. An explanation of the subdivisions is given in the "Soil Survey Manual." The major horizons of mineral soil are as follows:

*O horizon.*—An organic layer of fresh and decaying plant residue.

*A horizon.*—The mineral horizon at or near the surface in which an accumulation of humified organic matter is mixed with the mineral material. Also, a plowed surface horizon, most of which was originally part of a B horizon.

*E horizon.*—The mineral horizon in which the main feature is loss of silicate clay, iron, aluminum, or some combination of these.

*B horizon.*—The mineral horizon below an A horizon. The B horizon is in part a layer of transition from the overlying A to the underlying C horizon. The B horizon also has distinctive characteristics, such as (1) accumulation of clay, sesquioxides, humus, or a combination of these; (2) prismatic or blocky structure; (3) redder or browner colors than those in the A horizon; or (4) a combination of these.

*C horizon.*—The mineral horizon or layer, excluding indurated bedrock, that is little affected by soil-forming processes and does not have the properties typical of the overlying soil material. The material of a C horizon may be either like or unlike that in which the solum formed. If the material is known to differ from that in the solum, an Arabic numeral, commonly a 2, precedes the letter C.

*Cr horizon.*—Soft, consolidated bedrock beneath the soil.

*R layer.*—Consolidated bedrock beneath the soil. The bedrock commonly underlies a C horizon, but it can be directly below an A or a B horizon.

**Hydrologic soil groups.** Refers to soils grouped according to their runoff potential.

The soil properties that influence this potential are those that affect the minimum rate of water infiltration on a bare soil during periods after prolonged wetting when the soil is not frozen. These properties are depth to a seasonal high water table, the infiltration rate and permeability after prolonged wetting, and depth to a very slowly permeable layer. The slope and the kind of plant cover are not considered but are separate factors in predicting runoff.

**Illuviation.** The movement of soil material from one horizon to another in the soil profile. Generally, material is removed from an upper horizon and deposited in a lower horizon.

**Infiltration.** The downward entry of water into the immediate surface of soil or other material, as contrasted with percolation, which is movement of water through soil layers or material.

**Infiltration capacity.** The maximum rate at which water can infiltrate into a soil under a given set of conditions.

**Infiltration rate.** The rate at which water penetrates the surface of the soil at any given instant, usually expressed in inches per hour. The rate can be limited by the infiltration capacity of the soil or the rate at which water is applied at the surface.

**Intake rate.** The average rate of water entering the soil under irrigation. Most soils have a fast initial rate; the rate decreases with application time. Therefore, intake rate for design purposes is not a constant but is a variable depending on the net irrigation application. The rate of water intake, in inches per hour, is expressed as follows:

Less than 0.2 .....	very low
0.2 to 0.4 .....	low
0.4 to 0.75 .....	moderately low
0.75 to 1.25 .....	moderate
1.25 to 1.75 .....	moderately high
1.75 to 2.5 .....	high
More than 2.5 .....	very high

**K<sub>sat</sub>.** Saturated hydraulic conductivity. (See Permeability.)

**Leaching.** The removal of soluble material from soil or other material by percolating water.

**LEP.** See Linear extensibility percent.

**Linear extensibility (LE).** Refers to the change in length of an unconfined clod as moisture content is decreased from a moist to a dry state. Linear extensibility is used to determine the shrink-swell potential of soils. It is an expression of the volume change between the water content of the clod at  $\frac{1}{3}$ - or  $\frac{1}{10}$ -bar tension (33kPa or 10kPa tension) and oven dryness. Volume change is influenced by the amount and type of clay minerals in the soil. The volume change is the percent change for the whole soil. If it is expressed as a fraction, the resulting value is COLE, coefficient of linear extensibility.

**Linear extensibility percent.** Refers to the percent change in linear extensibility.

**Liquid limit.** The moisture content at which the soil passes from a plastic to a liquid state.

**Loam.** Soil material that is 7 to 27 percent clay particles, 28 to 50 percent silt particles, and less than 52 percent sand particles.

**Loess.** Fine grained material, dominantly of silt-sized particles, deposited by wind.

**Low strength.** The soil is not strong enough to support loads.

**Medium textured soil.** Very fine sandy loam, loam, silt loam, or silt.

**Mineral soil.** Soil that is mainly mineral material and low in organic material. Its bulk density is more than that of organic soil.

**Miscellaneous area.** An area that has little or no natural soil and supports little or no vegetation.

**Moderately coarse textured soil.** Coarse sandy loam, sandy loam, or fine sandy loam.

**Moderately fine textured soil.** Clay loam, sandy clay loam, or silty clay loam.

**Neutral soil.** A soil having a pH value of 6.6 to 7.3. (See Reaction, soil.)

**Nutrient, plant.** Any element taken in by a plant essential to its growth. Plant nutrients are mainly nitrogen, phosphorus, potassium, calcium, magnesium, sulfur, iron, manganese, copper, boron, and zinc obtained from the soil and carbon, hydrogen, and oxygen obtained from the air and water.

**Organic matter.** Plant and animal residue in the soil in various stages of decomposition. The content of organic matter in the surface layer is described as follows:

Very low .....	less than 0.5 percent
Low .....	0.5 to 1.0 percent
Moderately low .....	1.0 to 2.0 percent



## Soil Survey of Obed Wild and Scenic River, Tennessee

Moderate.....	2.0 to 4.0 percent
High .....	4.0 to 8.0 percent
Very high.....	more than 8.0 percent

**Pan.** A compact, dense layer in a soil that impedes the movement of water and the growth of roots. For example, *hardpan*, *fragipan*, *claypan*, *plowpan*, and *traffic pan*.

**Parent material.** The unconsolidated organic and mineral material in which soil forms.

**Ped.** An individual natural soil aggregate, such as a granule, a prism, or a block.

**Pedon.** The smallest volume that can be called “a soil.” A pedon is three dimensional and large enough to permit study of all horizons. Its area ranges from about 10 to 100 square feet (1 square meter to 10 square meters), depending on the variability of the soil.

**Percolation.** The movement of water through the soil.

**Permeability.** The quality of the soil that enables water or air to move downward through the profile. The rate at which a saturated soil transmits water is accepted as a measure of this quality. In soil physics, the rate is referred to as “saturated hydraulic conductivity,” which is defined in the “Soil Survey Manual.” In line with conventional usage in the engineering profession and with traditional usage in published soil surveys, this rate of flow continues to be expressed as “permeability.” Terms describing permeability, measured in inches per hour, are as follows:

Extremely slow.....	0.0 to 0.01 inch
Very slow .....	0.01 to 0.06 inch
Slow .....	0.06 to 0.2 inch
Moderately slow.....	0.2 to 0.6 inch
Moderate.....	0.6 inch to 2.0 inches
Moderately rapid .....	2.0 to 6.0 inches
Rapid .....	6.0 to 20 inches
Very rapid.....	more than 20 inches

**Phase, soil.** A subdivision of a soil series based on features that affect its use and management, such as slope, stoniness, and flooding.

**pH value.** A numerical designation of acidity and alkalinity in soil. (See Reaction, soil.)

**Plasticity index.** The numerical difference between the liquid limit and the plastic limit; the range of moisture content within which the soil remains plastic.

**Plastic limit.** The moisture content at which a soil changes from semisolid to plastic.

**Plowpan.** A compacted layer formed in the soil directly below the plowed layer.

**Ponding.** Standing water on soils in closed depressions. Unless the soils are artificially drained, the water can be removed only by percolation or evapotranspiration.

**Poorly graded.** Refers to a coarse grained soil or soil material consisting mainly of particles of nearly the same size. Because there is little difference in size of the particles, density can be increased only slightly by compaction.

**Potential rooting depth (effective rooting depth).** Depth to which roots could penetrate if the content of moisture in the soil were adequate. The soil has no properties restricting the penetration of roots to this depth.

**Productivity, soil.** The capability of a soil for producing a specified plant or sequence of plants under specific management.

**Profile, soil.** A vertical section of the soil extending through all its horizons and into the parent material.

**Rangeland.** Land on which the potential natural vegetation is predominantly grasses, grasslike plants, forbs, or shrubs suitable for grazing or browsing. It includes natural grasslands, savannas, many wetlands, some deserts, tundras, and areas that support certain forb and shrub communities.

**Reaction, soil.** A measure of acidity or alkalinity of a soil, expressed in pH values. A soil that tests to pH 7.0 is described as precisely neutral in reaction because it is neither acid nor alkaline. The degrees of acidity or alkalinity, expressed as pH values, are:

## Soil Survey of Obed Wild and Scenic River, Tennessee

Ultra acid.....	less than 3.5
Extremely acid .....	3.5 to 4.4
Very strongly acid .....	4.5 to 5.0
Strongly acid .....	5.1 to 5.5
Moderately acid .....	5.6 to 6.0
Slightly acid.....	6.1 to 6.5
Neutral .....	6.6 to 7.3
Slightly alkaline .....	7.4 to 7.8
Moderately alkaline.....	7.9 to 8.4
Strongly alkaline .....	8.5 to 9.0
Very strongly alkaline.....	9.1 and higher

**Redoximorphic concentrations.** Nodules, concretions, soft masses, pore linings, and other features resulting from the accumulation of iron or manganese oxide. An indication of chemical reduction and oxidation resulting from saturation.

**Redoximorphic depletions.** Low-chroma zones from which iron and manganese oxide or a combination of iron and manganese oxide and clay has been removed. These zones are indications of the chemical reduction of iron resulting from saturation.

**Redoximorphic features.** Redoximorphic concentrations, redoximorphic depletions, reduced matrices, a positive reaction to alpha,alpha-dipyridyl, and other features indicating the chemical reduction and oxidation of iron and manganese compounds resulting from saturation.

**Relief.** The elevations or inequalities of a land surface, considered collectively.

**Residuum (residual soil material).** Unconsolidated, weathered or partly weathered mineral material that accumulated as consolidated rock disintegrated in place.

**Rock fragments.** Rock or mineral fragments having a diameter of 2 millimeters or more; for example, pebbles, cobbles, stones, and boulders.

**Root zone.** The part of the soil that can be penetrated by plant roots.

**Runoff.** The precipitation discharged into stream channels from an area. The water that flows off the surface of the land without sinking into the soil is called surface runoff. Water that enters the soil before reaching surface streams is called ground-water runoff or seepage flow from ground water.

**Saline soil.** A soil containing soluble salts in an amount that impairs growth of plants. A saline soil does not contain excess exchangeable sodium.

**Sand.** As a soil separate, individual rock or mineral fragments from 0.05 millimeter to 2.0 millimeters in diameter. Most sand grains consist of quartz. As a soil textural class, a soil that is 85 percent or more sand and not more than 10 percent clay.

**Sandstone.** Sedimentary rock containing dominantly sand-sized particles.

**Saprolite.** Unconsolidated residual material underlying the soil and grading to hard bedrock below.

**Saturation.** Wetness characterized by zero or positive pressure of the soil water. Under conditions of saturation, the water will flow from the soil matrix into an unlined auger hole.

**Sedimentary rock.** Rock made up of particles deposited from suspension in water. The chief kinds of sedimentary rock are conglomerate, formed from gravel; sandstone, formed from sand; shale, formed from clay; and limestone, formed from soft masses of calcium carbonate. There are many intermediate types. Some wind-deposited sand is consolidated into sandstone.

**Series, soil.** A group of soils that have profiles that are almost alike. All the soils of a series have horizons that are similar in composition, thickness, and arrangement.

**Shale.** Sedimentary rock formed by the hardening of a clay deposit.

**Silt.** As a soil separate, individual mineral particles that range in diameter from the upper limit of clay (0.002 millimeter) to the lower limit of very fine sand (0.05 millimeter). As a soil textural class, soil that is 80 percent or more silt and less than 12 percent clay.

**Siltstone.** Sedimentary rock made up of dominantly silt-sized particles.

**Similar soils.** Soils that share limits of diagnostic criteria, behave and perform in a similar manner, and have similar conservation needs or management requirements for the major land uses in the survey area.

**Site index.** A designation of the quality of a forest site based on the height of the dominant stand at an arbitrarily chosen age. For example, if the average height attained by dominant and codominant trees in a fully stocked stand at the age of 50 years is 75 feet, the site index is 75.

**Slope.** The inclination of the land surface from the horizontal. Percentage of slope is the vertical distance divided by horizontal distance, then multiplied by 100. Thus, a slope of 20 percent is a drop of 20 feet in 100 feet of horizontal distance.

**Sodic (alkali) soil.** A soil having so high a degree of alkalinity (pH 8.5 or higher) or so high a percentage of exchangeable sodium (15 percent or more of the total exchangeable bases), or both, that plant growth is restricted.

**Sodicity.** The degree to which a soil is affected by exchangeable sodium. Sodicity is expressed as a sodium adsorption ratio (SAR) of a saturation extract, or the ratio of  $\text{Na}^+$  to  $\text{Ca}^{++} + \text{Mg}^{++}$ . The degrees of sodicity and their respective ratios are:

Slight.....	less than 13:1
Moderate.....	13-30:1
Strong .....	more than 30:1

**Sodium adsorption ratio (SAR).** A measure of the amount of sodium (Na) relative to calcium (Ca) and magnesium (Mg) in the water extract from saturated soil paste. It is the ratio of the Na concentration divided by the square root of one-half of the Ca + Mg concentration.

**Soft bedrock.** Bedrock that can be excavated with trenching machines, backhoes, small rippers, and other equipment commonly used in construction.

**Soil.** A natural, three-dimensional body at the earth's surface. It is capable of supporting plants and has properties resulting from the integrated effect of climate and living matter acting on earthy parent material, as conditioned by relief over periods of time.

**Soil separates.** Mineral particles less than 2 millimeters in equivalent diameter and ranging between specified size limits. The names and sizes, in millimeters, of separates recognized in the United States are as follows:

Very coarse sand .....	2.0 to 1.0
Coarse sand .....	1.0 to 0.5
Medium sand .....	0.5 to 0.25
Fine sand .....	0.25 to 0.10
Very fine sand .....	0.10 to 0.05
Silt .....	0.05 to 0.002
Clay.....	less than 0.002

**Soil strength.** The load-supporting capacity of a soil at specific moisture and density conditions.

**Solum.** The upper part of a soil profile, above the C horizon, in which the processes of soil formation are active. The solum consists of the A, E, and B horizons. Generally, the characteristics of the material in these horizons are unlike those of the material below the solum. The living roots and plant and animal activities are largely confined to the solum.

**Stones.** Rock fragments 10 to 24 inches (25 to 60 centimeters) in diameter if rounded or 15 to 24 inches (38 to 60 centimeters) in length if flat.

**Stony.** Refers to a soil containing stones in numbers that interfere with or prevent tillage.

**Structure, soil.** The arrangement of primary soil particles into compound particles or aggregates. The principal forms of soil structure are—*platy* (laminated), *prismatic* (vertical axis of aggregates longer than horizontal), *columnar* (prisms with rounded

tops), *blocky* (angular or subangular), and *granular*. *Structureless* soils are either *single grained* (each grain by itself, as in dune sand) or *massive* (the particles adhering without any regular cleavage, as in many hardpans).

**Subsoil.** Technically, the B horizon; roughly, the part of the solum below plow depth.

**Substratum.** The part of the soil below the solum.

**Subsurface layer.** Any surface soil horizon (A, E, AB, or EB) below the surface layer.

**Surface layer.** The soil ordinarily moved in tillage, or its equivalent in uncultivated soil, ranging in depth from 4 to 10 inches (10 to 25 centimeters). Frequently designated as the "plow layer," or the "Ap horizon."

**Surface soil.** The A, E, AB, and EB horizons, considered collectively. It includes all subdivisions of these horizons.

**Terrace.** An embankment, or ridge, constructed across sloping soils on the contour or at a slight angle to the contour. The terrace intercepts surface runoff so that water soaks into the soil or flows slowly to a prepared outlet. A terrace in a field generally is built so that the field can be farmed. A terrace intended mainly for drainage has a deep channel that is maintained in permanent sod.

**Terrace** (geologic). An old alluvial plain, ordinarily flat or undulating, bordering a river, a lake, or the sea.

**Texture, soil.** The relative proportions of sand, silt, and clay particles in a mass of soil.

The basic textural classes, in order of increasing proportion of fine particles, are *sand*, *loamy sand*, *sandy loam*, *loam*, *silt loam*, *silt*, *sandy clay loam*, *clay loam*, *silty clay loam*, *sandy clay*, *silty clay*, and *clay*. The sand, loamy sand, and sandy loam classes may be further divided by specifying "coarse," "fine," or "very fine."

**Tilth, soil.** The physical condition of the soil as related to tillage, seedbed preparation, seedling emergence, and root penetration.

**Topsoil.** The upper part of the soil, which is the most favorable material for plant growth. It is ordinarily rich in organic matter and is used to topdress roadbanks, lawns, and land affected by mining.

**Upland.** Land at a higher elevation, in general, than the alluvial plain or stream terrace; land above the lowlands along streams.

**Weathering.** All physical and chemical changes produced in rocks or other deposits at or near the earth's surface by atmospheric agents. These changes result in disintegration and decomposition of the material.

**Well graded.** Refers to soil material consisting of coarse grained particles that are well distributed over a wide range in size or diameter. Such soil normally can be easily increased in density and bearing properties by compaction. Contrasts with poorly graded soil.

# Tables

---

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 1.—Soil Legend

Map unit symbol and map unit name	Components in map unit	Percent of map unit
523861: Ealy-Craigsville complex, 0 to 5 percent slopes, occasionally flooded----	Ealy	60
	Craigsville	30
	Minor components	10
523880: Jefferson-Varilla-Shelocta complex, 20 to 60 percent slopes, very stony--	Jefferson	50
	Varilla	20
	Shelocta	15
	Minor components	15
523895: Ramsey-Rock outcrop complex, 20 to 50 percent slopes-----	Ramsey	70
	Rock outcrop	20
	Minor components	10
523909: Water-----	Water	100
2439088: Bethesda-Mines pit complex, 10 to 80 percent slopes-----	Bethesda, unstable fill	75
	Mines pit, unstable fill	20
	Lily	2
	Ramsey	2
	Gilpin	1
2439089: Gilpin silt loam, 5 to 12 percent slopes-----	Gilpin	90
	Lily	5
	Sequoia	5
2439090: Gilpin silt loam, 12 to 20 percent slopes-----	Gilpin	90
	Lily	5
	Sequoia	5
2439091: Gilpin-Petros complex, 20 to 35 percent slopes-----	Gilpin	55
	Petros	35
	Sequoia	5
	Lily	3
	Shelocta	2

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 1.—Soil Legend—Continued

Map unit symbol and map unit name	Components in map unit	Percent of map unit
2439092: Gilpin-Petros complex, 35 to 80 percent slopes-----	Gilpin	65
	Petros	25
	Bouldin	5
	Shelocta	4
	Rock outcrop	1
2439093: Gilpin-Bouldin-Petros complex, 25 to 80 percent slopes, very stony-----	Gilpin	35
	Bouldin	30
	Petros	25
	Shelocta	5
	Lily	4
	Rock outcrop	1
2439098: Lily loam, 5 to 12 percent slopes-----	Lily	85
	Gilpin	8
	Shelocta	7
2439099: Lily loam, 12 to 20 percent slopes-----	Lily	85
	Ramsey	8
	Gilpin	6
	Rock outcrop	1
2439100: Lily-Gilpin complex, 5 to 12 percent slopes-----	Lily	65
	Gilpin	30
	Sequoia	3
	Ramsey	2
2439101: Lily-Gilpin complex, 12 to 20 percent slopes-----	Lily	60
	Gilpin	35
	Ramsey	2
	Sequoia	2
	Petros	1

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 1.—Soil Legend—Continued

Map unit symbol and map unit name	Components in map unit	Percent of map unit
2439102: Lily-Gilpin complex, 20 to 35 percent slopes-----	Lily	55
	Gilpin	35
	Sequoia	5
	Ramsey	3
	Petros	2
2439103: Lily-Ramsey complex, 5 to 12 percent slopes-----	Lily	60
	Ramsey	30
	Lonewood	5
	Wernock	5
2439104: Lily-Ramsey complex, 12 to 20 percent slopes-----	Lily	55
	Ramsey	40
	Lonewood	3
	Wernock	2
2439105: Lily-Ramsey complex, 20 to 35 percent slopes-----	Lily	50
	Ramsey	40
	Lonewood	5
	Wernock	5
2439107: Lonewood silt loam, 5 to 12 percent slopes-----	Lonewood	85
	Lily	7
	Gilpin	5
	Wernock	3
2439108: Pope-Philo complex, frequently flooded-----	Pope	50
	Philo	45
	Rowdy	3
	Atkins	2
2439114: Shelocta silt loam, 5 to 12 percent slopes-----	Shelocta	90
	Gilpin	6
	Highsplint	3
	Rock outcrop	1



# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 1.—Soil Legend—Continued

Map unit symbol and map unit name	Components in map unit	Percent of map unit
2439115: Shelocta silt loam, 12 to 20 percent slopes-----	Shelocta	90
	Bouldin	6
	Gilpin	3
	Rock outcrop	1
2439116: Shelocta silt loam, 20 to 35 percent slopes-----	Shelocta	90
	Bouldin	6
	Gilpin	3
	Rock outcrop	1
2439117: Water-----	Water	100
2439118: Wernock silt loam, 2 to 5 percent slopes-----	Wernock	90
	Lily	6
	Lonewood	4
2439119: Wernock silt loam, 5 to 12 percent slopes-----	Wernock	90
	Lily	6
	Lonewood	4

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 2.—Land Capability Classification

(Land capability classification is a system of grouping soils primarily on the basis of their capability to produce common cultivated crops and pasture plants without deteriorating over a long period of time. Only the soils suitable for cultivation are listed)

Map unit symbol and component name	Land capability	
	N	I
523861:		
Ealy-----	2w	---
Craigsville-----	2w	---
523880:		
Jefferson-----	7s	---
Varilla-----	7s	---
Shelocta-----	7s	---
523895:		
Ramsey-----	7s	---
2439088:		
Bethesda, unstable fill-----	7e	---
2439089:		
Gilpin-----	3e	---
2439090:		
Gilpin-----	4e	---
2439091:		
Gilpin-----	6e	---
Petros-----	6e	---
2439092:		
Gilpin-----	7s	---
Petros-----	7s	---
2439093:		
Gilpin-----	7s	---
Bouldin-----	7s	---
Petros-----	7s	---
2439098:		
Lily-----	3e	---
2439099:		
Lily-----	4e	---
2439100:		
Lily-----	3e	---
Gilpin-----	3e	---

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 2.-Land Capability Classification-Continued

Map unit symbol and component name	Land capability	
	N	I
2439101:		
Lily-----	4e	---
Gilpin-----	4e	---
2439102:		
Lily-----	6e	---
Gilpin-----	6e	---
2439103:		
Lily-----	6e	---
Ramsey-----	6e	---
2439104:		
Lily-----	6e	---
Ramsey-----	6e	---
2439105:		
Lily-----	7e	---
Ramsey-----	7e	---
2439107:		
Lonewood-----	3e	---
2439108:		
Pope-----	2w	---
Philo-----	2w	---
2439114:		
Shelocta-----	3e	---
2439115:		
Shelocta-----	4e	---
2439116:		
Shelocta-----	6e	---
2439118:		
Wernock-----	2e	---
2439119:		
Wernock-----	3e	---

Table 3.—Prime and Other Important Farmland

(Only the soils considered prime or important farmland are listed. Urban or built-up areas of the soils listed are not considered prime or important farmland. If a soil is prime or important farmland only under certain conditions, the conditions are indicated in the column "Farmland classification")

Map unit symbol	Map unit name	Farmland classification
2439108	Pope-Philo complex, frequently flooded	Prime farmland if protected from flooding or not frequently flooded during the growing season
2439118	Wernock silt loam, 2 to 5 percent slopes	All areas are prime farmland

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 4.--Hydric Soils

(This report lists only those map unit components that are rated as hydric. Definitions of hydric criteria codes are included at the end of the report)

Map unit symbol and map unit name	Component	Percent of map unit	Landform	Hydric soils criteria			
				Hydric criteria code	Meets saturation criteria	Meets flooding criteria	Meets ponding criteria
2439108: Pope-Philo complex, frequently flooded----	Atkins	2	flood plains	2B3	Yes	No	No

## Explanation of hydric criteria codes

1. All Histels (except for Folistels), and Histosols (except for Folists), which are, by definition, saturated.
2. Soils in Aquic suborders, great groups, or subgroups, Albolls suborder, Historthels great group, Histoturbels great group, Pachic subgroups, or Cumulic subgroups that:
  - A. are somewhat poorly drained and have a water table at the surface (0.0 feet) during the growing season, or
  - B. are poorly drained or very poorly drained and have either:
    - 1.) a water table at the surface (0.0 feet) during the growing season if textures are coarse sand, sand, or fine sand in all layers within a depth of 20 inches, or
    - 2.) a water table at a depth of 0.5 foot or less during the growing season if permeability is equal to or greater than 6.0 in/hr in all layers within a depth of 20 inches, or
    - 3.) a water table at a depth of 1.0 foot or less during the growing season if permeability is less than 6.0 in/hr in any layer within a depth of 20 inches.
3. Soils that are frequently ponded for periods of long or very long duration during the growing season.
4. Soils that are frequently flooded for periods of long or very long duration during the growing season.

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.—Land Management, Part I (Planting)

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.01 to 1.00. The larger the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Suitability for hand planting		Suitability for mechanical planting		Soil rutting hazard	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
523861: Ealy-----	60	Well suited		Well suited		Severe Low strength	1.00
Craigsville-----	30	Moderately suited Rock fragments	0.50	Poorly suited Rock fragments	0.75	Moderate Low strength	0.50
523880: Jefferson-----	50	Moderately suited Slope Rock fragments	0.50 0.50	Unsuited Slope Rock fragments	1.00 0.75	Severe Low strength	1.00
Varilla-----	20	Moderately suited Slope Rock fragments	0.50 0.50	Unsuited Slope Rock fragments	1.00 0.75	Slight Strength	0.10
Shelocta-----	15	Moderately suited Slope	0.50	Unsuited Slope	1.00	Severe Low strength	1.00
523895: Ramsey-----	70	Moderately suited Slope	0.50	Unsuited Slope	1.00	Severe Low strength	1.00
Rock outcrop-----	20	Not rated		Not rated		Not rated	
523909: Water-----	100	Not rated		Not rated		Not rated	
2439088: Bethesda, unstable fill-----	75	Moderately suited Slope	0.50	Unsuited Slope Rock fragments	1.00 0.50	Moderate Low strength	0.50
Mines pit, unstable fill-----	20	Not rated		Not rated		Not rated	
2439089: Gilpin-----	90	Moderately suited Stickiness; high plasticity index	0.50	Moderately suited Slope Stickiness; high plasticity index	0.50 0.50	Severe Low strength	1.00
2439090: Gilpin-----	90	Moderately suited Stickiness; high plasticity index	0.50	Poorly suited Slope Stickiness; high plasticity index	0.75 0.50	Severe Low strength	1.00
2439091: Gilpin-----	55	Moderately suited Stickiness; high plasticity index	0.50	Unsuited Slope Stickiness; high plasticity index	1.00 0.50	Severe Low strength	1.00

Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.—Land Management, Part I (Planting)—Continued

Map unit symbol and soil name	Pct. of map unit	Suitability for hand planting	Value	Suitability for mechanical planting	Value	Soil rutting hazard	
		Rating class and limiting features		Rating class and limiting features		Rating class and limiting features	Value
2439091: Petros-----	35	Moderately suited Rock fragments	0.50	Unsuited Slope Rock fragments	1.00 0.75	Severe Low strength	1.00
2439092: Gilpin-----	65	Moderately suited Slope Stickiness; high plasticity index	0.50 0.50	Unsuited Slope Stickiness; high plasticity index	1.00 0.50	Severe Low strength	1.00
Petros-----	25	Moderately suited Slope Rock fragments	0.50 0.50	Unsuited Slope Rock fragments	1.00 0.75	Severe Low strength	1.00
2439093: Gilpin-----	35	Moderately suited Slope Stickiness; high plasticity index	0.50 0.50	Unsuited Slope Rock fragments Stickiness; high plasticity index	1.00 0.50 0.50	Severe Low strength	1.00
Bouldin-----	30	Moderately suited Slope	0.50	Unsuited Slope Rock fragments	1.00 0.50	Moderate Low strength	0.50
Petros-----	25	Moderately suited Slope Rock fragments	0.50 0.50	Unsuited Slope Rock fragments	1.00 0.75	Severe Low strength	1.00
2439098: Lily-----	85	Moderately suited Stickiness; high plasticity index	0.50	Moderately suited Slope Stickiness; high plasticity index	0.50 0.50	Severe Low strength	1.00
2439099: Lily-----	85	Moderately suited Stickiness; high plasticity index	0.50	Poorly suited Slope Stickiness; high plasticity index	0.75 0.50	Severe Low strength	1.00
2439100: Lily-----	65	Moderately suited Stickiness; high plasticity index	0.50	Moderately suited Slope Stickiness; high plasticity index	0.50 0.50	Severe Low strength	1.00
Gilpin-----	30	Moderately suited Stickiness; high plasticity index	0.50	Moderately suited Slope Stickiness; high plasticity index	0.50 0.50	Severe Low strength	1.00
2439101: Lily-----	60	Moderately suited Stickiness; high plasticity index	0.50	Poorly suited Slope Stickiness; high plasticity index	0.75 0.50	Severe Low strength	1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.—Land Management, Part I (Planting)—Continued

Map unit symbol and soil name	Pct. of map unit	Suitability for hand planting		Suitability for mechanical planting		Soil rutting hazard	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439101: Gilpin-----	35	Moderately suited Stickiness; high plasticity index	0.50	Poorly suited Slope Stickiness; high plasticity index	0.75 0.50	Severe Low strength	1.00
2439102: Lily-----	55	Moderately suited Stickiness; high plasticity index	0.50	Unsuited Slope Stickiness; high plasticity index	1.00 0.50	Severe Low strength	1.00
Gilpin-----	35	Moderately suited Stickiness; high plasticity index	0.50	Unsuited Slope Stickiness; high plasticity index	1.00 0.50	Severe Low strength	1.00
2439103: Lily-----	60	Moderately suited Stickiness; high plasticity index	0.50	Moderately suited Slope Stickiness; high plasticity index	0.50 0.50	Severe Low strength	1.00
Ramsey-----	30	Well suited		Moderately suited Slope	0.50	Severe Low strength	1.00
2439104: Lily-----	55	Moderately suited Stickiness; high plasticity index	0.50	Poorly suited Slope Stickiness; high plasticity index	0.75 0.50	Severe Low strength	1.00
Ramsey-----	40	Well suited		Poorly suited Slope	0.75	Severe Low strength	1.00
2439105: Lily-----	50	Moderately suited Stickiness; high plasticity index	0.50	Unsuited Slope Stickiness; high plasticity index	1.00 0.50	Severe Low strength	1.00
Ramsey-----	40	Well suited		Unsuited Slope	1.00	Severe Low strength	1.00
2439107: Lonewood-----	85	Well suited		Moderately suited Slope	0.50	Severe Low strength	1.00
2439108: Pope-----	50	Well suited		Well suited		Severe Low strength	1.00
Philo-----	45	Well suited		Well suited		Severe Low strength	1.00
2439114: Shelocta-----	90	Moderately suited Stickiness; high plasticity index	0.50	Moderately suited Slope Stickiness; high plasticity index	0.50 0.50	Severe Low strength	1.00



# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.—Land Management, Part I (Planting)—Continued

Map unit symbol and soil name	Pct. of map unit	Suitability for hand planting	Value	Suitability for mechanical planting	Value	Soil rutting hazard	
		Rating class and limiting features		Rating class and limiting features		Rating class and limiting features	Value
2439115: Shelocta-----	90	Moderately suited Stickiness; high plasticity index	0.50	Moderately suited Slope Stickiness; high plasticity index	0.50	Severe Low strength	1.00
2439116: Shelocta-----	90	Moderately suited Stickiness; high plasticity index	0.50	Unsuited Slope Stickiness; high plasticity index	1.00 0.50	Severe Low strength	1.00
2439117: Water-----	100	Not rated		Not rated		Not rated	
2439118: Wernock-----	90	Moderately suited Stickiness; high plasticity index	0.50	Moderately suited Stickiness; high plasticity index	0.50	Severe Low strength	1.00
2439119: Wernock-----	90	Moderately suited Stickiness; high plasticity index	0.50	Moderately suited Slope Stickiness; high plasticity index	0.50 0.50	Severe Low strength	1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.-Land Management, Part II (Hazard of Erosion and Suitability for Roads)

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.01 to 1.00. The larger the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Hazard of erosion		Hazard of erosion on roads and trails		Suitability for roads (natural surface)	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
523861: Ealy-----	60	Slight		Slight		Moderately suited Low strength Flooding	0.50 0.50
Craigsville-----	30	Slight		Slight		Moderately suited Low strength	0.50
523880: Jefferson-----	50	Severe Slope/erodibility	0.75	Severe Slope/erodibility	0.95	Poorly suited Slope Low strength	1.00 0.50
Varilla-----	20	Severe Slope/erodibility	0.75	Severe Slope/erodibility	0.95	Poorly suited Slope	1.00
Shelocta-----	15	Severe Slope/erodibility	0.75	Severe Slope/erodibility	0.95	Poorly suited Slope Low strength	1.00 0.50
523895: Ramsey-----	70	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Low strength	1.00 0.50
Rock outcrop-----	20	Not rated		Not rated		Not rated	
523909: Water-----	100	Not rated		Not rated		Not rated	
2439088: Bethesda, unstable fill-----	75	Severe Slope/erodibility	0.75	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides	1.00 1.00
Mines pit, unstable fill-----	20	Not rated		Not rated		Not rated	
2439089: Gilpin-----	90	Slight		Severe Slope/erodibility	0.95	Moderately suited Low strength Slope	0.50 0.50
2439090: Gilpin-----	90	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Low strength	1.00 0.50
2439091: Gilpin-----	55	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides Low strength	1.00 1.00 0.50

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.-Land Management, Part II (Hazard of Erosion and Suitability for Roads)-Continued

Map unit symbol and soil name	Pct. of map unit	Hazard of erosion		Hazard of erosion on roads and trails		Suitability for roads (natural surface)	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439091: Petros-----	35	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides	1.00 1.00
2439092: Gilpin-----	65	Very severe Slope/erodibility	0.95	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides Low strength	1.00 1.00 0.50
Petros-----	25	Very severe Slope/erodibility	0.95	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides	1.00 1.00
2439093: Gilpin-----	35	Severe Slope/erodibility	0.75	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides Low strength	1.00 1.00 0.50
Bouldin-----	30	Very severe Slope/erodibility	0.95	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides Rock fragments	1.00 1.00 0.50
Petros-----	25	Severe Slope/erodibility	0.75	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides	1.00 1.00
2439098: Lily-----	85	Slight		Severe Slope/erodibility	0.95	Moderately suited Low strength Slope	0.50 0.50
2439099: Lily-----	85	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Low strength Landslides	1.00 0.50 0.33
2439100: Lily-----	65	Slight		Severe Slope/erodibility	0.95	Moderately suited Low strength Slope	0.50 0.50
Gilpin-----	30	Slight		Severe Slope/erodibility	0.95	Moderately suited Low strength Slope	0.50 0.50
2439101: Lily-----	60	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Low strength Landslides	1.00 0.50 0.33
Gilpin-----	35	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Low strength Landslides	1.00 0.50 0.33

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.-Land Management, Part II (Hazard of Erosion and Suitability for Roads)-Continued

Map unit symbol and soil name	Pct. of map unit	Hazard of erosion		Hazard of erosion on roads and trails		Suitability for roads (natural surface)	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439102: Lily-----	55	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides Low strength	1.00 1.00 0.50
Gilpin-----	35	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides Low strength	1.00 1.00 0.50
2439103: Lily-----	60	Slight		Severe Slope/erodibility	0.95	Moderately suited Low strength Slope	0.50 0.50
Ramsey-----	30	Slight		Moderate Slope/erodibility	0.50	Moderately suited Low strength Slope	0.50 0.50
2439104: Lily-----	55	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Low strength Landslides	1.00 0.50 0.33
Ramsey-----	40	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Low strength Landslides	1.00 0.50 0.33
2439105: Lily-----	50	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides Low strength	1.00 1.00 0.50
Ramsey-----	40	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides Low strength	1.00 1.00 0.50
2439107: Lonewood-----	85	Slight		Severe Slope/erodibility	0.95	Moderately suited Low strength Slope	0.50 0.50
2439108: Pope-----	50	Slight		Slight		Poorly suited Flooding Low strength	1.00 0.50
Philo-----	45	Slight		Slight		Poorly suited Flooding Low strength	1.00 0.50
2439114: Shelocta-----	90	Slight		Severe Slope/erodibility	0.95	Moderately suited Low strength Slope	0.50 0.50

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.-Land Management, Part II (Hazard of Erosion and Suitability for Roads)-Continued

Map unit symbol and soil name	Pct. of map unit	Hazard of erosion		Hazard of erosion on roads and trails		Suitability for roads (natural surface)	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439115: Shelocta-----	90	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Low strength Landslides	1.00 0.50 0.30
2439116: Shelocta-----	90	Moderate Slope/erodibility	0.50	Severe Slope/erodibility	0.95	Poorly suited Slope Landslides Low strength	1.00 1.00 0.50
2439117: Water-----	100	Not rated		Not rated		Not rated	
2439118: Wernock-----	90	Slight		Moderate Slope/erodibility	0.50	Moderately suited Low strength	0.50
2439119: Wernock-----	90	Slight		Severe Slope/erodibility	0.95	Moderately suited Low strength Slope	0.50 0.50

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.—Land Management, Part III (Site Preparation)

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.01 to 1.00. The larger the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Suitability for mechanical site preparation (deep)		Suitability for mechanical site preparation (surface)	
		Rating class and limiting features	Value	Rating class and limiting features	Value
523861:					
Ealy-----	60	Well suited		Well suited	
Craigsville-----	30	Poorly suited Rock fragments	0.50	Poorly suited Rock fragments	0.50
523880:					
Jefferson-----	50	Unsuited Slope	1.00	Unsuited Slope Rock fragments	1.00 0.50
Varilla-----	20	Unsuited Slope	1.00	Unsuited Slope Rock fragments	1.00 0.50
Shelocta-----	15	Unsuited Slope	1.00	Unsuited Slope	1.00
523895:					
Ramsey-----	70	Unsuited Restrictive layer Slope	1.00 0.50	Poorly suited Slope	0.50
Rock outcrop-----	20	Not rated		Not rated	
523909:					
Water-----	100	Not rated		Not rated	
2439088:					
Bethesda, unstable fill-----	75	Unsuited Slope	1.00	Unsuited Slope	1.00
Mines pit, unstable fill-----	20	Not rated		Not rated	
2439089:					
Gilpin-----	90	Well suited		Well suited	
2439090:					
Gilpin-----	90	Poorly suited Slope	0.50	Poorly suited Slope	0.50
2439091:					
Gilpin-----	55	Poorly suited Slope	0.50	Poorly suited Slope	0.50
Petros-----	35	Poorly suited Slope	0.50	Poorly suited Slope Rock fragments	0.50 0.50

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.—Land Management, Part III (Site Preparation)—Continued

Map unit symbol and soil name	Pct. of map unit	Suitability for mechanical site preparation (deep)		Suitability for mechanical site preparation (surface)	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439092: Gilpin-----	65	Unsuited Slope	1.00	Unsuited Slope	1.00
Petros-----	25	Unsuited Slope	1.00	Unsuited Slope Rock fragments	1.00 0.50
2439093: Gilpin-----	35	Unsuited Slope	1.00	Unsuited Slope	1.00
Bouldin-----	30	Unsuited Slope	1.00	Unsuited Slope Rock fragments	1.00 0.50
Petros-----	25	Unsuited Slope	1.00	Unsuited Slope Rock fragments	1.00 0.50
2439098: Lily-----	85	Poorly suited Restrictive layer	0.50	Well suited	
2439099: Lily-----	85	Poorly suited Slope Restrictive layer	0.50 0.50	Poorly suited Slope	0.50
2439100: Lily-----	65	Poorly suited Restrictive layer	0.50	Well suited	
Gilpin-----	30	Well suited		Well suited	
2439101: Lily-----	60	Poorly suited Slope Restrictive layer	0.50 0.50	Poorly suited Slope	0.50
Gilpin-----	35	Poorly suited Slope	0.50	Poorly suited Slope	0.50
2439102: Lily-----	55	Poorly suited Slope Restrictive layer	0.50 0.50	Poorly suited Slope	0.50
Gilpin-----	35	Poorly suited Slope	0.50	Poorly suited Slope	0.50
2439103: Lily-----	60	Poorly suited Restrictive layer	0.50	Well suited	
Ramsey-----	30	Unsuited Restrictive layer	1.00	Well suited	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.—Land Management, Part III (Site Preparation)—Continued

Map unit symbol and soil name	Pct. of map unit	Suitability for mechanical site preparation (deep)	Value	Suitability for mechanical site preparation (surface)	Value
		Rating class and limiting features		Rating class and limiting features	
2439104: Lily-----	55	Poorly suited Slope Restrictive layer	0.50 0.50	Poorly suited Slope	0.50
Ramsey-----	40	Unsuited Restrictive layer Slope	1.00 0.50	Poorly suited Slope	0.50
2439105: Lily-----	50	Poorly suited Slope Restrictive layer	0.50 0.50	Poorly suited Slope	0.50
Ramsey-----	40	Unsuited Restrictive layer Slope	1.00 0.50	Poorly suited Slope	0.50
2439107: Loneoood-----	85	Well suited		Well suited	
2439108: Pope-----	50	Well suited		Well suited	
Philo-----	45	Well suited		Well suited	
2439114: Shelocta-----	90	Well suited		Well suited	
2439115: Shelocta-----	90	Poorly suited Slope	0.50	Poorly suited Slope	0.50
2439116: Shelocta-----	90	Poorly suited Slope	0.50	Poorly suited Slope	0.50
2439117: Water-----	100	Not rated		Not rated	
2439118: Wernock-----	90	Well suited		Well suited	
2439119: Wernock-----	90	Well suited		Well suited	



# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.-Land Management, Part IV (Site Restoration)

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.01 to 1.00. The larger the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Potential for damage to soil by fire		Potential for seedling mortality	
		Rating class and limiting features	Value	Rating class and limiting features	Value
523861: Ealy-----	60	Low Texture/rock fragments	0.10	High Wetness	1.00
Craigsville-----	30	Low		Low	
523880: Jefferson-----	50	Low		Low	
Varilla-----	20	Moderate Texture/slope/ rock fragments	0.50	Low	
Shelocta-----	15	Moderate Texture/slope/ surface depth/ rock fragments	0.50	Low	
523895: Ramsey-----	70	High Texture/slope/ surface depth/ rock fragments	1.00	Low	
Rock outcrop-----	20	Not rated		Not rated	
523909: Water-----	100	Not rated		Not rated	
2439088: Bethesda, unstable fill-----	75	High Texture/slope/ surface depth/ rock fragments	1.00	Low	
Mines pit, unstable fill-----	20	Not rated		Not rated	
2439089: Gilpin-----	90	Low Texture/rock fragments	0.10	Low	
2439090: Gilpin-----	90	Low Texture/rock fragments	0.10	Low	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.-Land Management, Part IV (Site Restoration)-Continued

Map unit symbol and soil name	Pct. of map unit	Potential for damage to soil by fire		Potential for seedling mortality	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439091: Gilpin-----	55	Low Texture/rock fragments	0.10	Low	
Petros-----	35	Low		Low	
2439092: Gilpin-----	65	Low		Low	
Petros-----	25	High Texture/slope/ surface depth/ rock fragments	1.00	Low	
2439093: Gilpin-----	35	Low		Low	
Bouldin-----	30	Moderate Texture/slope/ surface depth/ rock fragments	0.50	Low	
Petros-----	25	High Texture/slope/ surface depth/ rock fragments	1.00	Low	
2439098: Lily-----	85	Low		Low	
2439099: Lily-----	85	Low		Low	
2439100: Lily-----	65	Low		Low	
Gilpin-----	30	Low Texture/rock fragments	0.10	Low	
2439101: Lily-----	60	Low		Low	
Gilpin-----	35	Low Texture/rock fragments	0.10	Low	
2439102: Lily-----	55	Low		Low	
Gilpin-----	35	Low Texture/rock fragments	0.10	Low	
2439103: Lily-----	60	Low		Low	
Ramsey-----	30	Low		Low	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 5.-Land Management, Part IV (Site Restoration)-Continued

Map unit symbol and soil name	Pct. of map unit	Potential for damage to soil by fire	Potential for seedling mortality
		Rating class and limiting features	Value
2439104: Lily-----	55	Low	Low
Ramsey-----	40	Low	Low
2439105: Lily-----	50	Low	Low
Ramsey-----	40	Low	Low
2439107: Lonewood-----	85	Low	Low
		Texture/rock fragments	0.10
2439108: Pope-----	50	Low	High
		Texture/rock fragments	0.10
			Wetness
			1.00
Philo-----	45	Low	High
		Texture/rock fragments	0.10
			Wetness
			1.00
2439114: Shelocta-----	90	Low	Low
		Texture/rock fragments	0.10
2439115: Shelocta-----	90	Low	Low
		Texture/rock fragments	0.10
2439116: Shelocta-----	90	Low	Low
		Texture/rock fragments	0.10
2439117: Water-----	100	Not rated	Not rated
2439118: Wernock-----	90	Low	Low
		Texture/rock fragments	0.10
2439119: Wernock-----	90	Low	Low
		Texture/rock fragments	0.10

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 6.-Recreation, Part I (Camp and Picnic Areas)

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.01 to 1.00. The larger the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Camp areas		Picnic areas	
		Rating class and limiting features	Value	Rating class and limiting features	Value
523861: Ealy-----	60	Very limited Flooding	1.00	Not limited	
Craigsville-----	30	Very limited Flooding Large stones content	1.00 0.14	Somewhat limited Large stones content	0.14
523880: Jefferson-----	50	Very limited Too steep Large stones content	1.00 0.01	Very limited Too steep Large stones content	1.00 0.01
Varilla-----	20	Very limited Too steep Large stones content	1.00 0.08	Very limited Too steep Large stones content	1.00 0.08
Shelocta-----	15	Very limited Too steep	1.00	Very limited Too steep	1.00
523895: Ramsey-----	70	Very limited Too steep Depth to bedrock	1.00 1.00	Very limited Too steep Depth to bedrock	1.00 1.00
Rock outcrop-----	20	Not rated		Not rated	
523909: Water-----	100	Not rated		Not rated	
2439088: Bethesda, unstable fill-----	75	Very limited Too steep Gravel Slow water movement	1.00 0.26 0.21	Very limited Too steep Gravel Slow water movement	1.00 0.26 0.21
Mines pit, unstable fill-----	20	Not rated		Not rated	
2439089: Gilpin-----	90	Somewhat limited Slope	0.04	Somewhat limited Slope	0.04
2439090: Gilpin-----	90	Very limited Too steep	1.00	Very limited Too steep	1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 6.—Recreation, Part I (Camp and Picnic Areas)—Continued

Map unit symbol and soil name	Pct. of map unit	Camp areas		Picnic areas	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439091: Gilpin-----	55	Very limited Too steep	1.00	Very limited Too steep	1.00
Petros-----	35	Very limited Too steep Depth to bedrock Gravel	1.00 1.00 0.26	Very limited Too steep Depth to bedrock Gravel	1.00 1.00 0.26
2439092: Gilpin-----	65	Very limited Too steep	1.00	Very limited Too steep	1.00
Petros-----	25	Very limited Too steep Depth to bedrock Gravel	1.00 1.00 0.26	Very limited Too steep Depth to bedrock Gravel	1.00 1.00 0.26
2439093: Gilpin-----	35	Very limited Too steep Large stones content	1.00 0.19	Very limited Too steep Large stones content	1.00 0.19
Bouldin-----	30	Very limited Too steep Large stones content	1.00 0.94	Very limited Too steep Large stones content	1.00 0.94
Petros-----	25	Very limited Too steep Depth to bedrock Gravel Large stones content	1.00 1.00 0.26 0.19	Very limited Too steep Depth to bedrock Gravel Large stones content	1.00 1.00 0.26 0.19
2439098: Lily-----	85	Somewhat limited Slope	0.04	Somewhat limited Slope	0.04
2439099: Lily-----	85	Very limited Too steep	1.00	Very limited Too steep	1.00
2439100: Lily-----	65	Somewhat limited Slope	0.04	Somewhat limited Slope	0.04
Gilpin-----	30	Somewhat limited Slope	0.04	Somewhat limited Slope	0.04
2439101: Lily-----	60	Very limited Too steep	1.00	Very limited Too steep	1.00
Gilpin-----	35	Very limited Too steep	1.00	Very limited Too steep	1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 6.—Recreation, Part I (Camp and Picnic Areas)—Continued

Map unit symbol and soil name	Pct. of map unit	Camp areas		Picnic areas	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439102: Lily-----	55	Very limited Too steep	1.00	Very limited Too steep	1.00
Gilpin-----	35	Very limited Too steep	1.00	Very limited Too steep	1.00
2439103: Lily-----	60	Somewhat limited Slope	0.04	Somewhat limited Slope	0.04
Ramsey-----	30	Very limited Depth to bedrock Slope	1.00 0.04	Very limited Depth to bedrock Slope	1.00 0.04
2439104: Lily-----	55	Very limited Too steep	1.00	Very limited Too steep	1.00
Ramsey-----	40	Very limited Too steep Depth to bedrock	1.00 1.00	Very limited Too steep Depth to bedrock	1.00 1.00
2439105: Lily-----	50	Very limited Too steep	1.00	Very limited Too steep	1.00
Ramsey-----	40	Very limited Too steep Depth to bedrock	1.00 1.00	Very limited Too steep Depth to bedrock	1.00 1.00
2439107: Lonewood-----	85	Somewhat limited Slope	0.04	Somewhat limited Slope	0.04
2439108: Pope-----	50	Very limited Flooding	1.00	Somewhat limited Flooding	0.40
Philo-----	45	Very limited Flooding Depth to saturated zone	1.00 0.07	Somewhat limited Flooding Depth to saturated zone	0.40 0.03
2439114: Shelocta-----	90	Somewhat limited Slope	0.04	Somewhat limited Slope	0.04
2439115: Shelocta-----	90	Very limited Too steep	1.00	Very limited Too steep	1.00
2439116: Shelocta-----	90	Very limited Too steep	1.00	Very limited Too steep	1.00
2439117: Water-----	100	Not rated		Not rated	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 6.—Recreation, Part I (Camp and Picnic Areas)—Continued

Map unit symbol and soil name	Pct. of map unit	Camp areas		Picnic areas	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439118: Wernock-----	90	Not limited		Not limited	
2439119: Wernock-----	90	Somewhat limited Slope	0.01	Somewhat limited Slope	0.01

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 6.-Recreation, Part II (Trail Management)

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.01 to 1.00. The larger the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Foot traffic and equestrian trails		Mountain bike and off-road vehicle trails	
		Rating class and limiting features	Value	Rating class and limiting features	Value
523861:					
Ealy-----	60	Not limited		Not limited	
Craigsville-----	30	Somewhat limited Large stones content	0.14	Somewhat limited Large stones content	0.14
523880:					
Jefferson-----	50	Very limited Slope Large stones content	1.00 0.01	Very limited Slope Large stones content	1.00 0.01
Varilla-----	20	Very limited Slope Large stones content	1.00 0.08	Very limited Slope Large stones content	1.00 0.08
Shelocta-----	15	Very limited Slope	1.00	Very limited Slope	1.00
523895:					
Ramsey-----	70	Very limited Slope	1.00	Somewhat limited Slope	0.78
Rock outcrop-----	20	Not rated		Not rated	
523909:					
Water-----	100	Not rated		Not rated	
2439088:					
Bethesda, unstable fill-----	75	Very limited Slope	1.00	Very limited Slope	1.00
Mines pit, unstable fill-----	20	Not rated		Not rated	
2439089:					
Gilpin-----	90	Not limited		Not limited	
2439090:					
Gilpin-----	90	Somewhat limited Slope	0.02	Not limited	
2439091:					
Gilpin-----	55	Very limited Slope	1.00	Somewhat limited Slope	0.08
Petros-----	35	Very limited Slope	1.00	Somewhat limited Slope	0.08



# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 6.-Recreation, Part II (Trail Management)-Continued

Map unit symbol and soil name	Pct. of map unit	Foot traffic and equestrian trails	Value	Mountain bike and off-road vehicle trails	Value
		Rating class and limiting features		Rating class and limiting features	
2439092: Gilpin-----	65	Very limited Slope	1.00	Very limited Slope	1.00
Petros-----	25	Very limited Slope	1.00	Very limited Slope	1.00
2439093: Gilpin-----	35	Very limited Slope Large stones content	1.00 0.19	Very limited Slope Large stones content	1.00 0.19
Bouldin-----	30	Very limited Slope Large stones content	1.00 0.94	Very limited Slope Large stones content	1.00 0.94
Petros-----	25	Very limited Slope Large stones content	1.00 0.19	Very limited Slope Large stones content	1.00 0.19
2439098: Lily-----	85	Not limited		Not limited	
2439099: Lily-----	85	Somewhat limited Slope	0.02	Not limited	
2439100: Lily-----	65	Not limited		Not limited	
Gilpin-----	30	Not limited		Not limited	
2439101: Lily-----	60	Somewhat limited Slope	0.02	Not limited	
Gilpin-----	35	Somewhat limited Slope	0.02	Not limited	
2439102: Lily-----	55	Very limited Slope	1.00	Somewhat limited Slope	0.08
Gilpin-----	35	Very limited Slope	1.00	Somewhat limited Slope	0.08
2439103: Lily-----	60	Not limited		Not limited	
Ramsey-----	30	Not limited		Not limited	
2439104: Lily-----	55	Somewhat limited Slope	0.02	Not limited	
Ramsey-----	40	Somewhat limited Slope	0.02	Not limited	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 6.-Recreation, Part II (Trail Management)-Continued

Map unit symbol and soil name	Pct. of map unit	Foot traffic and equestrian trails		Mountain bike and off-road vehicle trails	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439105: Lily-----	50	Very limited Slope	1.00	Somewhat limited Slope	0.08
Ramsey-----	40	Very limited Slope	1.00	Somewhat limited Slope	0.08
2439107: Lonewood-----	85	Very limited Water erosion	1.00	Very limited Water erosion	1.00
2439108: Pope-----	50	Somewhat limited Flooding	0.40	Somewhat limited Flooding	0.40
Philo-----	45	Somewhat limited Flooding	0.40	Somewhat limited Flooding	0.40
2439114: Shelocta-----	90	Not limited		Not limited	
2439115: Shelocta-----	90	Not limited		Not limited	
2439116: Shelocta-----	90	Very limited Slope	1.00	Somewhat limited Slope	0.08
2439117: Water-----	100	Not rated		Not rated	
2439118: Wernock-----	90	Not limited		Not limited	
2439119: Wernock-----	90	Very limited Water erosion	1.00	Very limited Water erosion	1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 7.-Dwellings and Small Commercial Buildings

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.01 to 1.00. The larger the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Dwellings without basements		Dwellings with basements		Small commercial buildings	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
523861: Ealy-----	60	Very limited Flooding	1.00	Very limited Flooding Depth to saturated zone	1.00 0.03	Very limited Flooding	1.00
Craigsville-----	30	Very limited Flooding Large stones	1.00 1.00	Very limited Flooding Large stones	1.00 1.00	Very limited Flooding Large stones	1.00 1.00
523880: Jefferson-----	50	Very limited Too steep Large stones	1.00 0.03	Very limited Too steep Large stones	1.00 0.03	Very limited Slope Large stones	1.00 0.03
Varilla-----	20	Very limited Too steep Large stones	1.00 0.32	Very limited Too steep Large stones	1.00 0.32	Very limited Slope Large stones	1.00 0.32
Shelocta-----	15	Very limited Too steep	1.00	Very limited Too steep	1.00	Very limited Slope	1.00
523895: Ramsey-----	70	Very limited Too steep Depth to hard bedrock	1.00 1.00	Very limited Too steep Depth to hard bedrock	1.00 1.00	Very limited Slope Depth to hard bedrock	1.00 1.00
Rock outcrop-----	20	Not rated		Not rated		Not rated	
523909: Water-----	100	Not rated		Not rated		Not rated	
2439088: Bethesda, unstable fill-----	75	Very limited Unstable fill Too steep	1.00 1.00	Very limited Unstable fill Too steep	1.00 1.00	Very limited Slope Unstable fill	1.00 1.00
Mines pit, unstable fill-----	20	Not rated		Not rated		Not rated	
2439089: Gilpin-----	90	Somewhat limited Slope	0.04	Somewhat limited Depth to soft bedrock Slope	0.84 0.04	Very limited Slope	1.00
2439090: Gilpin-----	90	Very limited Too steep	1.00	Very limited Too steep Depth to soft bedrock	1.00 0.84	Very limited Slope	1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 7.-Dwellings and Small Commercial Buildings--Continued

Map unit symbol and soil name	Pct. of map unit	Dwellings without basements		Dwellings with basements		Small commercial buildings	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439091: Gilpin-----	55	Very limited Too steep	1.00	Very limited Too steep Depth to soft bedrock	1.00 0.84	Very limited Slope	1.00
Petros-----	35	Very limited Too steep Depth to soft bedrock	1.00 0.50	Very limited Too steep Depth to soft bedrock	1.00 1.00	Very limited Slope Depth to soft bedrock	1.00 1.00
2439092: Gilpin-----	65	Very limited Too steep	1.00	Very limited Too steep Depth to soft bedrock	1.00 0.84	Very limited Slope	1.00
Petros-----	25	Very limited Too steep Depth to soft bedrock	1.00 0.50	Very limited Too steep Depth to soft bedrock	1.00 1.00	Very limited Slope Depth to soft bedrock	1.00 1.00
2439093: Gilpin-----	35	Very limited Too steep	1.00	Very limited Too steep Depth to soft bedrock	1.00 0.84	Very limited Slope	1.00
Bouldin-----	30	Very limited Too steep Large stones	1.00 0.90	Very limited Too steep Large stones	1.00 0.90	Very limited Slope Large stones	1.00 0.90
Petros-----	25	Very limited Too steep Depth to soft bedrock	1.00 0.50	Very limited Too steep Depth to soft bedrock	1.00 1.00	Very limited Slope Depth to soft bedrock	1.00 1.00
2439098: Lily-----	85	Somewhat limited Depth to hard bedrock Slope	0.46 0.04	Very limited Depth to hard bedrock Slope	1.00 0.04	Very limited Slope Depth to hard bedrock	1.00 0.46
2439099: Lily-----	85	Very limited Too steep Depth to hard bedrock	1.00 0.46	Very limited Depth to hard bedrock Too steep	1.00 1.00	Very limited Slope Depth to hard bedrock	1.00 0.46
2439100: Lily-----	65	Somewhat limited Depth to hard bedrock Slope	0.46 0.04	Very limited Depth to hard bedrock Slope	1.00 0.04	Very limited Slope Depth to hard bedrock	1.00 0.46
Gilpin-----	30	Somewhat limited Slope	0.04	Somewhat limited Depth to soft bedrock Slope	0.84 0.04	Very limited Slope	1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 7.-Dwellings and Small Commercial Buildings--Continued

Map unit symbol and soil name	Pct. of map unit	Dwellings without basements		Dwellings with basements		Small commercial buildings	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439101: Lily-----	60	Very limited Too steep Depth to hard bedrock	1.00 0.46	Very limited Depth to hard bedrock Too steep	1.00 1.00	Very limited Slope Depth to hard bedrock	1.00 0.46
Gilpin-----	35	Very limited Too steep	1.00	Very limited Too steep Depth to soft bedrock	1.00 0.84	Very limited Slope	1.00
2439102: Lily-----	55	Very limited Too steep Depth to hard bedrock	1.00 0.46	Very limited Too steep Depth to hard bedrock	1.00 1.00	Very limited Slope Depth to hard bedrock	1.00 0.46
Gilpin-----	35	Very limited Too steep	1.00	Very limited Too steep Depth to soft bedrock	1.00 0.84	Very limited Slope	1.00
2439103: Lily-----	60	Somewhat limited Depth to hard bedrock Slope	0.46 0.04	Very limited Depth to hard bedrock Slope	1.00 0.04	Very limited Slope Depth to hard bedrock	1.00 0.46
Ramsey-----	30	Very limited Depth to hard bedrock Slope	1.00 0.04	Very limited Depth to hard bedrock Slope	1.00 0.04	Very limited Depth to hard bedrock Slope	1.00 1.00
2439104: Lily-----	55	Very limited Too steep Depth to hard bedrock	1.00 0.46	Very limited Depth to hard bedrock Too steep	1.00 1.00	Very limited Slope Depth to hard bedrock	1.00 0.46
Ramsey-----	40	Very limited Depth to hard bedrock Too steep	1.00 1.00	Very limited Depth to hard bedrock Too steep	1.00 1.00	Very limited Slope Depth to hard bedrock	1.00 1.00
2439105: Lily-----	50	Very limited Too steep Depth to hard bedrock	1.00 0.46	Very limited Too steep Depth to hard bedrock	1.00 1.00	Very limited Slope Depth to hard bedrock	1.00 0.46
Ramsey-----	40	Very limited Too steep Depth to hard bedrock	1.00 1.00	Very limited Too steep Depth to hard bedrock	1.00 1.00	Very limited Slope Depth to hard bedrock	1.00 1.00
2439107: Lonewood-----	85	Somewhat limited Slope	0.04	Somewhat limited Slope	0.04	Very limited Slope	1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 7.-Dwellings and Small Commercial Buildings--Continued

Map unit symbol and soil name	Pct. of map unit	Dwellings without basements		Dwellings with basements		Small commercial buildings	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439108: Pope-----	50	Very limited Flooding	1.00	Very limited Flooding Depth to saturated zone	1.00 0.03	Very limited Flooding	1.00
Philo-----	45	Very limited Flooding Depth to saturated zone	1.00 0.07	Very limited Flooding Depth to saturated zone	1.00 1.00	Very limited Flooding Depth to saturated zone	1.00 0.07
2439114: Shelocta-----	90	Somewhat limited Slope	0.04	Somewhat limited Slope	0.04	Very limited Slope	1.00
2439115: Shelocta-----	90	Very limited Too steep	1.00	Very limited Too steep	1.00	Very limited Slope	1.00
2439116: Shelocta-----	90	Very limited Too steep	1.00	Very limited Too steep	1.00	Very limited Slope	1.00
2439117: Water-----	100	Not rated		Not rated		Not rated	
2439118: Wernock-----	90	Not limited		Somewhat limited Depth to soft bedrock	0.10	Not limited	
2439119: Wernock-----	90	Somewhat limited Slope	0.01	Somewhat limited Depth to soft bedrock Slope	0.10 0.01	Very limited Slope	1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 8.-Roads and Streets, Shallow Excavations, and Landscaping

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.01 to 1.00. The larger the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Local roads and streets	Value	Shallow excavations	Value	Landscaping	Value
		Rating class and limiting features		Rating class and limiting features		Rating class and limiting features	
523861: Ealy-----	60	Very limited Flooding	1.00	Somewhat limited Flooding Unstable excavation walls Depth to saturated zone	0.60 0.10 0.03	Somewhat limited Flooding	0.60
Craigsville-----	30	Very limited Large stones Flooding	1.00 0.40	Very limited Unstable excavation walls Large stones	1.00 1.00	Very limited Large stones Droughty	1.00 0.07
523880: Jefferson-----	50	Very limited Too steep Large stones	1.00 0.03	Very limited Too steep Unstable excavation walls Large stones	1.00 1.00 0.03	Very limited Too steep Large stones	1.00 0.99
Varilla-----	20	Very limited Too steep Large stones	1.00 0.32	Very limited Too steep Large stones Unstable excavation walls	1.00 0.32 0.10	Very limited Too steep Large stones Droughty	1.00 1.00 0.15
Shelocta-----	15	Very limited Too steep	1.00	Very limited Too steep Unstable excavation walls	1.00 0.10	Very limited Too steep	1.00
523895: Ramsey-----	70	Very limited Depth to hard bedrock Too steep	1.00 1.00	Very limited Depth to hard bedrock Too steep Unstable excavation walls	1.00 1.00 0.10	Very limited Depth to bedrock Too steep Droughty	1.00 1.00 1.00
Rock outcrop-----	20	Not rated		Not rated		Not rated	
523909: Water-----	100	Not rated		Not rated		Not rated	
2439088: Bethesda, unstable fill-----	75	Very limited Unstable fill Too steep	1.00 1.00	Very limited Too steep Unstable excavation walls	1.00 0.10	Very limited Too steep Droughty Gravel	1.00 0.59 0.26
Mines pit, unstable fill-----	20	Not rated		Not rated		Not rated	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 8.-Roads and Streets, Shallow Excavations, and Landscaping-Continued

Map unit symbol and soil name	Pct. of map unit	Local roads and streets		Shallow excavations		Landscaping	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439089: Gilpin-----	90	Very limited Low strength Slope	1.00 0.04	Somewhat limited Depth to soft bedrock Unstable excavation walls Slope	0.84 0.10 0.04	Somewhat limited Depth to bedrock Slope Droughty	0.84 0.04 0.03
2439090: Gilpin-----	90	Very limited Too steep Low strength	1.00 1.00	Very limited Too steep Depth to soft bedrock Unstable excavation walls	1.00 0.84 0.10	Very limited Too steep Depth to bedrock Droughty	1.00 0.84 0.03
2439091: Gilpin-----	55	Very limited Too steep Low strength	1.00 1.00	Very limited Too steep Depth to soft bedrock Unstable excavation walls	1.00 0.84 0.10	Very limited Too steep Depth to bedrock Droughty	1.00 0.84 0.03
Petros-----	35	Very limited Too steep Depth to soft bedrock	1.00 1.00	Very limited Depth to soft bedrock Too steep Unstable excavation walls	1.00 1.00 1.00 0.10	Very limited Depth to bedrock Too steep Droughty Gravel	1.00 1.00 1.00 0.26
2439092: Gilpin-----	65	Very limited Too steep Low strength	1.00 1.00	Very limited Too steep Depth to soft bedrock Unstable excavation walls	1.00 0.84 0.10	Very limited Too steep Depth to bedrock Droughty	1.00 0.84 0.03
Petros-----	25	Very limited Too steep Depth to soft bedrock	1.00 1.00	Very limited Depth to soft bedrock Too steep Unstable excavation walls	1.00 1.00 1.00 0.10	Very limited Depth to bedrock Too steep Droughty Gravel	1.00 1.00 1.00 0.26
2439093: Gilpin-----	35	Very limited Too steep Low strength	1.00 1.00	Very limited Too steep Depth to soft bedrock Unstable excavation walls	1.00 0.84 0.10	Very limited Too steep Depth to bedrock Droughty	1.00 0.84 0.03
Bouldin-----	30	Very limited Too steep Large stones	1.00 0.90	Very limited Too steep Large stones Unstable excavation walls	1.00 0.90 0.10	Very limited Too steep Droughty Large stones	1.00 0.34 0.32



# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 8.-Roads and Streets, Shallow Excavations, and Landscaping-Continued

Map unit symbol and soil name	Pct. of map unit	Local roads and streets		Shallow excavations		Landscaping	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439093: Petros-----	25	Very limited Too steep Depth to soft bedrock	1.00 1.00	Very limited Depth to soft bedrock Too steep Unstable excavation walls	1.00 1.00 1.00 0.10	Very limited Depth to bedrock Too steep Droughty Gravel	1.00 1.00 1.00 0.26
2439098: Lily-----	85	Very limited Low strength Depth to hard bedrock Slope	1.00 0.46 0.04	Very limited Depth to hard bedrock Unstable excavation walls Slope	1.00 1.00 0.10 0.04	Somewhat limited Depth to bedrock Slope	0.46 0.04
2439099: Lily-----	85	Very limited Too steep Low strength Depth to hard bedrock	1.00 1.00 1.00 0.46	Very limited Depth to hard bedrock Too steep Unstable excavation walls	1.00 1.00 1.00 0.10	Very limited Too steep Depth to bedrock	1.00 0.46
2439100: Lily-----	65	Very limited Low strength Depth to hard bedrock Slope	1.00 0.46 0.04	Very limited Depth to hard bedrock Unstable excavation walls Slope	1.00 1.00 0.10 0.04	Somewhat limited Depth to bedrock Slope	0.46 0.04
Gilpin-----	30	Very limited Low strength Slope	1.00 0.04	Somewhat limited Depth to soft bedrock Unstable excavation walls Slope	0.84 0.10 0.04	Somewhat limited Depth to bedrock Slope Droughty	0.84 0.04 0.03
2439101: Lily-----	60	Very limited Too steep Low strength Depth to hard bedrock	1.00 1.00 0.46	Very limited Depth to hard bedrock Too steep Unstable excavation walls	1.00 1.00 1.00 0.10	Very limited Too steep Depth to bedrock	1.00 0.46
Gilpin-----	35	Very limited Too steep Low strength	1.00 1.00	Very limited Too steep Depth to soft bedrock Unstable excavation walls	1.00 0.84 0.10	Very limited Too steep Depth to bedrock Droughty	1.00 0.84 0.03

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 8.-Roads and Streets, Shallow Excavations, and Landscaping-Continued

Map unit symbol and soil name	Pct. of map unit	Local roads and streets	Value	Shallow excavations	Value	Landscaping	Value
		Rating class and limiting features		Rating class and limiting features		Rating class and limiting features	
2439102: Lily-----	55	Very limited Too steep Low strength Depth to hard bedrock	 1.00 1.00 0.46	Very limited Depth to hard bedrock Too steep Unstable excavation walls	 1.00  1.00 0.10	Very limited Too steep Depth to bedrock	 1.00 0.46
Gilpin-----	35	Very limited Too steep Low strength	 1.00 1.00	Very limited Too steep Depth to soft bedrock Unstable excavation walls	 1.00 0.84  0.10	Very limited Too steep Depth to bedrock Droughty	 1.00 0.84 0.03
2439103: Lily-----	60	Very limited Low strength Depth to hard bedrock Slope	 1.00 0.46  0.04	Very limited Depth to hard bedrock Unstable excavation walls Slope	 1.00  0.10 0.04	Somewhat limited Depth to bedrock Slope	 0.46 0.04
Ramsey-----	30	Very limited Depth to hard bedrock Slope	 1.00  0.04	Very limited Depth to hard bedrock Unstable excavation walls Slope	 1.00  0.50 0.04	Very limited Depth to bedrock Droughty Slope	 1.00 1.00 0.04
2439104: Lily-----	55	Very limited Too steep Low strength Depth to hard bedrock	 1.00 1.00 0.46	Very limited Depth to hard bedrock Too steep Unstable excavation walls	 1.00  1.00 0.10	Very limited Too steep Depth to bedrock	 1.00 0.46
Ramsey-----	40	Very limited Depth to hard bedrock Too steep	 1.00  1.00	Very limited Depth to hard bedrock Too steep Unstable excavation walls	 1.00  1.00 0.50	Very limited Depth to bedrock Droughty Too steep	 1.00 1.00 1.00
2439105: Lily-----	50	Very limited Too steep Low strength Depth to hard bedrock	 1.00 1.00 0.46	Very limited Depth to hard bedrock Too steep Unstable excavation walls	 1.00  1.00 0.10	Very limited Too steep Depth to bedrock	 1.00 0.46
Ramsey-----	40	Very limited Depth to hard bedrock Too steep	 1.00  1.00	Very limited Depth to hard bedrock Too steep Unstable excavation walls	 1.00  1.00 0.50	Very limited Depth to bedrock Too steep Droughty	 1.00 1.00 1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 8.-Roads and Streets, Shallow Excavations, and Landscaping-Continued

Map unit symbol and soil name	Pct. of map unit	Local roads and streets	Value	Shallow excavations	Value	Landscaping	Value
		Rating class and limiting features		Rating class and limiting features		Rating class and limiting features	
2439107: Lonewood-----	85	Very limited Low strength Slope	1.00 0.04	Somewhat limited Unstable excavation walls Slope	0.10 0.04	Somewhat limited Slope	0.04
2439108: Pope-----	50	Very limited Flooding	1.00	Very limited Unstable excavation walls Flooding Depth to saturated zone	1.00 0.80 0.03	Very limited Flooding	1.00
Philo-----	45	Very limited Flooding Depth to saturated zone	1.00 0.03	Very limited Depth to saturated zone Unstable excavation walls Flooding	1.00 1.00 0.80	Very limited Flooding Depth to saturated zone	1.00 0.03
2439114: Shelocta-----	90	Very limited Low strength Slope	1.00 0.04	Somewhat limited Unstable excavation walls Slope	0.10 0.04	Somewhat limited Slope	0.04
2439115: Shelocta-----	90	Very limited Too steep Low strength	1.00 1.00	Very limited Too steep Unstable excavation walls	1.00 0.10	Very limited Too steep	1.00
2439116: Shelocta-----	90	Very limited Too steep Low strength	1.00 1.00	Very limited Too steep Unstable excavation walls	1.00 0.10	Very limited Too steep	1.00
2439117: Water-----	100	Not rated		Not rated		Not rated	
2439118: Wernock-----	90	Very limited Low strength	1.00	Somewhat limited Depth to soft bedrock Unstable excavation walls	0.10 0.10	Somewhat limited Depth to bedrock	0.10
2439119: Wernock-----	90	Very limited Low strength Slope	1.00 0.01	Somewhat limited Depth to soft bedrock Unstable excavation walls Slope	0.10 0.10 0.01	Somewhat limited Depth to bedrock Slope	0.10 0.01

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 9.—Sewage Disposal

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.01 to 1.00. The larger the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Septic tank absorption fields		Sewage lagoons	
		Rating class and limiting features	Value	Rating class and limiting features	Value
523861: Ealy-----	60	Very limited Flooding Seepage, bottom layer Depth to saturated zone	 1.00 1.00 0.08	Very limited Flooding Seepage Slope	 1.00 1.00 0.02
Craigsville-----	30	Very limited Filtering capacity Seepage, bottom layer Large stones Flooding	 1.00 1.00 1.00 1.00 0.40	Very limited Seepage Large stones Flooding Slope	 1.00 1.00 0.40 0.02
523880: Jefferson-----	50	Very limited Too steep Seepage, bottom layer Large stones	 1.00 1.00 0.03	Very limited Slope Seepage Large stones	 1.00 1.00 0.56
Varilla-----	20	Very limited Too steep Seepage, bottom layer Large stones	 1.00 1.00 0.32	Very limited Slope Seepage Large stones	 1.00 1.00 1.00
Shelocta-----	15	Very limited Too steep Moderate depth to bedrock Slow water movement	 1.00 0.77 0.46	Very limited Slope Seepage Depth to soft bedrock	 1.00 0.53 0.42
523895: Ramsey-----	70	Very limited Shallow depth to bedrock Too steep Seepage, bottom layer	 1.00 1.00 1.00	Very limited Depth to hard bedrock Slope Seepage	 1.00 1.00 1.00
Rock outcrop-----	20	Not rated		Not rated	
523909: Water-----	100	Not rated		Not rated	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 9.-Sewage Disposal--Continued

Map unit symbol and soil name	Pct. of map unit	Septic tank absorption fields		Sewage lagoons	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439088: Bethesda, unstable fill-----	75	Very limited Slow water movement Unstable fill Too steep	1.00 1.00 1.00	Very limited Slope	1.00
Mines pit, unstable fill-----	20	Not rated		Not rated	
2439089: Gilpin-----	90	Very limited Shallow depth to bedrock Slow water movement Slope	1.00 0.50 0.04	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 0.53
2439090: Gilpin-----	90	Very limited Shallow depth to bedrock Too steep Slow water movement	1.00 1.00 0.50	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 0.53
2439091: Gilpin-----	55	Very limited Shallow depth to bedrock Too steep Slow water movement	1.00 1.00 0.50	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 0.53
Petros-----	35	Very limited Shallow depth to bedrock Too steep Seepage, bottom layer	1.00 1.00 1.00	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 1.00
2439092: Gilpin-----	65	Very limited Shallow depth to bedrock Too steep Slow water movement	1.00 1.00 0.50	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 0.53
Petros-----	25	Very limited Shallow depth to bedrock Too steep Seepage, bottom layer	1.00 1.00 1.00	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 9.-Sewage Disposal--Continued

Map unit symbol and soil name	Pct. of map unit	Septic tank absorption fields		Sewage lagoons	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439093: Gilpin-----	35	Very limited Shallow depth to bedrock Too steep Slow water movement	1.00 1.00 0.50	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 0.53
Bouldin-----	30	Very limited Too steep Seepage, bottom layer Large stones	1.00 1.00 0.90	Very limited Slope Seepage Large stones	1.00 1.00 0.67
Petros-----	25	Very limited Shallow depth to bedrock Too steep Seepage, bottom layer	1.00 1.00 1.00	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 1.00
2439098: Lily-----	85	Very limited Shallow depth to bedrock Seepage, bottom layer Slope	1.00 1.00 0.04	Very limited Depth to hard bedrock Seepage Slope	1.00 1.00 1.00
2439099: Lily-----	85	Very limited Shallow depth to bedrock Seepage, bottom layer Too steep	1.00 1.00 1.00	Very limited Depth to hard bedrock Slope Seepage	1.00 1.00 1.00
2439100: Lily-----	65	Very limited Shallow depth to bedrock Seepage, bottom layer Slope	1.00 1.00 0.04	Very limited Depth to hard bedrock Seepage Slope	1.00 1.00 1.00
Gilpin-----	30	Very limited Shallow depth to bedrock Slow water movement Slope	1.00 0.50 0.04	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 0.53
2439101: Lily-----	60	Very limited Shallow depth to bedrock Seepage, bottom layer Too steep	1.00 1.00 1.00	Very limited Depth to hard bedrock Slope Seepage	1.00 1.00 1.00

Soil Survey of Obed Wild and Scenic River, Tennessee

Table 9.-Sewage Disposal--Continued

Map unit symbol and soil name	Pct. of map unit	Septic tank absorption fields		Sewage lagoons	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439101: Gilpin-----	35	Very limited Shallow depth to bedrock Too steep Slow water movement	1.00 1.00 0.50	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 0.53
2439102: Lily-----	55	Very limited Shallow depth to bedrock Too steep Seepage, bottom layer	1.00 1.00 1.00	Very limited Depth to hard bedrock Slope Seepage	1.00 1.00 1.00
Gilpin-----	35	Very limited Shallow depth to bedrock Too steep Slow water movement	1.00 1.00 0.50	Very limited Depth to soft bedrock Slope Seepage	1.00 1.00 0.53
2439103: Lily-----	60	Very limited Shallow depth to bedrock Seepage, bottom layer Slope	1.00 1.00 0.04	Very limited Depth to hard bedrock Seepage Slope	1.00 1.00 1.00
Ramsey-----	30	Very limited Shallow depth to bedrock Seepage, bottom layer Slope	1.00 1.00 0.04	Very limited Depth to hard bedrock Seepage Slope	1.00 1.00 1.00
2439104: Lily-----	55	Very limited Shallow depth to bedrock Seepage, bottom layer Too steep	1.00 1.00 1.00	Very limited Depth to hard bedrock Slope Seepage	1.00 1.00 1.00
Ramsey-----	40	Very limited Shallow depth to bedrock Seepage, bottom layer Too steep	1.00 1.00 1.00	Very limited Depth to hard bedrock Slope Seepage	1.00 1.00 1.00
2439105: Lily-----	50	Very limited Shallow depth to bedrock Too steep Seepage, bottom layer	1.00 1.00 1.00	Very limited Depth to hard bedrock Slope Seepage	1.00 1.00 1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 9.—Sewage Disposal—Continued

Map unit symbol and soil name	Pct. of map unit	Septic tank absorption fields		Sewage lagoons	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439105: Ramsey-----	40	Very limited Shallow depth to bedrock Too steep Seepage, bottom layer	1.00 1.00 1.00	Very limited Depth to hard bedrock Slope Seepage	1.00 1.00 1.00
2439107: Lonewood-----	85	Somewhat limited Bedrock lower in the soil Slow water movement Slope	0.50 0.46 0.04	Very limited Slope Seepage Depth to soft bedrock	1.00 0.53 0.08
2439108: Pope-----	50	Very limited Flooding Seepage, bottom layer Depth to saturated zone	1.00 1.00 0.08	Very limited Flooding Seepage	1.00 1.00
Philo-----	45	Very limited Flooding Depth to saturated zone Seepage, bottom layer Slow water movement	1.00 1.00 1.00 0.46	Very limited Flooding Seepage Depth to saturated zone	1.00 1.00 1.00
2439114: Shelocta-----	90	Very limited Slow water movement Slope	1.00 0.04	Very limited Slope Seepage	1.00 0.53
2439115: Shelocta-----	90	Very limited Slow water movement Too steep	1.00 1.00	Very limited Slope Seepage	1.00 0.53
2439116: Shelocta-----	90	Very limited Slow water movement Too steep	1.00 1.00	Very limited Slope Seepage	1.00 0.53
2439117: Water-----	100	Not rated		Not rated	
2439118: Wernock-----	90	Very limited Shallow depth to bedrock Slow water movement	1.00 0.46	Very limited Depth to soft bedrock Seepage Slope	1.00 0.53 0.18



# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 9.—Sewage Disposal—Continued

Map unit symbol and soil name	Pct. of map unit	Septic tank absorption fields		Sewage lagoons	
		Rating class and limiting features	Value	Rating class and limiting features	Value
2439119: Wernock-----	90	Very limited		Very limited	
		Shallow depth to bedrock	1.00	Depth to soft bedrock	1.00
		Slow water movement	0.46	Slope	1.00
		Slope	0.01	Seepage	0.53

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 10.—Source of Gravel and Sand

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The ratings given for the thickest layer are for the thickest layer above and excluding the bottom layer. The numbers in the value columns range from 0.00 to 0.99. The greater the value, the greater the likelihood that the bottom layer or thickest layer of the soil is a source of sand or gravel. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Gravel source		Sand source	
		Rating class	Value	Rating class	Value
523861: Ealy-----	60	Poor		Fair	
		Bottom layer	0.00	Thickest layer	0.00
		Thickest layer	0.00	Bottom layer	0.01
Craigsville-----	30	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
523880: Jefferson-----	50	Poor		Fair	
		Bottom layer	0.00	Thickest layer	0.00
		Thickest layer	0.00	Bottom layer	0.04
Varilla-----	20	Poor		Fair	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.03
Shelocta-----	15	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
523895: Ramsey-----	70	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Rock outcrop-----	20	Not rated		Not rated	
523909: Water-----	100	Not rated		Not rated	
2439088: Bethesda, unstable fill-----	75	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Mines pit, unstable fill-----	20	Not rated		Not rated	
2439089: Gilpin-----	90	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
2439090: Gilpin-----	90	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 10.—Source of Gravel and Sand—Continued

Map unit symbol and soil name	Pct. of map unit	Gravel source		Sand source	
		Rating class	Value	Rating class	Value
2439091: Gilpin-----	55	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Petros-----	35	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
2439092: Gilpin-----	65	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Petros-----	25	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
2439093: Gilpin-----	35	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Bouldin-----	30	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Petros-----	25	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
2439098: Lily-----	85	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
2439099: Lily-----	85	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
2439100: Lily-----	65	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Gilpin-----	30	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
2439101: Lily-----	60	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Gilpin-----	35	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 10.—Source of Gravel and Sand—Continued

Map unit symbol and soil name	Pct. of map unit	Gravel source		Sand source	
		Rating class	Value	Rating class	Value
2439102:					
Lily-----	55	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Gilpin-----	35	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
2439103:					
Lily-----	60	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Ramsey-----	30	Poor		Fair	
		Bottom layer	0.00	Thickest layer	0.00
		Thickest layer	0.00	Bottom layer	0.05
2439104:					
Lily-----	55	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Ramsey-----	40	Poor		Fair	
		Bottom layer	0.00	Thickest layer	0.00
		Thickest layer	0.00	Bottom layer	0.05
2439105:					
Lily-----	50	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
Ramsey-----	40	Poor		Fair	
		Bottom layer	0.00	Thickest layer	0.00
		Thickest layer	0.00	Bottom layer	0.05
2439107:					
Lonewood-----	85	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
2439108:					
Pope-----	50	Poor		Fair	
		Bottom layer	0.00	Thickest layer	0.00
		Thickest layer	0.00	Bottom layer	0.04
Philo-----	45	Poor		Fair	
		Bottom layer	0.00	Thickest layer	0.00
		Thickest layer	0.00	Bottom layer	0.02
2439114:					
Shelocta-----	90	Not rated		Poor	
				Bottom layer	0.00
				Thickest layer	0.00
2439115:					
Shelocta-----	90	Not rated		Poor	
				Bottom layer	0.00
				Thickest layer	0.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 10.—Source of Gravel and Sand—Continued

Map unit symbol and soil name	Pct. of map unit	Gravel source		Sand source	
		Rating class	Value	Rating class	Value
2439116: Shelocta-----	90	Not rated		Poor	
				Bottom layer	0.00
				Thickest layer	0.00
2439117: Water-----	100	Not rated		Not rated	
2439118: Wernock-----	90	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00
2439119: Wernock-----	90	Poor		Poor	
		Bottom layer	0.00	Bottom layer	0.00
		Thickest layer	0.00	Thickest layer	0.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 11.—Source of Reclamation Material, Roadfill, and Topsoil

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.00 to 0.99. The smaller the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Source of reclamation material		Roadfill source		Topsoil source	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
523861: Ealy-----	60	Fair Too acid Organic matter content low	 0.50 0.88	Good		Fair Too acid Rock fragments	 0.88 0.97
Craigsville-----	30	Poor Too sandy Organic matter content low Too acid	 0.04 0.12 0.50	Poor Cobble content Stones	 0.00 0.92	Poor Hard to reclaim (rock fragments) Rock fragments Too sandy	 0.00 0.00 0.04
523880: Jefferson-----	50	Fair Organic matter content low Too acid	 0.12 0.32	Poor Slope Cobble content	 0.00 0.68	Poor Slope Hard to reclaim (rock fragments) Rock fragments	 0.00 0.02 0.02
Varilla-----	20	Fair Organic matter content low Too acid Droughty	 0.12 0.12 0.41	Poor Slope Cobble content	 0.00 0.13	Poor Hard to reclaim (rock fragments) Slope Rock fragments	 0.00 0.00 0.00
Shelocta-----	15	Fair Organic matter content low Too acid	 0.12 0.50	Poor Slope Depth to bedrock	 0.00 0.58	Poor Slope Rock fragments Too acid	 0.00 0.03 0.88
523895: Ramsey-----	70	Poor Droughty Depth to bedrock Organic matter content low	 0.00 0.00 0.12	Poor Depth to bedrock Slope	 0.00 0.00	Poor Depth to bedrock Slope Rock fragments	 0.00 0.00 0.88
Rock outcrop-----	20	Not rated		Not rated		Not rated	
523909: Water-----	100	Not rated		Not rated		Not rated	
2439088: Bethesda, unstable fill-----	75	Fair Organic matter content low Too acid Droughty	 0.02 0.12 0.42	Poor Slope	 0.00	Poor Rock fragments Slope Hard to reclaim (rock fragments)	 0.00 0.00 0.50
Mines pit, unstable fill-----	20	Not rated		Not rated		Not rated	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 11.—Source of Reclamation Material, Roadfill, and Topsoil—Continued

Map unit symbol and soil name	Pct. of map unit	Source of reclamation material		Roadfill source		Topsoil source	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439089: Gilpin-----	90	Fair		Poor		Fair	
		Droughty	0.14	Depth to bedrock	0.00	Depth to bedrock	0.16
		Depth to bedrock	0.16	Low strength	0.00	Too clayey	0.70
		Too acid	0.50			Too acid	0.76
2439090: Gilpin-----	90	Fair		Poor		Poor	
		Droughty	0.14	Depth to bedrock	0.00	Slope	0.00
		Depth to bedrock	0.16	Low strength	0.00	Depth to bedrock	0.16
		Too acid	0.50	Slope	0.98	Too clayey	0.70
2439091: Gilpin-----	55	Fair		Poor		Poor	
		Droughty	0.14	Depth to bedrock	0.00	Slope	0.00
		Depth to bedrock	0.16	Slope	0.00	Depth to bedrock	0.16
		Too acid	0.50	Low strength	0.00	Too clayey	0.70
Petros-----	35	Poor		Poor		Poor	
		Droughty	0.00	Depth to bedrock	0.00	Rock fragments	0.00
		Depth to bedrock	0.00	Slope	0.00	Depth to bedrock	0.00
		Organic matter content low	0.12	Cobble content	0.95	Slope	0.00
2439092: Gilpin-----	65	Fair		Poor		Poor	
		Droughty	0.14	Depth to bedrock	0.00	Slope	0.00
		Depth to bedrock	0.16	Slope	0.00	Depth to bedrock	0.16
		Too acid	0.50	Low strength	0.00	Too clayey	0.70
Petros-----	25	Poor		Poor		Poor	
		Droughty	0.00	Depth to bedrock	0.00	Rock fragments	0.00
		Depth to bedrock	0.00	Slope	0.00	Depth to bedrock	0.00
		Organic matter content low	0.12	Cobble content	0.95	Slope	0.00
2439093: Gilpin-----	35	Fair		Poor		Poor	
		Droughty	0.14	Depth to bedrock	0.00	Slope	0.00
		Depth to bedrock	0.16	Slope	0.00	Depth to bedrock	0.16
		Too acid	0.50	Low strength	0.00	Too clayey	0.70
Bouldin-----	30	Poor		Poor		Poor	
		Stone content	0.00	Slope	0.00	Slope	0.00
		Organic matter content low	0.12	Stones	0.00	Rock fragments	0.00
		Too acid	0.54	Cobble content	0.39	Hard to reclaim (rock fragments)	0.00
Petros-----	25	Poor		Poor		Poor	
		Droughty	0.00	Depth to bedrock	0.00	Rock fragments	0.00
		Depth to bedrock	0.00	Slope	0.00	Depth to bedrock	0.00
		Organic matter content low	0.12	Cobble content	0.95	Slope	0.00
2439098: Lily-----	85	Fair		Poor		Fair	
		Organic matter content low	0.12	Depth to bedrock	0.00	Too clayey	0.53
		Too acid	0.50	Low strength	0.00	Depth to bedrock	0.54
		Droughty	0.56			Too acid	0.59

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 11.—Source of Reclamation Material, Roadfill, and Topsoil—Continued

Map unit symbol and soil name	Pct. of map unit	Source of reclamation material		Roadfill source		Topsoil source	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439099: Lily-----	85	Fair		Poor		Poor	
		Organic matter content low	0.12	Depth to bedrock	0.00	Slope	0.00
		Too acid	0.50	Low strength	0.00	Too clayey	0.53
		Droughty	0.56	Slope	0.98	Depth to bedrock	0.54
2439100: Lily-----	65	Fair		Poor		Fair	
		Organic matter content low	0.12	Depth to bedrock	0.00	Too clayey	0.53
		Too acid	0.50	Low strength	0.00	Depth to bedrock	0.54
		Droughty	0.56			Too acid	0.59
Gilpin-----	30	Fair		Poor		Fair	
		Droughty	0.14	Depth to bedrock	0.00	Depth to bedrock	0.16
		Depth to bedrock	0.16	Low strength	0.00	Too clayey	0.70
		Too acid	0.50			Too acid	0.76
2439101: Lily-----	60	Fair		Poor		Poor	
		Organic matter content low	0.12	Depth to bedrock	0.00	Slope	0.00
		Too acid	0.50	Low strength	0.00	Too clayey	0.53
		Droughty	0.56	Slope	0.98	Depth to bedrock	0.54
Gilpin-----	35	Fair		Poor		Poor	
		Droughty	0.14	Depth to bedrock	0.00	Slope	0.00
		Depth to bedrock	0.16	Low strength	0.00	Depth to bedrock	0.16
		Too acid	0.50	Slope	0.98	Too clayey	0.70
2439102: Lily-----	55	Fair		Poor		Poor	
		Organic matter content low	0.12	Depth to bedrock	0.00	Slope	0.00
		Too acid	0.50	Slope	0.00	Too clayey	0.53
		Droughty	0.56	Low strength	0.00	Depth to bedrock	0.54
Gilpin-----	35	Fair		Poor		Poor	
		Droughty	0.14	Depth to bedrock	0.00	Slope	0.00
		Depth to bedrock	0.16	Slope	0.00	Depth to bedrock	0.16
		Too acid	0.50	Low strength	0.00	Too clayey	0.70
2439103: Lily-----	60	Fair		Poor		Fair	
		Organic matter content low	0.12	Depth to bedrock	0.00	Too clayey	0.53
		Too acid	0.50	Low strength	0.00	Depth to bedrock	0.54
		Droughty	0.56			Too acid	0.59
Ramsey-----	30	Poor		Poor		Poor	
		Droughty	0.00	Depth to bedrock	0.00	Depth to bedrock	0.00
		Depth to bedrock	0.00			Rock fragments	0.08
		Organic matter content low	0.12			Slope	0.96



# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 11.—Source of Reclamation Material, Roadfill, and Topsoil—Continued

Map unit symbol and soil name	Pct. of map unit	Source of reclamation material		Roadfill source		Topsoil source	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439104: Lily-----	55	Fair		Poor		Poor	
		Organic matter content low	0.12	Depth to bedrock	0.00	Slope	0.00
		Too acid	0.50	Low strength	0.00	Too clayey	0.53
		Droughty	0.56	Slope	0.98	Depth to bedrock	0.54
Ramsey-----	40	Poor		Poor		Poor	
		Droughty	0.00	Depth to bedrock	0.00	Depth to bedrock	0.00
		Depth to bedrock	0.00	Slope	0.98	Slope	0.00
		Organic matter content low	0.12			Rock fragments	0.08
2439105: Lily-----	50	Fair		Poor		Poor	
		Organic matter content low	0.12	Depth to bedrock	0.00	Slope	0.00
		Too acid	0.50	Slope	0.00	Too clayey	0.53
		Droughty	0.56	Low strength	0.00	Depth to bedrock	0.54
Ramsey-----	40	Poor		Poor		Poor	
		Droughty	0.00	Depth to bedrock	0.00	Depth to bedrock	0.00
		Depth to bedrock	0.00	Slope	0.00	Slope	0.00
		Organic matter content low	0.12			Rock fragments	0.08
2439107: Lonewood-----	85	Fair		Poor		Fair	
		Organic matter content low	0.12	Low strength	0.00	Slope	0.96
		Too acid	0.50	Depth to bedrock	0.92	Too acid	0.98
		Water erosion	0.99				
2439108: Pope-----	50	Fair		Good		Poor	
		Organic matter content low	0.12			Hard to reclaim (rock fragments)	0.00
		Too acid	0.54			Too acid	0.98
		Water erosion	0.99				
Philo-----	45	Fair		Fair		Fair	
		Organic matter content low	0.12	Wetness depth	0.76	Hard to reclaim (rock fragments)	0.74
		Too acid	0.54			Wetness depth	0.76
		Water erosion	0.99			Too acid	0.98
2439114: Shelocta-----	90	Fair		Poor		Poor	
		Organic matter content low	0.12	Low strength	0.00	Rock fragments	0.00
		Too acid	0.54			Too clayey	0.57
		Too clayey	0.98			Hard to reclaim (rock fragments)	0.88
2439115: Shelocta-----	90	Fair		Poor		Poor	
		Organic matter content low	0.12	Low strength	0.00	Slope	0.00
		Too acid	0.54			Rock fragments	0.00
		Too clayey	0.98			Too clayey	0.57

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 11.—Source of Reclamation Material, Roadfill, and Topsoil—Continued

Map unit symbol and soil name	Pct. of map unit	Source of reclamation material		Roadfill source		Topsoil source	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439116: Shelocta-----	90	Fair		Poor		Poor	
		Organic matter content low	0.12	Slope	0.00	Slope	0.00
		Too acid	0.54	Low strength	0.00	Rock fragments	0.00
		Too clayey	0.98			Too clayey	0.57
2439117: Water-----	100	Not rated		Not rated		Not rated	
2439118: Wernock-----	90	Fair		Poor		Fair	
		Organic matter content low	0.12	Depth to bedrock	0.00	Too clayey	0.53
		Too acid	0.50	Low strength	0.00	Too acid	0.88
		Water erosion	0.99			Depth to bedrock	0.90
2439119: Wernock-----	90	Fair		Poor		Fair	
		Organic matter content low	0.12	Depth to bedrock	0.00	Too clayey	0.53
		Too acid	0.50	Low strength	0.00	Too acid	0.88
		Depth to bedrock	0.90			Depth to bedrock	0.90

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 12.—Ponds and Embankments

(Onsite investigation may be needed to validate the interpretations in this table and to confirm the identity of the soil on a given site. The numbers in the value columns range from 0.01 to 1.00. The larger the value, the greater the limitation. See text for further explanation of ratings in this table)

Map unit symbol and soil name	Pct. of map unit	Pond reservoir areas		Embankments, dikes, and levees		Aquifer-fed excavated ponds	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
523861: Ealy-----	60	Very limited Seepage	1.00	Not limited		Very limited Depth to water	1.00
Craigsville-----	30	Very limited Seepage	1.00	Very limited Seepage Large stones	1.00 1.00	Very limited Depth to water	1.00
523880: Jefferson-----	50	Very limited Seepage Slope	1.00 1.00	Somewhat limited Large stones	0.03	Very limited Depth to water	1.00
Varilla-----	20	Very limited Seepage Slope	1.00 1.00	Somewhat limited Large stones	0.32	Very limited Depth to water	1.00
Shelocta-----	15	Very limited Slope Seepage	1.00 0.72	Very limited Piping	1.00	Very limited Depth to water	1.00
523895: Ramsey-----	70	Very limited Slope Depth to bedrock	1.00 1.00	Very limited Thin layer	1.00	Very limited Depth to water	1.00
Rock outcrop-----	20	Not rated		Not rated		Not rated	
523909: Water-----	100	Not rated		Not rated		Not rated	
2439088: Bethesda, unstable fill-----	75	Very limited Slope Seepage	1.00 0.04	Not limited		Very limited Depth to water	1.00
Mines pit, unstable fill-----	20	Not rated		Not rated		Not rated	
2439089: Gilpin-----	90	Very limited Slope Seepage Depth to bedrock	1.00 0.72 0.26	Somewhat limited Piping Thin layer	0.01 0.96	Very limited Depth to water	1.00
2439090: Gilpin-----	90	Very limited Slope Seepage Depth to bedrock	1.00 0.72 0.26	Somewhat limited Piping Thin layer	0.01 0.96	Very limited Depth to water	1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 12.—Ponds and Embankments—Continued

Map unit symbol and soil name	Pct. of map unit	Pond reservoir areas		Embankments, dikes, and levees		Aquifer-fed excavated ponds	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439091: Gilpin-----	55	Very limited Slope Seepage Depth to bedrock	 1.00 0.72 0.26	Somewhat limited Thin layer Piping	 0.96 0.01	Very limited Depth to water	 1.00
Petros-----	35	Very limited Slope Depth to bedrock	 1.00 0.61	Very limited Thin layer Seepage	 1.00 0.20	Very limited Depth to water	 1.00
2439092: Gilpin-----	65	Very limited Slope Seepage Depth to bedrock	 1.00 0.72 0.26	Somewhat limited Thin layer Piping	 0.96 0.01	Very limited Depth to water	 1.00
Petros-----	25	Very limited Slope Depth to bedrock	 1.00 0.61	Very limited Thin layer Seepage	 1.00 0.20	Very limited Depth to water	 1.00
2439093: Gilpin-----	35	Very limited Slope Seepage Depth to bedrock	 1.00 0.72 0.26	Somewhat limited Thin layer Piping	 0.96 0.01	Very limited Depth to water	 1.00
Bouldin-----	30	Very limited Seepage Slope	 1.00 1.00	Somewhat limited Large stones	 0.90	Very limited Depth to water	 1.00
Petros-----	25	Very limited Slope Depth to bedrock	 1.00 0.61	Very limited Thin layer Seepage	 1.00 0.20	Very limited Depth to water	 1.00
2439098: Lily-----	85	Very limited Seepage Slope Depth to bedrock	 1.00 1.00 0.86	Somewhat limited Thin layer	 0.86	Very limited Depth to water	 1.00
2439099: Lily-----	85	Very limited Seepage Slope Depth to bedrock	 1.00 1.00 0.86	Somewhat limited Thin layer	 0.86	Very limited Depth to water	 1.00
2439100: Lily-----	65	Very limited Seepage Slope Depth to bedrock	 1.00 1.00 0.86	Somewhat limited Thin layer	 0.86	Very limited Depth to water	 1.00
Gilpin-----	30	Very limited Slope Seepage Depth to bedrock	 1.00 0.72 0.26	Somewhat limited Thin layer Piping	 0.96 0.01	Very limited Depth to water	 1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 12.—Ponds and Embankments—Continued

Map unit symbol and soil name	Pct. of map unit	Pond reservoir areas		Embankments, dikes, and levees		Aquifer-fed excavated ponds	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439101: Lily-----	60	Very limited Seepage Slope Depth to bedrock	 1.00 1.00 0.86	Somewhat limited Thin layer	 0.86	Very limited Depth to water	 1.00
Gilpin-----	35	Very limited Slope Seepage Depth to bedrock	 1.00 0.72 0.26	Somewhat limited Thin layer Piping	 0.96 0.01	Very limited Depth to water	 1.00
2439102: Lily-----	55	Very limited Seepage Slope Depth to bedrock	 1.00 1.00 0.86	Somewhat limited Thin layer	 0.86	Very limited Depth to water	 1.00
Gilpin-----	35	Very limited Slope Seepage Depth to bedrock	 1.00 0.72 0.26	Somewhat limited Thin layer Piping	 0.96 0.01	Very limited Depth to water	 1.00
2439103: Lily-----	60	Very limited Seepage Slope Depth to bedrock	 1.00 1.00 0.86	Somewhat limited Thin layer	 0.86	Very limited Depth to water	 1.00
Ramsey-----	30	Very limited Depth to bedrock Slope	 1.00 1.00	Very limited Thin layer	 1.00	Very limited Depth to water	 1.00
2439104: Lily-----	55	Very limited Seepage Slope Depth to bedrock	 1.00 1.00 0.86	Somewhat limited Thin layer	 0.86	Very limited Depth to water	 1.00
Ramsey-----	40	Very limited Slope Depth to bedrock	 1.00 1.00	Very limited Thin layer	 1.00	Very limited Depth to water	 1.00
2439105: Lily-----	50	Very limited Seepage Slope Depth to bedrock	 1.00 1.00 0.86	Somewhat limited Thin layer	 0.86	Very limited Depth to water	 1.00
Ramsey-----	40	Very limited Slope Depth to bedrock	 1.00 1.00	Very limited Thin layer	 1.00	Very limited Depth to water	 1.00
2439107: Lonewood-----	85	Very limited Slope Seepage	 1.00 0.72	Somewhat limited Thin layer Piping	 0.02 0.01	Very limited Depth to water	 1.00

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 12.—Ponds and Embankments—Continued

Map unit symbol and soil name	Pct. of map unit	Pond reservoir areas		Embankments, dikes, and levees		Aquifer-fed excavated ponds	
		Rating class and limiting features	Value	Rating class and limiting features	Value	Rating class and limiting features	Value
2439108: Pope-----	50	Very limited Seepage	1.00	Not limited		Very limited Depth to water	1.00
Philo-----	45	Very limited Seepage	1.00	Somewhat limited Depth to saturated zone	0.95	Very limited Unstable excavation walls Depth to saturated zone	1.00 0.02
2439114: Shelocta-----	90	Very limited Slope Seepage	1.00 0.72	Somewhat limited Piping	0.01	Very limited Depth to water	1.00
2439115: Shelocta-----	90	Very limited Slope Seepage	1.00 0.72	Somewhat limited Piping	0.01	Very limited Depth to water	1.00
2439116: Shelocta-----	90	Very limited Slope Seepage	1.00 0.72	Somewhat limited Piping	0.01	Very limited Depth to water	1.00
2439117: Water-----	100	Not rated		Not rated		Not rated	
2439118: Wernock-----	90	Somewhat limited Seepage Depth to bedrock Slope	0.72 0.04 0.02	Somewhat limited Thin layer Piping	0.70 0.01	Very limited Depth to water	1.00
2439119: Wernock-----	90	Very limited Slope Seepage Depth to bedrock	1.00 0.72 0.04	Somewhat limited Thin layer Piping	0.70 0.01	Very limited Depth to water	1.00

Table 13.—Engineering Properties

(Absence of an entry indicates that data were not estimated)

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	In				Pct	Pct					Pct	
523861: Ealy-----	0-10	Fine sandy loam	SC-SM, SM, CL-ML, ML	A-4, A-2	0	0-3	85-100	75-100	55-95	30-70	0-30	NP-8
	10-60	Fine sandy loam, loamy fine sand	SC-SM, SM, CL-ML, ML	A-4, A-2	0	0	85-100	75-100	50-95	25-70	0-30	NP-8
Craigsville-----	0-3	Cobbly fine sandy loam	SC, SM, CL-ML, ML	A-4, A-2	0-5	25-50	80-95	75-95	50-80	25-60	0-25	NP-10
	3-21	Gravelly sandy loam, cobbly loam, very cobbly sandy loam	SC, SM, GC, GM	A-4, A-2, A-1	0-20	25-60	50-80	30-65	25-60	15-40	0-25	NP-10
	21-60	Extremely cobbly loamy sand, very gravelly sandy loam, very cobbly sandy loam	GM, GP-GM, GC, GC-GM	A-2, A-1	0-20	35-75	35-55	30-50	20-45	10-25	0-25	NP-8
523880: Jefferson-----	0-7	Cobbly loam	ML, SM, CL, GM	A-4, A-2	0-10	10-35	65-90	60-90	50-80	30-60	20-35	2-10
	7-56	Cobbly loam, cobbly clay loam, gravelly sandy clay loam	SC, SM, CL, ML	A-6, A-4, A-2	0-10	10-35	75-90	70-90	50-80	30-70	20-40	2-15
	56-60	Cobbly loam, cobbly clay loam, very gravelly sandy loam	ML, SM, GC-GM, GM	A-4, A-2, A-1	0-10	10-35	55-75	50-75	35-70	20-60	20-35	2-10
Varilla-----	0-7	Very cobbly sandy loam	SM, SC-SM, SC	A-6, A-4, A-2	0-10	20-40	70-90	70-90	50-80	25-50	0-30	NP-15
	7-44	Very cobbly sandy loam, very gravelly fine sandy loam, very gravelly loam	SM, SC-SM, SC	A-6, A-4, A-2	0-10	20-40	70-90	70-90	50-80	25-50	0-30	NP-15
	44-60	Very cobbly sandy loam, extremely cobbly loamy sand, extremely gravelly loamy sand	SC-SM, SM, GC-GM, GM	A-2	0-10	30-50	60-80	55-80	50-70	10-35	0-25	NP-10
Shelocta-----	0-3	Loam	ML, CL-ML	A-4	0-2	0-5	80-95	75-95	60-95	55-90	0-35	NP-10
	3-50	Silty clay loam, silt loam, channery silty clay loam	GC, SC, CL, CL-ML	A-6, A-4	0-5	0-10	55-95	50-95	45-95	40-90	25-40	4-15
	50-60	Weathered bedrock			---	---	---	---	---	---	---	---

Table 13.-Engineering Properties-Continued

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	<u>In</u>				<u>Pct</u>	<u>Pct</u>					<u>Pct</u>	
523895: Ramsey-----	0-2	Loam	SC-SM, SM, CL-ML, ML	A-4, A-2	0	0-10	85-100	75-95	60-75	30-70	0-25	NP-7
	2-18	Loam, sandy loam, fine sandy loam	SC-SM, SM, CL-ML, ML	A-4, A-2	0	0-10	85-100	75-95	60-77	30-70	0-25	NP-7
	18-25	Unweathered bedrock			---	---	---	---	---	---	---	---
2439088: Bethesda, unstable fill--	0-2	Channery loam	GC-GM, CL-ML, SC	A-6, A-4	0	0	56-100	25-100	20-95	15-75	20-40	5-20
	2-45	Very channery silty clay loam, extremely channery silty clay loam, very channery clay loam, extremely channery clay loam, very channery silt loam, extremely channery silt loam, very channery loam, extremely channery loam	GC-GM, GC, SC	A-7, A-6, A-2	0-10	0-20	56-69	18-44	15-40	10-40	25-50	10-30
	45-60	Channery silty clay loam, very channery silty clay loam, extremely channery silty clay loam, channery silt loam, very channery silt loam, extremely channery silt loam, channery clay loam, very channery clay loam, extremely channery clay loam, channery loam, very channery loam, extremely channery loam	SC, GC, GC-GM, GM	A-6, A-7, A-2, A-4	0	0-25	56-88	18-74	15-70	10-65	20-50	5-30



Table 13.-Engineering Properties-Continued

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	In				Pct	Pct					Pct	
2439089: Gilpin-----	0-6	Silt loam, loam	CL-ML, CL	A-6, A-4	0	0-5	88-97	74-92	65-90	50-80	25-45	5-20
	6-21	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	CL	A-7, A-6	0	0-10	90-97	78-92	65-90	50-85	30-45	10-25
	21-25	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	SC, GC, CL	A-6	0	0-15	86-97	66-92	55-90	45-85	25-50	10-30
	25-35	Weathered bedrock			---	---	---	---	---	---	---	---
2439090: Gilpin-----	0-6	Silt loam, loam	CL-ML, CL	A-6, A-4	0	0-5	88-97	74-92	65-90	50-80	25-45	5-20
	6-21	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	CL	A-7, A-6	0	0-10	90-97	78-92	65-90	50-85	30-45	10-25
	21-25	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	SC, GC, CL	A-6	0	0-15	86-97	66-92	55-90	45-85	25-50	10-30
	25-35	Weathered bedrock			---	---	---	---	---	---	---	---
2439091: Gilpin-----	0-6	Silt loam, loam	CL-ML, CL	A-6, A-4	0	0-5	88-97	74-92	65-90	50-80	25-45	5-20
	6-21	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	CL	A-7, A-6	0	0-10	90-97	78-92	65-90	50-85	30-45	10-25
	21-25	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	SC, GC, CL	A-6	0	0-15	86-97	66-92	55-90	45-85	25-50	10-30
	25-35	Weathered bedrock			---	---	---	---	---	---	---	---

Table 13.—Engineering Properties—Continued

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	In				Pct	Pct					Pct	
2439091: Petros-----	0-2	Channery silt loam, channery loam	SC, CL-ML, CL	A-6, A-4	0	0-10	78-88	53-74	40-70	35-65	20-40	5-20
	2-8	Very channery silty clay loam, extremely channery silty clay loam, very channery silt loam, extremely channery silt loam	SC, GC-GM, GC	A-6, A-2	0	0-25	56-75	6-44	5-40	0-40	30-45	10-25
	8-16	Very channery silty clay loam, extremely channery silty clay loam, very channery silt loam, extremely channery silt loam	SW, SC, GC-GM, GC	A-2	0	0-30	50-75	0-44	0-40	0-35	20-45	5-25
	16-26	Weathered bedrock			---	---	---	---	---	---	---	---
2439092: Gilpin-----	0-6	Silt loam, loam	CL-ML, CL	A-6, A-4	0	0-5	88-97	74-92	65-90	50-80	25-45	5-20
	6-21	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	CL	A-7, A-6	0	0-10	90-97	78-92	65-90	50-85	30-45	10-25
	21-25	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	SC, GC, CL	A-6	0	0-15	86-97	66-92	55-90	45-85	25-50	10-30
	25-35	Weathered bedrock			---	---	---	---	---	---	---	---
Petros-----	0-2	Channery silt loam, channery loam	SC, CL-ML, CL	A-6, A-4	0	0-10	78-88	53-74	40-70	35-65	20-40	5-20
	2-8	Very channery silty clay loam, extremely channery silty clay loam, very channery silt loam, extremely channery silt loam	SC, GC-GM, GC	A-6, A-2	0	0-25	56-75	6-44	5-40	0-40	30-45	10-25
	8-16	Very channery silty clay loam, extremely channery silty clay loam, very channery silt loam, extremely channery silt loam	SW, SC, GC-GM, GC	A-2	0	0-30	50-75	0-44	0-40	0-35	20-45	5-25
	16-26	Weathered bedrock			---	---	---	---	---	---	---	---

Table 13.—Engineering Properties—Continued

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	In				Pct	Pct					Pct	
2439093:												
Gilpin-----	0-6	Silt loam, loam	CL-ML, CL	A-6, A-4	0	0-5	88-97	74-92	65-90	50-80	25-45	5-20
	6-21	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	CL	A-7, A-6	0	0-10	90-97	78-92	65-90	50-85	30-45	10-25
	21-25	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	SC, GC, CL	A-6	0	0-15	86-97	66-92	55-90	45-85	25-50	10-30
	25-35	Weathered bedrock			---	---	---	---	---	---	---	---
Bouldin-----	0-2	Flaggy loam, flaggy fine sandy loam	GM, ML, SC-SM, SM, SC, GC-GM	A-4, A-2	0-20	5-25	62-88	31-80	20-75	10-60	20-45	5-20
	2-17	Channery loam, very channery loam, extremely channery loam, channery fine sandy loam, very channery fine sandy loam, extremely channery fine sandy loam	SC, SC-SM, GC-GM	A-6, A-4, A-2	0-20	5-25	62-88	31-80	20-75	10-60	20-40	5-20
	17-80	Very channery clay loam, extremely channery clay loam, very flaggy clay loam, extremely flaggy clay loam, flaggy loam, extremely channery loam, very flaggy loam, extremely flaggy loam	SC, GC	A-6, A-4, A-2	0-30	5-40	62-88	31-80	25-75	20-65	20-45	5-25

Table 13.-Engineering Properties-Continued

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	In				Pct	Pct					Pct	
2439093: Petros-----	0-2	Channery silt loam, channery loam	SC, CL-ML, CL	A-6, A-4	0	0-10	78-88	53-74	40-70	35-65	20-40	5-20
	2-8	Very channery silty clay loam, extremely channery silty clay loam, very channery silt loam, extremely channery silt loam	SC, GC-GM, GC	A-6, A-2	0	0-25	56-75	6-44	5-40	0-40	30-45	10-25
	8-16	Very channery silty clay loam, extremely channery silty clay loam, very channery silt loam, extremely channery silt loam	SW, SC, GC-GM, GC	A-2	0	0-30	50-75	0-44	0-40	0-35	20-45	5-25
	16-26	Weathered bedrock			---	---	---	---	---	---	---	---
2439098: Lily-----	0-3	Loam	ML, CL-ML, CL	A-6, A-4	0	0-10	80-100	58-100	50-95	35-75	20-45	5-20
	3-30	Clay loam, channery clay loam, loam, channery loam	SC, CL	A-6	0	0-15	80-100	58-100	50-100	35-80	25-45	10-25
	30-37	Unweathered bedrock			---	---	---	---	---	---	---	---
2439099: Lily-----	0-3	Loam	ML, CL-ML, CL	A-6, A-4	0	0-10	80-100	58-100	50-95	35-75	20-45	5-20
	3-30	Clay loam, channery clay loam, loam, channery loam	SC, CL	A-6	0	0-15	80-100	58-100	50-100	35-80	25-45	10-25
	30-37	Unweathered bedrock			---	---	---	---	---	---	---	---
2439100: Lily-----	0-3	Loam	ML, CL-ML, CL	A-6, A-4	0	0-10	80-100	58-100	50-95	35-75	20-45	5-20
	3-30	Clay loam, channery clay loam, loam, channery loam	SC, CL	A-6	0	0-15	80-100	58-100	50-100	35-80	25-45	10-25
	30-37	Unweathered bedrock			---	---	---	---	---	---	---	---

Table 13.-Engineering Properties-Continued

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	In				Pct	Pct					Pct	
2439100: Gilpin-----	0-6	Silt loam, loam	CL-ML, CL	A-6, A-4	0	0-5	88-97	74-92	65-90	50-80	25-45	5-20
	6-21	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	CL	A-7, A-6	0	0-10	90-97	78-92	65-90	50-85	30-45	10-25
	21-25	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	SC, GC, CL	A-6	0	0-15	86-97	66-92	55-90	45-85	25-50	10-30
	25-35	Weathered bedrock			---	---	---	---	---	---	---	---
2439101: Lily-----	0-3	Loam	ML, CL-ML, CL	A-6, A-4	0	0-10	80-100	58-100	50-95	35-75	20-45	5-20
	3-30	Clay loam, channery clay loam, loam, channery loam	SC, CL	A-6	0	0-15	80-100	58-100	50-100	35-80	25-45	10-25
	30-37	Unweathered bedrock			---	---	---	---	---	---	---	---
Gilpin-----	0-6	Silt loam, loam	CL-ML, CL	A-6, A-4	0	0-5	88-97	74-92	65-90	50-80	25-45	5-20
	6-21	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	CL	A-7, A-6	0	0-10	90-97	78-92	65-90	50-85	30-45	10-25
	21-25	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	SC, GC, CL	A-6	0	0-15	86-97	66-92	55-90	45-85	25-50	10-30
	25-35	Weathered bedrock			---	---	---	---	---	---	---	---
2439102: Lily-----	0-3	Loam	ML, CL-ML, CL	A-6, A-4	0	0-10	80-100	58-100	50-95	35-75	20-45	5-20
	3-30	Clay loam, channery clay loam, loam, channery loam	SC, CL	A-6	0	0-15	80-100	58-100	50-100	35-80	25-45	10-25
	30-37	Unweathered bedrock			---	---	---	---	---	---	---	---

Table 13.—Engineering Properties—Continued

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	In				Pct	Pct					Pct	
2439102: Gilpin-----	0-6	Silt loam, loam	CL-ML, CL	A-6, A-4	0	0-5	88-97	74-92	65-90	50-80	25-45	5-20
	6-21	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	CL	A-7, A-6	0	0-10	90-97	78-92	65-90	50-85	30-45	10-25
	21-25	Silty clay loam, channery silty clay loam, silt loam, channery silt loam, loam, channery loam	SC, GC, CL	A-6	0	0-15	86-97	66-92	55-90	45-85	25-50	10-30
	25-35	Weathered bedrock			---	---	---	---	---	---	---	---
2439103: Lily-----	0-3	Loam	ML, CL-ML, CL	A-6, A-4	0	0-10	80-100	58-100	50-95	35-75	20-45	5-20
	3-30	Clay loam, channery clay loam, loam, channery loam	SC, CL	A-6	0	0-15	80-100	58-100	50-100	35-80	25-45	10-25
	30-37	Unweathered bedrock			---	---	---	---	---	---	---	---
Ramsey-----	0-4	Loam	SM, CL, SC-SM, CL-ML, ML	A-4, A-2	0	0-10	69-97	44-92	40-85	30-70	20-40	5-15
	4-10	Loam, channery loam, fine sandy loam, channery fine sandy loam, sandy loam, channery sandy loam	SC, SC-SM, CL-ML	A-4, A-2	0	0-15	69-97	44-92	25-85	10-70	20-35	5-15
	10-16	Loam, channery loam, fine sandy loam, channery fine sandy loam, sandy loam, channery sandy loam	SC, CL-ML, SC-SM	A-2, A-1, A-4	0	0-15	69-97	44-92	35-85	15-70	20-35	5-15
	16-18	Unweathered bedrock			---	---	---	---	---	---	---	---
2439104: Lily-----	0-3	Loam	ML, CL-ML, CL	A-6, A-4	0	0-10	80-100	58-100	50-95	35-75	20-45	5-20
	3-30	Clay loam, channery clay loam, loam, channery loam	SC, CL	A-6	0	0-15	80-100	58-100	50-100	35-80	25-45	10-25
	30-37	Unweathered bedrock			---	---	---	---	---	---	---	---

Table 13.—Engineering Properties—Continued

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	In				Pct	Pct					Pct	
2439104: Ramsey-----	0-4	Loam	SC-SM, SM, ML, CL, CL-ML	A-4, A-2	0	0-10	69-97	44-92	40-85	30-70	20-40	5-15
	4-10	Loam, channery loam, fine sandy loam, channery fine sandy loam, sandy loam, channery sandy loam	SC, SC-SM, CL-ML	A-4, A-2	0	0-15	69-97	44-92	25-85	10-70	20-35	5-15
	10-16	Loam, channery loam, fine sandy loam, channery fine sandy loam, sandy loam, channery sandy loam	SC-SM, SC, CL-ML	A-2, A-1, A-4	0	0-15	69-97	44-92	35-85	15-70	20-35	5-15
	16-18	Unweathered bedrock			---	---	---	---	---	---	---	---
2439105: Lily-----	0-3	Loam	ML, CL-ML, CL	A-6, A-4	0	0-10	80-100	58-100	50-95	35-75	20-45	5-20
	3-30	Clay loam, channery clay loam, loam, channery loam	SC, CL	A-6	0	0-15	80-100	58-100	50-100	35-80	25-45	10-25
	30-37	Unweathered bedrock			---	---	---	---	---	---	---	---
Ramsey-----	0-4	Loam	SC-SM, SM, ML, CL, CL-ML	A-4, A-2	0	0-10	69-97	44-92	40-85	30-70	20-40	5-15
	4-10	Loam, channery loam, fine sandy loam, channery fine sandy loam, sandy loam, channery sandy loam	SC, SC-SM, CL-ML	A-4, A-2	0	0-15	69-97	44-92	25-85	10-70	20-35	5-15
	10-16	Loam, channery loam, fine sandy loam, channery fine sandy loam, sandy loam, channery sandy loam	SC-SM, SC, CL-ML	A-2, A-1, A-4	0	0-15	69-97	44-92	35-85	15-70	20-35	5-15
	16-18	Unweathered bedrock			---	---	---	---	---	---	---	---
2439107: Lonewood-----	0-8	Silt loam	ML, CL-ML, CL	A-6, A-4	0	0	97-100	92-100	80-100	65-90	25-45	5-20
	8-28	Silty clay loam, silt loam, clay loam, loam	CL	A-6, A-7	0	0	97-100	92-100	75-100	63-95	25-45	10-25
	28-55	Silty clay loam, clay loam	CL	A-7, A-6	0	0	95-100	83-100	75-100	60-95	35-50	20-30
	55-65	Weathered bedrock			---	---	---	---	---	---	---	---

Table 13.—Engineering Properties—Continued

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	In				Pct	Pct					Pct	
2439108: Pope-----	0-8	Silt loam, loam	ML, SM, CL, CL-ML	A-6, A-4	0	0-10	80-100	55-100	45-100	35-90	20-45	5-20
	8-43	Silt loam, loam, fine sandy loam	SM, CL, SC-SM, CL-ML, ML	A-4, A-2	0	0	80-100	55-100	40-100	25-90	15-40	NP-20
	43-60	Fine sandy loam, gravelly fine sandy loam, very gravelly fine sandy loam, sandy loam, gravelly sandy loam, very gravelly sandy loam	SM, SC, SC-SM, GM, ML	A-4, A-2, A-1	0	0-20	62-100	18-100	10-85	5-55	15-30	NP-15
Philo-----	0-6	Silt loam, loam	ML, SM, CL, CL-ML	A-4, A-6	0	0-10	88-100	74-100	60-100	45-90	20-45	5-20
	6-36	Silt loam, loam, fine sandy loam	SM, CL, CL-ML, ML	A-4	0	0-15	88-100	74-100	55-100	35-90	15-40	NP-20
	36-60	Gravelly fine sandy loam, very gravelly fine sandy loam, gravelly sandy loam, very gravelly sandy loam	SM, SC-SM, ML, CL-ML, GM	A-4, A-2	0	0-30	62-100	18-100	13-85	5-55	15-30	NP-10
2439114: Shelocta-----	0-10	Silt loam, loam	CL, ML, CL-ML	A-6, A-4	0	0	80-100	55-100	45-100	35-90	20-45	5-20
	10-65	Silty clay loam, channery silty clay loam, silt loam, channery silt loam	CL	A-6	0	0	62-100	18-100	15-100	15-95	25-50	10-30
	65-75	Weathered bedrock			---	---	---	---	---	---	---	---
2439115: Shelocta-----	0-10	Silt loam, loam	CL, ML, CL-ML	A-6, A-4	0	0	80-100	55-100	45-100	35-90	20-45	5-20
	10-65	Silty clay loam, channery silty clay loam, silt loam, channery silt loam	CL	A-6	0	0	62-100	18-100	15-100	15-95	25-50	10-30
	65-75	Weathered bedrock			---	---	---	---	---	---	---	---



Table 13.—Engineering Properties—Continued

Map unit symbol and soil name	Depth	USDA texture	Classification		Fragments		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	>10 in	3-10 in	4	10	40	200		
	In				Pct	Pct					Pct	
2439116: Shelocta-----	0-10	Silt loam, loam	CL, ML, CL-ML	A-6, A-4	0	0	80-100	55-100	45-100	35-90	20-45	5-20
	10-65	Silty clay loam, channery silty clay loam, silt loam, channery silt loam	CL	A-6	0	0	62-100	18-100	15-100	15-95	25-50	10-30
	65-75	Weathered bedrock			---	---	---	---	---	---	---	---
2439118: Wernock-----	0-12	Silt loam	ML, CL	A-6, A-4	0	0	95-100	83-100	75-100	60-95	25-45	5-20
	12-27	Silt loam, silty clay loam	CL	A-6	0	0	95-100	83-100	75-100	65-100	25-50	10-30
	27-35	Silty clay loam	CL	A-7, A-6	0	0	92-100	80-100	75-100	65-95	35-50	20-30
	35-45	Weathered bedrock			---	---	---	---	---	---	---	---
2439119: Wernock-----	0-12	Silt loam	ML, CL	A-6, A-4	0	0	95-100	83-100	75-100	60-95	25-45	5-20
	12-27	Silt loam, silty clay loam	CL	A-6	0	0	95-100	83-100	75-100	65-100	25-50	10-30
	27-35	Silty clay loam	CL	A-7, A-6	0	0	92-100	80-100	75-100	65-95	35-50	20-30
	35-45	Weathered bedrock			---	---	---	---	---	---	---	---

Table 14.—Physical Soil Properties

(Sand, silt, and clay values are shown either as a range or as a representative value. Absence of an entry indicates that data were not estimated)

Map unit symbol and soil name	Depth	Sand	Silt	Clay	Moist bulk density	Permeability (Ksat)	Available water capacity	Shrink- swell potential	Organic matter
	In	Pct	Pct	Pct	g/cc	In/hr	In/in	Pct	Pct
523861:									
Ealy-----	0-10	65	20	5-18	1.40-1.60	2.0-6.0	0.14-0.18	0.0-2.9	1.0-3.0
	10-60	69	16	5-18	1.40-1.65	2.0-6.0	0.12-0.18	0.0-2.9	0.5-1.0
Craigsville----	0-3	68	20	5-15	1.20-1.40	2.0-20.0	0.07-0.15	0.0-2.9	1.0-3.0
	3-21	68	20	5-15	1.30-1.60	2.0-20.0	0.06-0.15	0.0-2.9	0.0-0.5
	21-60	83	9	5-10	1.35-1.55	6.0-20.0	0.04-0.09	0.0-2.9	0.0-0.5
523880:									
Jefferson-----	0-7	43	39	10-25	1.30-1.50	2.0-6.0	0.10-0.16	0.0-2.9	0.5-5.0
	7-56	38	36	18-34	1.30-1.65	2.0-6.0	0.10-0.16	0.0-2.9	0.0-0.5
	56-60	67	15	15-30	1.30-1.65	2.0-6.0	0.08-0.14	0.0-2.9	0.0-0.5
Varilla-----	0-7	68	20	3-20	1.00-1.40	2.0-6.0	0.10-0.13	0.0-2.9	1.0-3.0
	7-44	66	19	3-20	1.45-1.65	2.0-6.0	0.05-0.10	0.0-2.9	0.0-0.5
	44-60	66	19	3-20	1.45-1.65	2.0-20.0	0.01-0.05	0.0-2.9	0.0-0.5
Shelocta-----	0-3	43	40	10-25	1.15-1.30	0.6-2.0	0.16-0.22	0.0-2.9	0.5-5.0
	3-50	20	50	18-34	1.30-1.55	0.6-2.0	0.10-0.20	0.0-2.9	0.0-0.5
	50-60				---	---	---	---	---
523895:									
Ramsey-----	0-2	44	40	8-25	1.25-1.50	6.0-20.0	0.09-0.12	0.0-2.9	0.5-2.0
	2-18	43	40	8-25	1.20-1.40	6.0-20.0	0.09-0.12	0.0-2.9	0.0-0.5
	18-25				---	0.0-0.2	---	---	---
2439088:									
Bethesda, unstable fill--	0-2	23-52	28-50	7-27	1.40-1.55	0.6-2.0	0.10-0.16	0.0-2.9	0.0-0.5
	2-45	10-45	28-65	18-40	1.60-1.90	0.2-0.6	0.04-0.10	0.0-2.9	0.0-0.5
	45-60	10-52	28-80	7-40	1.60-1.90	0.2-0.6	0.04-0.10	0.0-2.9	0.0-0.5
2439089:									
Gilpin-----	0-6	3-48	40-85	12-27	1.20-1.40	0.6-2.0	0.12-0.18	0.0-2.9	0.5-4.0
	6-21	15-52	28-65	18-35	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.3-1.0
	21-25	10-52	28-70	18-40	1.20-1.50	0.6-2.0	0.12-0.16	0.0-2.9	0.0-0.5
	25-35				---	0.0-0.0	---	---	---
2439090:									
Gilpin-----	0-6	3-48	40-85	12-27	1.20-1.40	0.6-2.0	0.12-0.18	0.0-2.9	0.5-4.0
	6-21	15-52	28-65	18-35	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.3-1.0
	21-25	10-52	28-70	18-40	1.20-1.50	0.6-2.0	0.12-0.16	0.0-2.9	0.0-0.5
	25-35				---	0.0-0.0	---	---	---

Table 14.—Physical Soil Properties—Continued

Map unit symbol and soil name	Depth	Sand	Silt	Clay	Moist bulk density	Permeability (Ksat)	Available water capacity	Shrink- swell potential	Organic matter
	In	Pct	Pct	Pct	g/cc	In/hr	In/in	Pct	Pct
2439091:									
Gilpin-----	0-6	3-48	40-85	12-27	1.20-1.40	0.6-2.0	0.12-0.18	0.0-2.9	0.5-4.0
	6-21	15-52	28-65	18-35	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.3-1.0
	21-25	10-52	28-70	18-40	1.20-1.50	0.6-2.0	0.12-0.16	0.0-2.9	0.0-0.5
	25-35				---	0.0-0.0	---	---	---
Petros-----	0-2	13-52	28-80	7-27	1.30-1.50	0.6-6.0	0.10-0.14	0.0-2.9	0.5-2.0
	2-8	10-32	45-65	18-35	1.30-1.55	0.6-6.0	0.04-0.09	0.0-2.9	0.3-1.3
	8-16	10-38	45-80	12-35	1.30-1.55	0.6-6.0	0.04-0.09	0.0-2.9	0.0-0.5
	16-26				---	0.0-0.0	---	---	---
2439092:									
Gilpin-----	0-6	3-48	40-85	12-27	1.20-1.40	0.6-2.0	0.12-0.18	0.0-2.9	0.5-4.0
	6-21	15-52	28-65	18-35	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.3-1.0
	21-25	10-52	28-70	18-40	1.20-1.50	0.6-2.0	0.12-0.16	0.0-2.9	0.0-0.5
	25-35				---	0.0-0.0	---	---	---
Petros-----	0-2	13-52	28-80	7-27	1.30-1.50	0.6-6.0	0.10-0.14	0.0-2.9	0.5-2.0
	2-8	10-32	45-65	18-35	1.30-1.55	0.6-6.0	0.04-0.09	0.0-2.9	0.3-1.3
	8-16	10-38	45-80	12-35	1.30-1.55	0.6-6.0	0.04-0.09	0.0-2.9	0.0-0.5
	16-26				---	0.0-0.0	---	---	---
2439093:									
Gilpin-----	0-6	3-48	40-85	12-27	1.20-1.40	0.6-2.0	0.12-0.18	0.0-2.9	0.5-4.0
	6-21	15-52	28-65	18-35	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.3-1.0
	21-25	10-52	28-70	18-40	1.20-1.50	0.6-2.0	0.12-0.16	0.0-2.9	0.0-0.5
	25-35				---	0.0-0.0	---	---	---
Bouldin-----	0-2	23-52	28-50	7-27	1.35-1.50	2.0-6.0	0.06-0.10	0.0-2.9	1.0-3.0
	2-17	23-52	28-50	7-27	1.35-1.50	2.0-6.0	0.06-0.10	0.0-2.9	0.5-2.0
	17-80	20-52	28-50	7-35	1.40-1.55	2.0-6.0	0.06-0.10	0.0-2.9	0.0-0.5
Petros-----	0-2	13-52	28-80	7-27	1.30-1.50	0.6-6.0	0.10-0.14	0.0-2.9	0.5-2.0
	2-8	10-32	45-65	18-35	1.30-1.55	0.6-6.0	0.04-0.09	0.0-2.9	0.3-1.3
	8-16	10-38	45-80	12-35	1.30-1.55	0.6-6.0	0.04-0.09	0.0-2.9	0.0-0.5
	16-26				---	0.0-0.0	---	---	---
2439098:									
Lily-----	0-3	23-52	28-50	7-27	1.20-1.40	0.6-6.0	0.13-0.18	0.0-2.9	0.5-4.0
	3-30	20-52	20-50	18-35	1.25-1.35	2.0-6.0	0.12-0.18	0.0-2.9	0.0-0.5
	30-37				---	0.0-0.0	---	---	---
2439099:									
Lily-----	0-3	23-52	28-50	7-27	1.20-1.40	0.6-6.0	0.13-0.18	0.0-2.9	0.5-4.0
	3-30	20-52	20-50	18-35	1.25-1.35	2.0-6.0	0.12-0.18	0.0-2.9	0.0-0.5
	30-37				---	0.0-0.0	---	---	---
2439100:									
Lily-----	0-3	23-52	28-50	7-27	1.20-1.40	0.6-6.0	0.13-0.18	0.0-2.9	0.5-4.0
	3-30	20-52	20-50	18-35	1.25-1.35	2.0-6.0	0.12-0.18	0.0-2.9	0.0-0.5
	30-37				---	0.0-0.0	---	---	---

Table 14.—Physical Soil Properties—Continued

Map unit symbol and soil name	Depth	Sand	Silt	Clay	Moist bulk density	Permeability (Ksat)	Available water capacity	Shrink- swell potential	Organic matter
	In	Pct	Pct	Pct	g/cc	In/hr	In/in	Pct	Pct
2439100:									
Gilpin-----	0-6	3-48	40-85	12-27	1.20-1.40	0.6-2.0	0.12-0.18	0.0-2.9	0.5-4.0
	6-21	15-52	28-65	18-35	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.3-1.0
	21-25	10-52	28-70	18-40	1.20-1.50	0.6-2.0	0.12-0.16	0.0-2.9	0.0-0.5
	25-35				---	0.0-0.0	---	---	---
2439101:									
Lily-----	0-3	23-52	28-50	7-27	1.20-1.40	0.6-6.0	0.13-0.18	0.0-2.9	0.5-4.0
	3-30	20-52	20-50	18-35	1.25-1.35	2.0-6.0	0.12-0.18	0.0-2.9	0.0-0.5
	30-37				---	0.0-0.0	---	---	---
Gilpin-----	0-6	3-48	40-85	12-27	1.20-1.40	0.6-2.0	0.12-0.18	0.0-2.9	0.5-4.0
	6-21	15-52	28-65	18-35	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.3-1.0
	21-25	10-52	28-70	18-40	1.20-1.50	0.6-2.0	0.12-0.16	0.0-2.9	0.0-0.5
	25-35				---	0.0-0.0	---	---	---
2439102:									
Lily-----	0-3	23-52	28-50	7-27	1.20-1.40	0.6-6.0	0.13-0.18	0.0-2.9	0.5-4.0
	3-30	20-52	20-50	18-35	1.25-1.35	2.0-6.0	0.12-0.18	0.0-2.9	0.0-0.5
	30-37				---	0.0-0.0	---	---	---
Gilpin-----	0-6	3-48	40-85	12-27	1.20-1.40	0.6-2.0	0.12-0.18	0.0-2.9	0.5-4.0
	6-21	15-52	28-65	18-35	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.3-1.0
	21-25	10-52	28-70	18-40	1.20-1.50	0.6-2.0	0.12-0.16	0.0-2.9	0.0-0.5
	25-35				---	0.0-0.0	---	---	---
2439103:									
Lily-----	0-3	23-52	28-50	7-27	1.20-1.40	0.6-6.0	0.13-0.18	0.0-2.9	0.5-4.0
	3-30	20-52	20-50	18-35	1.25-1.35	2.0-6.0	0.12-0.18	0.0-2.9	0.0-0.5
	30-37				---	0.0-0.0	---	---	---
Ramsey-----	0-4	25-52	28-50	8-25	1.25-1.50	6.0-20.0	0.09-0.12	0.0-2.9	0.5-2.0
	4-10	25-80	5-50	8-25	1.20-1.40	6.0-20.0	0.09-0.12	0.0-2.9	0.0-0.5
	10-16	25-80	5-50	8-25	1.30-1.60	2.0-6.0	0.09-0.15	0.0-2.9	0.0-0.5
	16-18				---	0.0-0.2	---	---	---
2439104:									
Lily-----	0-3	23-52	28-50	7-27	1.20-1.40	0.6-6.0	0.13-0.18	0.0-2.9	0.5-4.0
	3-30	20-52	20-50	18-35	1.25-1.35	2.0-6.0	0.12-0.18	0.0-2.9	0.0-0.5
	30-37				---	0.0-0.0	---	---	---
Ramsey-----	0-4	25-52	28-50	8-25	1.25-1.50	6.0-20.0	0.09-0.12	0.0-2.9	0.5-2.0
	4-10	25-80	5-50	8-25	1.20-1.40	6.0-20.0	0.09-0.12	0.0-2.9	0.0-0.5
	10-16	25-80	5-50	8-25	1.30-1.60	2.0-6.0	0.09-0.15	0.0-2.9	0.0-0.5
	16-18				---	0.0-0.2	---	---	---
2439105:									
Lily-----	0-3	23-52	28-50	7-27	1.20-1.40	0.6-6.0	0.13-0.18	0.0-2.9	0.5-4.0
	3-30	20-52	20-50	18-35	1.25-1.35	2.0-6.0	0.12-0.18	0.0-2.9	0.0-0.5
	30-37				---	0.0-0.0	---	---	---

Table 14.—Physical Soil Properties—Continued

Map unit symbol and soil name	Depth	Sand	Silt	Clay	Moist bulk density	Permeability (Ksat)	Available water capacity	Shrink- swell potential	Organic matter
	In	Pct	Pct	Pct	g/cc	In/hr	In/in	Pct	Pct
2439105: Ramsey-----	0-4	25-52	28-50	8-25	1.25-1.50	6.0-20.0	0.09-0.12	0.0-2.9	0.5-2.0
	4-10	25-80	5-50	8-25	1.20-1.40	6.0-20.0	0.09-0.12	0.0-2.9	0.0-0.5
	10-16	25-80	5-50	8-25	1.30-1.60	2.0-6.0	0.09-0.15	0.0-2.9	0.0-0.5
	16-18				---	0.0-0.2	---	---	---
2439107: Lonewood-----	0-8	24-52	50-73	12-27	1.30-1.40	0.6-2.0	0.18-0.20	0.0-2.9	1.0-3.0
	8-28	5-52	28-65	18-35	1.40-1.55	0.6-2.0	0.14-0.17	0.0-2.9	0.0-0.5
	28-55	5-45	15-65	27-40	1.40-1.55	0.6-2.0	0.14-0.17	0.0-2.9	0.0-0.5
	55-65				---	0.0-0.0	---	---	---
2439108: Pope-----	0-8	5-52	28-70	7-27	1.20-1.40	0.6-2.0	0.14-0.23	0.0-2.9	1.0-4.0
	8-43	15-80	5-80	5-27	1.30-1.60	0.6-6.0	0.10-0.18	0.0-2.9	0.0-0.5
	43-60	22-80	5-50	5-20	1.30-1.60	0.6-6.0	0.10-0.18	0.0-2.9	0.0-0.5
Philo-----	0-6	5-52	28-80	7-27	1.20-1.40	0.6-2.0	0.14-0.23	0.0-2.9	1.0-4.0
	6-36	5-80	5-80	5-27	1.20-1.40	0.6-2.0	0.10-0.20	0.0-2.9	0.0-0.5
	36-60	45-80	5-50	5-18	1.20-1.40	2.0-6.0	0.06-0.10	0.0-2.9	0.0-0.5
2439114: Shelocta-----	0-10	13-52	28-80	7-27	1.15-1.30	0.6-2.0	0.16-0.22	0.0-2.9	0.5-5.0
	10-65	5-30	40-75	18-40	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.0-0.5
	65-75				---	0.0-0.0	---	---	---
2439115: Shelocta-----	0-10	13-52	28-80	7-27	1.15-1.30	0.6-2.0	0.16-0.22	0.0-2.9	0.5-5.0
	10-65	5-30	40-75	18-40	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.0-0.5
	65-75				---	0.0-0.0	---	---	---
2439116: Shelocta-----	0-10	13-52	28-80	7-27	1.15-1.30	0.6-2.0	0.16-0.22	0.0-2.9	0.5-5.0
	10-65	5-30	40-75	18-40	1.40-1.60	0.6-2.0	0.12-0.18	0.0-2.9	0.0-0.5
	65-75				---	0.0-0.0	---	---	---
2439118: Wernock-----	0-12	5-32	50-80	12-27	1.20-1.40	0.6-2.0	0.19-0.23	0.0-2.9	0.5-4.0
	12-27	3-15	50-65	18-40	1.30-1.50	0.6-2.0	0.18-0.22	0.0-2.9	0.0-0.5
	27-35	3-15	50-65	27-40	1.30-1.50	0.6-2.0	0.18-0.22	0.0-2.9	0.0-0.5
	35-45				---	0.0-0.0	---	---	---
2439119: Wernock-----	0-12	5-32	50-80	12-27	1.20-1.40	0.6-2.0	0.19-0.23	0.0-2.9	0.5-4.0
	12-27	3-15	50-65	18-40	1.30-1.50	0.6-2.0	0.18-0.22	0.0-2.9	0.0-0.5
	27-35	3-15	50-65	27-40	1.30-1.50	0.6-2.0	0.18-0.22	0.0-2.9	0.0-0.5
	35-45				---	0.0-0.0	---	---	---

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 15.—Erosion Properties

(Entries under "Erosion factors" apply to the entire profile)

Map unit symbol and soil name	Depth (inches)	Erosion factors		
		Kw	Kf	T
523861:				
Ealy-----	0-10	.32	.32	5
	10-60	.32	.32	
Craigsville-----	0-3	.20	.24	3
	3-21	.17	.28	
	21-60	.17	.28	
523880:				
Jefferson-----	0-7	.17	.28	5
	7-56	.17	.24	
	56-60	.17	.24	
Varilla-----	0-7	.10	.28	3
	7-44	.10	.24	
	44-60	.10	.20	
Shelocta-----	0-3	.32	.32	4
	3-50	.28	.32	
	50-60	---	---	
523895:				
Ramsey-----	0-2	.20	.20	1
	2-18	.17	.20	
	18-25	---	---	
Rock outcrop.				
523909.				
Water				
2439088:				
Bethesda, unstable fill--	0-2	.28	.49	5
	2-45	.32	.64	
	45-60	.32	.64	
Mines pit, unstable fill.				
2439089:				
Gilpin-----	0-6	.32	.32	3
	6-21	.28	.28	
	21-25	.24	.49	
	25-35	---	---	
2439090:				
Gilpin-----	0-6	.32	.32	3
	6-21	.28	.28	
	21-25	.24	.49	
	25-35	---	---	
2439091:				
Gilpin-----	0-6	.32	.32	3
	6-21	.28	.28	
	21-25	.24	.49	
	25-35	---	---	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 15.-Erosion Properties-Continued

Map unit symbol and soil name	Depth (inches)	Erosion factors		
		Kw	Kf	T
2439091:				
Petros-----	0-2	.20	.28	2
	2-8	.15	.24	
	8-16	.15	.24	
	16-26	---	---	
2439092:				
Gilpin-----	0-6	.32	.32	3
	6-21	.28	.28	
	21-25	.24	.49	
	25-35	---	---	
Petros-----	0-2	.20	.28	2
	2-8	.15	.24	
	8-16	.15	.24	
	16-26	---	---	
2439093:				
Gilpin-----	0-6	.32	.32	3
	6-21	.28	.28	
	21-25	.24	.49	
	25-35	---	---	
Bouldin-----	0-2	.20	.28	2
	2-17	.20	.28	
	17-80	.20	.28	
Petros-----	0-2	.20	.28	2
	2-8	.15	.24	
	8-16	.15	.24	
	16-26	---	---	
2439098:				
Lily-----	0-3	.28	.37	2
	3-30	.28	.28	
	30-37	---	---	
2439099:				
Lily-----	0-3	.28	.37	2
	3-30	.28	.28	
	30-37	---	---	
2439100:				
Lily-----	0-3	.28	.37	2
	3-30	.28	.28	
	30-37	---	---	
Gilpin-----	0-6	.32	.32	3
	6-21	.28	.28	
	21-25	.24	.49	
	25-35	---	---	
2439101:				
Lily-----	0-3	.28	.37	2
	3-30	.28	.28	
	30-37	---	---	
Gilpin-----	0-6	.32	.32	3
	6-21	.28	.28	
	21-25	.24	.49	
	25-35	---	---	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 15.—Erosion Properties—Continued

Map unit symbol and soil name	Depth (inches)	Erosion factors		
		Kw	Kf	T
2439102:				
Lily-----	0-3	.28	.37	2
	3-30	.28	.28	
	30-37	---	---	
Gilpin-----	0-6	.32	.32	3
	6-21	.28	.28	
	21-25	.24	.49	
	25-35	---	---	
2439103:				
Lily-----	0-3	.28	.37	2
	3-30	.28	.28	
	30-37	---	---	
Ramsey-----	0-4	.20	.20	1
	4-10	.17	.20	
	10-16	.17	.20	
	16-18	---	---	
2439104:				
Lily-----	0-3	.28	.37	2
	3-30	.28	.28	
	30-37	---	---	
Ramsey-----	0-4	.20	.20	1
	4-10	.17	.20	
	10-16	.17	.20	
	16-18	---	---	
2439105:				
Lily-----	0-3	.28	.37	2
	3-30	.28	.28	
	30-37	---	---	
Ramsey-----	0-4	.20	.20	1
	4-10	.17	.20	
	10-16	.17	.20	
	16-18	---	---	
2439107:				
Lonewood-----	0-8	.37	.37	4
	8-28	.32	.32	
	28-55	.32	.32	
	55-65	---	---	
2439108:				
Pope-----	0-8	.37	.37	4
	8-43	.28	.28	
	43-60	.28	.20	
Philo-----	0-6	.37	.37	5
	6-36	.32	.32	
	36-60	.24	.28	
2439114:				
Shelocta-----	0-10	.32	.32	5
	10-65	.28	.28	
	65-75	---	---	



# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 15.—Erosion Properties—Continued

Map unit symbol and soil name	Depth (inches)	Erosion factors		
		Kw	Kf	T
2439115: Shelocta-----	0-10	.32	.32	5
	10-65	.28	.28	
	65-75	---	---	
2439116: Shelocta-----	0-10	.32	.32	5
	10-65	.28	.28	
	65-75	---	---	
2439117. Water				
2439118: Wernock-----	0-12	.37	.37	3
	12-27	.32	.32	
	27-35	.32	.32	
	35-45	---	---	
2439119: Wernock-----	0-12	.37	.37	3
	12-27	.32	.32	
	27-35	.32	.32	
	35-45	---	---	

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 16.—Total Soil Carbon

(This table displays soil organic carbon (SOC) and soil inorganic carbon (SIC) in kilograms per square meter to a depth of 2 meters or to the representative top depth of any kind of bedrock or any cemented soil horizon. SOC and SIC are reported on a volumetric whole soil basis, corrected for representative rock fragments indicated in the database. SOC is converted from horizon soil organic matter of the fraction of the soil less than 2 mm in diameter. If soil organic matter indicated in the database is NULL, SOC is assumed to be zero. SIC is converted from horizon calcium carbonate content fraction of the soil less than 2 mm in diameter. If horizon calcium carbonate indicated in the database is NULL, SIC is assumed to be zero. A weighted average of all horizons is used in the calculations. Only major components of a map unit are displayed in this table)

Map unit symbol, component name, and component percent	SOC	SIC
	kg/m2	kg/m2
523861:		
Ealy (60%)-----	12	0
Craigsville (30%)-----	2	0
523880:		
Jefferson (50%)-----	4	0
Varilla (20%)-----	4	0
Shelocta (15%)-----	3	0
523895:		
Ramsey (70%)-----	1	0
Rock outcrop (20%)-----	0	0
523909:		
Water (100%)-----	0	0
2439088:		
Bethesda, unstable fill (75%)-----	1	0
Mines pit, unstable fill (20%)-----	0	0
2439089:		
Gilpin (90%)-----	5	0
2439090:		
Gilpin (90%)-----	5	0
2439091:		
Gilpin (55%)-----	5	0
Petros (35%)-----	1	0
2439092:		
Gilpin (65%)-----	5	0
Petros (25%)-----	1	0

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 16.—Total Soil Carbon—Continued

Map unit symbol, component name, and component percent	SOC	SIC
	kg/m2	kg/m2
2439093:		
Gilpin (35%)-----	5	0
Bouldin (30%)-----	4	0
Petros (25%)-----	1	0
2439098:		
Lily (85%)-----	3	0
2439099:		
Lily (85%)-----	3	0
2439100:		
Lily (65%)-----	3	0
Gilpin (30%)-----	5	0
2439101:		
Lily (60%)-----	3	0
Gilpin (35%)-----	5	0
2439102:		
Lily (55%)-----	3	0
Gilpin (35%)-----	5	0
2439103:		
Lily (60%)-----	3	0
Ramsey (30%)-----	2	0
2439104:		
Lily (55%)-----	3	0
Ramsey (40%)-----	2	0
2439105:		
Lily (50%)-----	3	0
Ramsey (40%)-----	2	0
2439107:		
Lonewood (85%)-----	6	0
2439108:		
Pope (50%)-----	6	0
Philo (45%)-----	5	0
2439114:		
Shelocta (90%)-----	7	0
2439115:		
Shelocta (90%)-----	7	0
2439116:		
Shelocta (90%)-----	7	0

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 16.—Total Soil Carbon—Continued

Map unit symbol, component name, and component percent	SOC	SIC
	<u>kg/m2</u>	<u>kg/m2</u>
2439117: Water (100%)-----	0	0
2439118: Wernock (90%)-----	6	0
2439119: Wernock (90%)-----	6	0

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 17.—Chemical Soil Properties

(Absence of an entry indicates that data were not estimated)

Map unit symbol and soil name	Depth	Effective cation- exchange capacity	Soil reaction
	In	meq/100 g	pH
523861:			
Ealy-----	0-10	2.1-8.3	4.5-5.5
	10-60	1.7-6.1	4.5-5.5
Craigsville-----	0-3	2.1-7.5	4.5-5.5
	3-21	0.7-4.5	4.5-5.5
	21-60	0.7-3.6	4.5-5.5
523880:			
Jefferson-----	0-7	---	4.5-5.5
	7-56	---	4.5-5.5
	56-60	---	4.5-5.5
Varilla-----	0-7	1.0-12.1	3.6-6.5
	7-44	0.3-5.3	3.6-5.5
	44-60	0.3-5.3	3.6-5.5
Shelocta-----	0-3	---	4.5-5.5
	3-50	---	4.5-5.5
	50-60	---	---
523895:			
Ramsey-----	0-2	2.2-8.8	4.5-5.5
	2-18	0.8-6.0	4.5-5.5
	18-25	---	---
2439088:			
Bethesda, unstable fill-----	0-2	1.9-13.4	3.6-5.5
	2-45	5.7-21.0	3.6-5.5
	45-60	1.9-21.0	3.6-5.5
2439089:			
Gilpin-----	0-6	2.8-9.1	3.6-5.5
	6-21	5.3-13.3	3.6-5.5
	21-25	5.7-21.0	3.6-5.5
	25-35	---	---
2439090:			
Gilpin-----	0-6	2.8-9.1	3.6-5.5
	6-21	5.3-13.3	3.6-5.5
	21-25	5.7-21.0	3.6-5.5
	25-35	---	---
2439091:			
Gilpin-----	0-6	2.8-9.1	3.6-5.5
	6-21	5.3-13.3	3.6-5.5
	21-25	5.7-21.0	3.6-5.5
	25-35	---	---
Petros-----	0-2	1.2-5.3	4.5-5.5
	2-8	3.3-7.2	4.5-5.5
	8-16	2.3-8.4	4.5-5.5
	16-26	---	---

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 17.—Chemical Soil Properties—Continued

Map unit symbol and soil name	Depth	Effective cation- exchange capacity	Soil reaction
	In	meq/100 g	pH
2439092:			
Gilpin-----	0-6	2.8-9.1	3.6-5.5
	6-21	5.3-13.3	3.6-5.5
	21-25	5.7-21.0	3.6-5.5
	25-35	---	---
Petros-----	0-2	1.2-5.3	4.5-5.5
	2-8	3.3-7.2	4.5-5.5
	8-16	2.3-8.4	4.5-5.5
	16-26	---	---
2439093:			
Gilpin-----	0-6	2.8-9.1	3.6-5.5
	6-21	5.3-13.3	3.6-5.5
	21-25	5.7-21.0	3.6-5.5
	25-35	---	---
Bouldin-----	0-2	1.0-3.8	4.5-5.5
	2-17	1.0-3.8	4.5-5.5
	17-80	1.0-4.7	4.5-5.5
Petros-----	0-2	1.2-5.3	4.5-5.5
	2-8	3.3-7.2	4.5-5.5
	8-16	2.3-8.4	4.5-5.5
	16-26	---	---
2439098:			
Lily-----	0-3	1.1-5.3	3.6-5.5
	3-30	3.5-8.4	3.6-5.5
	30-37	---	---
2439099:			
Lily-----	0-3	1.1-5.3	3.6-5.5
	3-30	3.5-8.4	3.6-5.5
	30-37	---	---
2439100:			
Lily-----	0-3	1.1-5.3	3.6-5.5
	3-30	3.5-8.4	3.6-5.5
	30-37	---	---
Gilpin-----	0-6	2.8-9.1	3.6-5.5
	6-21	5.3-13.3	3.6-5.5
	21-25	5.7-21.0	3.6-5.5
	25-35	---	---
2439101:			
Lily-----	0-3	1.1-5.3	3.6-5.5
	3-30	3.5-8.4	3.6-5.5
	30-37	---	---
Gilpin-----	0-6	2.8-9.1	3.6-5.5
	6-21	5.3-13.3	3.6-5.5
	21-25	5.7-21.0	3.6-5.5
	25-35	---	---

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 17.—Chemical Soil Properties—Continued

Map unit symbol and soil name	Depth	Effective cation- exchange capacity	Soil reaction
	In	meq/100 g	pH
2439102:			
Lily-----	0-3	1.1-5.3	3.6-5.5
	3-30	3.5-8.4	3.6-5.5
	30-37	---	---
Gilpin-----	0-6	2.8-9.1	3.6-5.5
	6-21	5.3-13.3	3.6-5.5
	21-25	5.7-21.0	3.6-5.5
	25-35	---	---
2439103:			
Lily-----	0-3	1.1-5.3	3.6-5.5
	3-30	3.5-8.4	3.6-5.5
	30-37	---	---
Ramsey-----	0-4	1.0-3.6	4.5-6.0
	4-10	0.7-3.6	4.5-6.0
	10-16	0.7-3.6	4.5-6.0
	16-18	---	---
2439104:			
Lily-----	0-3	1.1-5.3	3.6-5.5
	3-30	3.5-8.4	3.6-5.5
	30-37	---	---
Ramsey-----	0-4	1.0-3.6	4.5-6.0
	4-10	0.7-3.6	4.5-6.0
	10-16	0.7-3.6	4.5-6.0
	16-18	---	---
2439105:			
Lily-----	0-3	1.1-5.3	3.6-5.5
	3-30	3.5-8.4	3.6-5.5
	30-37	---	---
Ramsey-----	0-4	1.0-3.6	4.5-6.0
	4-10	0.7-3.6	4.5-6.0
	10-16	0.7-3.6	4.5-6.0
	16-18	---	---
2439107:			
Lonewood-----	0-8	2.0-5.1	4.5-5.5
	8-28	3.5-8.4	4.5-5.5
	28-55	5.3-9.7	4.5-5.5
	55-65	---	---
2439108:			
Pope-----	0-8	1.5-8.4	3.6-5.5
	8-43	1.3-13.4	3.6-5.5
	43-60	1.3-9.5	3.6-5.5
Philo-----	0-6	1.5-8.4	4.5-6.0
	6-36	1.3-13.4	4.5-6.0
	36-60	1.3-8.4	4.5-6.0
2439114:			
Shelocta-----	0-10	1.5-9.1	4.5-5.5
	10-65	5.7-21.0	4.5-5.5
	65-75	---	---

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 17.—Chemical Soil Properties—Continued

Map unit symbol and soil name	Depth	Effective cation- exchange capacity	Soil reaction
	In	meq/100 g	pH
2439115: Shelocta-----	0-10	1.5-9.1	4.5-5.5
	10-65	5.7-21.0	4.5-5.5
	65-75	---	---
2439116: Shelocta-----	0-10	1.5-9.1	4.5-5.5
	10-65	5.7-21.0	4.5-5.5
	65-75	---	---
2439118: Wernock-----	0-12	2.0-5.3	3.6-7.3
	12-27	3.5-9.7	3.6-6.0
	27-35	5.3-9.7	3.6-6.0
	35-45	---	---
2439119: Wernock-----	0-12	2.0-5.3	3.6-7.3
	12-27	3.5-9.7	3.6-6.0
	27-35	5.3-9.7	3.6-6.0
	35-45	---	---



Table 18.-Water Features

(See text for definitions of terms used in this table. Estimates of the frequency of ponding and flooding apply to the whole year rather than to individual months. Absence of an entry indicates that the feature is not a concern or that data were not estimated)

Map unit symbol and soil name	Hydro- logic group	Months	Water table		Surface water depth	Ponding		Flooding	
			Upper limit	Lower limit		Duration	Frequency	Duration	Frequency
			Ft	Ft	Ft				
523861: Ealy-----	B	January	5.5	>6.0	---	---	---	Very brief	Occasional
		February	5.5	>6.0	---	---	---	Very brief	Occasional
		March	5.5	>6.0	---	---	---	Very brief	Occasional
		December	5.5	>6.0	---	---	---	---	None
Craigsville-----	B	January	---	---	---	---	---	---	Rare
		February	---	---	---	---	---	---	Rare
		March	---	---	---	---	---	---	Rare
		April	---	---	---	---	---	---	Rare
		May	---	---	---	---	---	---	Rare
		November	---	---	---	---	---	---	Rare
		December	---	---	---	---	---	---	Rare
523880: Jefferson-----	B	Jan-Dec	---	---	---	---	None	---	None
Varilla-----		Jan-Dec	---	---	---	---	None	---	None
Shelocta-----	B	Jan-Dec	---	---	---	---	None	---	None
523895: Ramsey-----		Jan-Dec	---	---	---	---	None	---	None
Rock outcrop.									
523909. Water									
2439088: Bethesda, unstable fill--	C	Jan-Dec	---	---	---	---	None	---	None
Mines pit, unstable fill.									

Table 18.-Water Features-Continued

Map unit symbol and soil name	Hydro- logic group	Months	Water table		Ponding			Flooding	
			Upper limit	Lower limit	Surface water depth	Duration	Frequency	Duration	Frequency
			<u>Ft</u>	<u>Ft</u>	<u>Ft</u>				
2439089: Gilpin-----	C	Jan-Dec	---	---	---	---	None	---	None
2439090: Gilpin-----	C	Jan-Dec	---	---	---	---	None	---	None
2439091: Gilpin-----	C	Jan-Dec	---	---	---	---	None	---	None
Petros-----	D	Jan-Dec	---	---	---	---	None	---	None
2439092: Gilpin-----	C	Jan-Dec	---	---	---	---	None	---	None
Petros-----	D	Jan-Dec	---	---	---	---	None	---	None
2439093: Gilpin-----	C	Jan-Dec	---	---	---	---	None	---	None
Bouldin-----	B	Jan-Dec	---	---	---	---	None	---	None
Petros-----	D	Jan-Dec	---	---	---	---	None	---	None
2439098: Lily-----	B	Jan-Dec	---	---	---	---	None	---	None
2439099: Lily-----	B	Jan-Dec	---	---	---	---	None	---	None
2439100: Lily-----	B	Jan-Dec	---	---	---	---	None	---	None
Gilpin-----	C	Jan-Dec	---	---	---	---	None	---	None

Table 18.-Water Features-Continued

Map unit symbol and soil name	Hydro- logic group	Months	Water table		Surface water depth	Ponding		Flooding	
			Upper limit	Lower limit		Duration	Frequency	Duration	Frequency
			<u>Ft</u>	<u>Ft</u>	<u>Ft</u>				
2439101: Lily-----	B	Jan-Dec	---	---	---	---	None	---	None
Gilpin-----	C	Jan-Dec	---	---	---	---	None	---	None
2439102: Lily-----	B	Jan-Dec	---	---	---	---	None	---	None
Gilpin-----	C	Jan-Dec	---	---	---	---	None	---	None
2439103: Lily-----	B	Jan-Dec	---	---	---	---	None	---	None
Ramsey-----	D	Jan-Dec	---	---	---	---	None	---	None
2439104: Lily-----	B	Jan-Dec	---	---	---	---	None	---	None
Ramsey-----	D	Jan-Dec	---	---	---	---	None	---	None
2439105: Lily-----	B	Jan-Dec	---	---	---	---	None	---	None
Ramsey-----	D	Jan-Dec	---	---	---	---	None	---	None
2439107: Lonewood-----	B	Jan-Dec	---	---	---	---	None	---	None
2439108: Pope-----	B	January	5.5	>6.0	---	---	None	Brief	Frequent
		February	5.5	>6.0	---	---	None	Brief	Frequent
		March	5.5	>6.0	---	---	None	Brief	Frequent
		April	5.5	>6.0	---	---	None	Brief	Frequent
		December	5.5	>6.0	---	---	None	Brief	Frequent

Table 18.-Water Features-Continued

Map unit symbol and soil name	Hydro- logic group	Months	Water table		Surface water depth	Ponding		Flooding	
			Upper limit	Lower limit		Duration	Frequency	Duration	Frequency
			<u>Ft</u>	<u>Ft</u>	<u>Ft</u>				
2439108: Philo-----	B	January	2.3	>6.0	---	---	None	Brief	Frequent
		February	2.3	>6.0	---	---	None	Brief	Frequent
		March	2.3	>6.0	---	---	None	Brief	Frequent
		April	2.3	>6.0	---	---	None	Brief	Frequent
		December	2.3	>6.0	---	---	None	Brief	Frequent
2439114: Shelocta-----	B	Jan-Dec	---	---	---	---	None	---	None
2439115: Shelocta-----	B	Jan-Dec	---	---	---	---	None	---	None
2439116: Shelocta-----	B	Jan-Dec	---	---	---	---	None	---	None
2439117: Water									
2439118: Wernock-----	B	Jan-Dec	---	---	---	---	None	---	None
2439119: Wernock-----	B	Jan-Dec	---	---	---	---	None	---	None

Table 19.-Soil Features

(See text for definitions of terms used in this table. Absence of an entry indicates that data were not estimated)

Map unit symbol and soil name	Restrictive layer				Potential for frost action	Risk of corrosion	
	Kind	Depth to top	Thickness	Hardness		Uncoated steel	Concrete
		In	In				
523861: Ealy-----	---	---	---	---	None	Low	Moderate
Craigsville-----	---	---	---	---	None	Moderate	Moderate
523880: Jefferson-----	---	---	---	---	None	Moderate	High
Varilla-----	---	---	---	---	None	Low	High
Shelocta-----	Paralithic bedrock	48-71	---	---	None	Low	High
523895: Ramsey-----	Lithic bedrock	7-20	---	Indurated	None	Low	Moderate
Rock outcrop-----	Lithic bedrock	0-0	---	Indurated	None	---	---
523909. Water							
2439088: Bethesda, unstable fill-----	---	---	---	---	None	Moderate	High
Mines pit, unstable fill.							
2439089: Gilpin-----	Paralithic bedrock	20-40	4-20	Strongly cemented	None	Low	High
2439090: Gilpin-----	Paralithic bedrock	20-40	4-20	Strongly cemented	None	Low	High
2439091: Gilpin-----	Paralithic bedrock	20-40	4-20	Strongly cemented	None	Low	High
Petros-----	Paralithic bedrock	10-20	4-20	Strongly cemented	None	Low	Moderate

Table 19.—Soil Features—Continued

Map unit symbol and soil name	Restrictive layer				Potential for frost action	Risk of corrosion	
	Kind	Depth to top	Thickness	Hardness		Uncoated steel	Concrete
		In	In				
2439092: Gilpin-----	Paralithic bedrock	20-40	4-20	Strongly cemented	None	Low	High
Petros-----	Paralithic bedrock	10-20	4-20	Strongly cemented	None	Low	Moderate
2439093: Gilpin-----	Paralithic bedrock	20-40	4-20	Strongly cemented	None	Low	High
Bouldin-----	---	---	---	---	None	Low	Moderate
Petros-----	Paralithic bedrock	10-20	4-20	Strongly cemented	None	Low	Moderate
2439098: Lily-----	Lithic bedrock	20-40	4-10	Indurated	None	Moderate	High
2439099: Lily-----	Lithic bedrock	20-40	4-10	Indurated	None	Moderate	High
2439100: Lily-----	Lithic bedrock	20-40	4-10	Indurated	None	Moderate	High
Gilpin-----	Paralithic bedrock	20-40	4-20	Strongly cemented	None	Low	High
2439101: Lily-----	Lithic bedrock	20-40	4-10	Indurated	None	Moderate	High
Gilpin-----	Paralithic bedrock	20-40	4-20	Strongly cemented	None	Low	High
2439102: Lily-----	Lithic bedrock	20-40	4-10	Indurated	None	Moderate	High
Gilpin-----	Paralithic bedrock	20-40	4-20	Strongly cemented	None	Low	High
2439103: Lily-----	Lithic bedrock	20-40	4-10	Indurated	None	Moderate	High
Ramsey-----	Lithic bedrock	7-20	0-4	Indurated	None	Low	Moderate

Table 19.—Soil Features—Continued

Map unit symbol and soil name	Restrictive layer				Potential for frost action	Risk of corrosion	
	Kind	Depth to top	Thickness	Hardness		Uncoated steel	Concrete
		In	In				
2439104: Lily-----	Lithic bedrock	20-40	4-10	Indurated	None	Moderate	High
Ramsey-----	Lithic bedrock	7-20	0-4	Indurated	None	Low	Moderate
2439105: Lily-----	Lithic bedrock	20-40	4-10	Indurated	None	Moderate	High
Ramsey-----	Lithic bedrock	7-20	0-4	Indurated	None	Low	Moderate
2439107: Lonewood-----	Paralithic bedrock	40-72	4-20	Strongly cemented	None	Low	Moderate
2439108: Pope-----	---	---	---	---	None	Low	High
Philo-----	---	---	---	---	None	Low	High
2439114: Shelocta-----	---	---	---	---	None	Low	High
2439115: Shelocta-----	---	---	---	---	None	Low	High
2439116: Shelocta-----	---	---	---	---	None	Low	High
2439117. Water							
2439118: Wernock-----	Paralithic bedrock	30-40	4-20	Strongly cemented	None	Moderate	High
2439119: Wernock-----	Paralithic bedrock	30-40	4-20	Strongly cemented	None	Moderate	High

# Soil Survey of Obed Wild and Scenic River, Tennessee

Table 20.—Taxonomic Classification of the Soils


Soil name	Family or higher taxonomic class
Atkins-----	Fine-loamy, mixed, active, acid, mesic Fluvaquentic Endoaquepts
Bethesda-----	Loamy-skeletal, mixed, active, acid, mesic Typic Udorthents
Bouldin-----	Loamy-skeletal, siliceous, subactive, mesic Typic Paleudults
Craigsville-----	Loamy-skeletal, mixed, mesic Fluventic Dystrochrepts
Ealy-----	Coarse-loamy, siliceous, mesic Fluventic Dystrochrepts
Gilpin-----	Fine-loamy, mixed, active, mesic Typic Hapludults
Highsplint-----	Loamy-skeletal, mixed, active, mesic Typic Dystrudepts
Jefferson-----	Fine-loamy, siliceous, mesic Typic Hapludults
Lily-----	Fine-loamy, siliceous, semiactive, mesic Typic Hapludults
Lonewood-----	Fine-loamy, siliceous, semiactive, mesic Typic Hapludults
Petros-----	Loamy-skeletal, mixed, semiactive, mesic, shallow Typic Dystrudepts
Philo-----	Coarse-loamy, mixed, active, mesic Fluvaquentic Dystrudepts
Pope-----	Coarse-loamy, mixed, active, mesic Fluventic Dystrudepts
Ramsey-----	Loamy, siliceous, subactive, mesic Lithic Dystrudepts
Rowdy-----	Fine-loamy, mixed, semiactive, mesic Fluventic Dystrudepts
Sequoia-----	Fine, mixed, semiactive, mesic Typic Hapludults
Shelocta-----	Fine-loamy, mixed, active, mesic Typic Hapludults
Varilla-----	Loamy-skeletal, siliceous, mesic Typic Dystrochrepts
Wernock-----	Fine-silty, mixed, semiactive, mesic Typic Hapludults







# NRCS Accessibility Statement

---

The Natural Resources Conservation Service (NRCS) is committed to making its information accessible to all of its customers and employees. If you are experiencing accessibility issues and need assistance, please contact our Helpdesk by phone at 1-800-457-3642 or by e-mail at [ServiceDesk-FTC@ftc.usda.gov](mailto:ServiceDesk-FTC@ftc.usda.gov). For assistance with publications that include maps, graphs, or similar forms of information, you may also wish to contact our State or local office. You can locate the correct office and phone number at <http://offices.sc.egov.usda.gov/locator/app>.





-  Park Boundary (2012)
-  Actual Map Extent
-  USGS 24k Quadrangle

**Map Sheet Number**  
24k Quadrangle Name



Scale 1:75,000  
1 Inch = 1.91 Kilometers  
0 1 2 3 4 Kilometers  
0 1 2 3 4 Miles  
1 Inch = 1.18 Miles

U.S. DEPARTMENT OF  
AGRICULTURE

NATURAL RESOURCES  
CONSERVATION SERVICE

**MAP UNIT LEGEND**  
**OBED WILD AND SCENIC RIVER**  
**TENNESSEE**

U.S. DEPARTMENT  
OF THE INTERIOR

NATIONAL PARK  
SERVICE

**SYMBOL**


**NAME**

523861	Ealy-Craigsville complex, 0 to 5 percent slopes, occasionally flooded
523880	Jefferson-Varilla-Shelocta complex, 20 to 60 percent slopes, very stony
523895	Ramsey-Rock outcrop complex, 20 to 50 percent slopes
523909	Water
2439088	Bethesda-Mines pit complex, 10 to 80 percent slopes
2439089	Gilpin silt loam, 5 to 12 percent slopes
2439090	Gilpin silt loam, 12 to 20 percent slopes
2439091	Gilpin-Petros complex, 20 to 35 percent slopes
2439092	Gilpin-Petros complex, 35 to 80 percent slopes
2439093	Gilpin-Bouldin-Petros complex, 25 to 80 percent slopes, very stony
2439098	Lily loam, 5 to 12 percent slopes
2439099	Lily loam, 12 to 20 percent slopes
2439100	Lily-Gilpin complex, 5 to 12 percent slopes
2439101	Lily-Gilpin complex, 12 to 20 percent slopes
2439102	Lily-Gilpin complex, 20 to 35 percent slopes
2439103	Lily-Ramsey complex, 5 to 12 percent slopes
2439104	Lily-Ramsey complex, 12 to 20 percent slopes
2439105	Lily-Ramsey complex, 20 to 35 percent slopes
2439107	Lonewood silt loam, 5 to 12 percent slopes
2439108	Pope-Philo complex, frequently flooded
2439114	Shelocta silt loam, 5 to 12 percent slopes
2439115	Shelocta silt loam, 12 to 20 percent slopes
2439116	Shelocta silt loam, 20 to 35 percent slopes
2439117	Water
2439118	Wernock silt loam, 2 to 5 percent slopes
2439119	Wernock silt loam, 5 to 12 percent slopes





UNITED STATES DEPARTMENT OF AGRICULTURE  
NATURAL RESOURCES CONSERVATION SERVICE

SOIL SURVEY OF OBED WILD & SCENIC RIVER, TENNESSEE  
PORTIONS OF FOX CREEK AND JONES KNOB QUADRANGLES  
SHEET NUMBER 1 OF 3



SCALE 1:24,000



Obed Wild & Scenic  
River, Tennessee

Sheet 1 of 3






UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

UNITED STATES DEPARTMENT OF AGRICULTURE  
NATURAL RESOURCES CONSERVATION SERVICE

SOIL SURVEY OF OBED WILD & SCENIC RIVER, TENNESSEE  
PORTIONS OF HEBBERTSBURG AND TWIN BRIDGES QUADRANGLES  
SHEET NUMBER 2 OF 3



This soil survey was compiled by the U.S. Department of Agriculture, Natural Resources Conservation Service, at the request of the Department of the Interior, National Park Service. Base maps are orthophotographs prepared by the U.S. Department of Agriculture, Farm Service Agency from 2006 - 2011 aerial photographs. A 2012 National Park Service boundary was used. Soil information was derived from USDA/NRCS Soil Survey Geographic (SSURGO) database for Obed Wild & Scenic River. Universal Transverse Mercator Zone 16 North, North American Datum of 1983 (NAD83).




Obed Wild & Scenic  
River, Tennessee  
Sheet 2 of 3

SCALE 1:24,000





This soil survey was compiled by the U.S. Department of Agriculture, Natural Resources Conservation Service, at the request of the Department of the Interior, National Park Service. Base maps are orthophotographs prepared by the U.S. Department of Agriculture, Farm Service Agency from 2006 - 2011 aerial photographs. A 2012 National Park Service boundary was used. Soil information was derived from USDA/NRCS Soil Survey Geographic (SSURGO) database for Obed Wild & Scenic River, Universal Transverse Mercator Zone 16 North, North American Datum of 1983 (NAD83).



SCALE 1:24,000

